

Provita Chicks Limited প্রভিটা চিকস্ লিমিটেড

Ref. No: PG/HO/Admin/06/16/258

Date: 13/07/2016

To

Cross World Power Ltd. H: NE (O) 06, R: 92, Gulshan-2, Dhaka-1212.

e-mail: info@cross-world.com

Kind Attention: Zahidur Rahman, (Engineer, Sales & Marketing).

Subject: Work order against quotation under Ref. CWPL-AM/1823/16F, dated 12/07/2016 for 250 KVA 3 Phase Heavy Duty Diesel Generating Sets.

Dear Sir.

With Ref. to your discussion as being held with the Chairman of Provita Group today the 13th July 2016 and came into a conclusion to supply the following generator at our project located in Noakhali, Provita Chicks Ltd. at Jahajmara.

With Ref. to your quotation as mentioned on the captioned subject to supply 250 KVA 3 Phase Heavy Duty Diesel Generating Sets.

Item	Description of Equipment	Quantity	Unit Price	Total Amount
No			(In GBP)	(In GBP)
1	TEMPEST Brand 250 KVA (Prime)			×,
	Rating Diesel Generator with Perkins	BIA B	W. W. Carlo	
	engine and Mecc-Alte Alternator.	2 Set	18,000.00	36,000.00
	Brand: Tempest Engine: Perkins- USA	I East	mula	
	Engine: Perkins- USA	LEOF	THELLE	
	Engine Model: 1506A-E88TAG3		*	
	Alternator: Mecc Alte, UK			
	Controller: Deepsea- UK			
	Shipment: Thames Port, UK	1	41	
	Shipment time: 10 weeks from L/c			
	opening.			*
2	Local Canopy for 250 KVA Genset	2 Set	Arranged by buyer	
3	Local Made trolley for generator	2 Set	Arranged by buyer	1.0
Total Amount in GBP (C & F Chittagong)				36,000.00
In Word: Thirty Six thousand GBP only.				

Con't. at page-2





Provita Chicks Limited প্রভিটা চিকস্ লিমিটেড

page-2

Mode of Payment:

100% payment of the order is to be made at sight though an irrevocable confirmed letter of credit to be established negotiated with the shipping documents in favor of Allam Marine Limited, Wyke Way, Melton, Hull, HU14 3BQ, England.

Additional Terms & Conditions:

- 1. No compensation shall be paid in case of any incident/ accident if occurred during installation.
- 2. You are to provide a certificate after satisfactory completion.
- 3.Installation Commissioning and testing of the genset would be completed within 3 (Three) working days from the date of delivery.

Standard Item:

- 1. Lead Acid battery 12/24 Volt as required.
- 2. Silencer Box.
- 3. Rubber anti Vibration Mountings.
- 4. Flexible Bellows.
- 5. Battery Charger.
- 6. Main Line 3 Pole Circuit Breaker.
- 7. Alternator Mounted Deep-Sea, UK Original Main Control Panel.
- 8. Fuel Tank for 10 hours operation.
- 9. Operation manual and keys as provided by the manufacturer.
- 10. 1st fill Lube oil, Radiator coolant will be provided by the supplier.

Replacement Warranty:

- a) 4000 running hour from the date of completion of commissioning.
- b) Backup is to be provided within 24 hours if a parts or the total body of generator becomes disorder that shall be replaced without condition.


Servicing:

4000 running hour servicing after commissioning without consumables like oil & air filter, lube oil etc.

1st Servicing:

1st servicing would be made after 250 hours running.

Con't. at page-3





Provita Chicks Limited প্রভিটা চিকস্ লিমিটেড

page-3

Installation:

Necessary cable and civil work will do as per requirement by the Provita Group.

Training:

Necessary training for operators and machineries will be provided free of charge at the time of Gen Set commissioning.

(Md. Habib Ullah)

AGM (Admin & HR & Company Secretary)

Copy To:

- 1. CFO, Head Office.
- 2. Sr. AGM (Factory), PFL.
- 3. AGM (Accounts), Head Office.
- 4. Sr. Manager (Finance), Noor-E-Madina.
- 5. Admin In charge, PCL.
- 6. Office File.
- 7. Master File.

Copy for Information:

- 1. Honorable Chairman.
- 2. Honorable Director & CEO.
- 3. Honorable Director Operation.

Enriched Formula

