



Provita Chicks Limited

প্রভিটা চিক্স লিমিটেড

Ref. No: PG/HO/Admin/06/16/259
Date: 13/07/2016

To
Cross World Power Ltd.
H: NE (O) 06, R: 92,
Gulshan-2, Dhaka-1212.
e-mail: info@cross-world.com

Kind Attention: **Zahidur Rahman, (Engineer, Sales & Marketing).**

Subject: Work order against quotation under Ref. CWPL-AM/1813/16F, dated 11/07/2016 for 250 KVA 3 Phase Heavy Duty Diesel Generating Sets.

Dear Sir,

With Ref. to your discussion as being held with the Chairman of Provita Group today the 13th July 2016 and came into a conclusion to supply the following generator at our project located in Noakhali, Provita Chicks Ltd. at Jahajmara.

With Ref. to your quotation as mentioned on the captioned subject to supply 250 KVA 3 Phase Heavy Duty Diesel Generating Sets.

Item No	Description of Equipment	Quantity	Unit Price (In TK.)	Total Amount (In TK.)
1	TEMPEST Brand 250 KVA (Prime) Rating Diesel Generator with Perkins engine and Mecc-Alte Alternator. Brand: Tempest Engine: Perkins- UK Engine Model: 1506A-E88TAG3 Alternator: Mecc Alte, UK Controller: Deepsea- UK Delivery time: 10 days after issuing the work order.	1 Set	24,00,000.00	24,00,000.00
2	Local Canopy for 250 KVA Genset			
3	Local Made trolley for generator	1 Set	Arranged by buyer	
Total Amount=				<u>24.00.000.00</u>
In Word: Twenty four lac taka only.				

Con't. at page-2



Provita Chicks Limited

প্রভিটা চিক্স লিমিটেড

page-2

Mode of Payment:

1. 50% of the total amount of Tk. 12,00,000/- (Tk. Twelve lac) only, is payable as an advance along with order.
2. Rest 50 % of total amount of Tk. 12,00,000/- (Tk. Twelve lac) only, is payable after installation and satisfactory running.

Additional Terms & Conditions:

1. No compensation shall be paid in case of any incident/ accident if occurred during installation.
2. You are to provide a certificate after satisfactory completion.
3. Installation Commissioning and testing of the genset would be completed within 3 (Three) working days from the date of delivery.

Standard Item:

1. Lead Acid battery 12/24 Volt as required.
2. Silencer Box.
3. Rubber anti Vibration Mountings.
4. Flexible Bellows.
5. Battery Charger.
6. Main Line 3 Pole Circuit Breaker.
7. Alternator Mounted Deep-Sea, UK Original Main Control Panel.
8. Fuel Tank for 10 hours operation.
9. Operation manual and keys as provided by the manufacturer.
10. 1st fill Lube oil, Radiator coolant will be provided by the supplier.

Replacement Warranty:

- a) 4000 running hour the date of completion of commissioning.
- b) Backup is to be provided within 24 hours if a parts or the total body of generator becomes disorder that shall be replaced without condition.

Servicing:

4000 running hour servicing after commissioning without consumables like oil & air filter, lube oil etc.

1st Servicing:

1st servicing would be made after 250 hours running.

Con't. at page-3

page-3

Installation:

Necessary cable and civil work will do as per requirement by the Provita Group.

Training:

Necessary training for operators and machineries will be provided free of charge at the time of Gen Set commissioning.


(Md. Habib Ullah)

AGM (Admin & HR & Company Secretary)

Copy To:

1. CFO, Head Office.
2. Sr. AGM (Factory), PFL.
3. AGM (Accounts), Head Office.
4. Sr. Manager (Finance), Noor-E-Madina.
5. Admin In charge, PCL.
6. Office File.
7. Master File.

Copy for Information:

1. Honorable Chairman.
2. Honorable Director & CEO.
3. Honorable Director Operation.

PROVITA
Enriched Formula

