

ADDITIONAL EXHAUST AND COOLING MATERIAL BQQ FOR SILVER LINE GROUP (FCAL)

3	Exhaust System:		Unit	Qty	Unit Rate	Total Rate	
3.1	Exhaust Silencer straight Pipe for the new piping route	MS Pipe bore 3", thickness 3-4mm	Feet(Approx)	3	625	1,875	
3.2	Exhaust Bends /Elbow	Long radius 90 deg L bow	Pcs	2	625	1,250	
3.3	Exhaust Socket	Threaded 3"dia MS Socket	Pcs	1	438	438	
3.4	Exhaust Heat Insulation	Insulation Of Pipe with Rockwool/Glasswool (25.4mm min thickness) along with 26SWG Aluminium sheet cladding.	Job	1	1,450	1,450	
3.5	Exhaust Fitting	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM with smooth finishing the edges	Job	1	1,500	1,500	
4	Cooling System:						
4.1	Radiator Ducting	As per layout with 20/22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth, Iron net mesh etc. Duct (WXH)ft- (2.9'X1.33')ft, Running Length, L- 30ft (Approx.).	Sq-ft (Approx.)	253.8	270	68,526	QTY. MAY VARY IF THE DUCT RUNNING LENGTH CHANGED.
4.2	Exhaust Heat Insulation	Insulation Of MS Sheet with Rockwool/Glasswool (25.4mm min thickness) along with 26SWG Aluminium sheet cladding.	Job	1	72,350	72,350	
4.3	Exhaust Fitting	All bracket , support must be made with MS angle, Flat Bar 50X50X 4, 5 & 6 MM with smooth finishing the edges.	Job	1	26,500	26,500	
4.4	Low Noise Industrial Axial Blower Fan with proper support & connection accessories.	Fan Dia- 18", 16000CFM, with SPL- 80dba @ 1 meter	Nos.	1	-	-	Clients will arrange
4.5	DG Replacement	1 Foot from its existing position	Job	1	3,000	3,000	
Total (BDT)						176,889	176,000

NOTE: REVISED LAYOUT MUST BE APPROVED BY CLIENT BEFORE FURTHER EXECUTION.
 SAMPLE WON'T TAKE ANY LIABILITY IF THE GEN SET GETS SHUT DOWN OR ANY KIND OF TROUBLE MADE BY THE REVISED AIR VENTILATION AS WELL AS THE DG POSITION ARRANGEMENTS.

28.11.16
 28.11.16
 28.11.16