



TRZ GARMENTS INDUSTRY LTD.

Gacha Road, Gacha, (Opposite side of Gazipur Technical School & College), Gazipur-1704, Bangladesh.

Tel. Head Office : 88-02- 8918481-2, 8919113, 8956188, Factory : 9293672. E-mail: info@trzgroup.com

Kind Attention: - Md. Sanwar Parvez
Sr. Engineer, Sales
Cross-world Power Ltd.
House 06, Road 92, Gulshan, Dhaka 1212, Bangladesh

Date: October 30, 2016

Sub: Work Order for the installing and commissioning of 1000 KVA generator along with synchronizing panel and existing 500 KVA generator.

Sir/Madam,

We are pleased to issue Work Order for supply and installation as per details appended below:

SL No	JOB DESCRIPTION	TECHNICAL DETAILS/ BRAND	UOM	QTY	UNIT SALE	TOTAL SALE
Electrical System:						
1	Power cable laying charge	Power Cable laying of 300 mm nyy cable 525 meter from 1000 KVA Generator to MCOS through Sync panel, 240 mm nyy cable 255 meter from 500 KVA Generator to MCOS through Sync panel, 185 mm bya earthing cable from copper bar to Gen & equipments.	Job	1	75,000	75,000
2	1000 KVA DG shifting Charge	Shifting of 1000 KVA DG from present location to new generator Room	Job	1	10,000	10,000
Exhaust System:						
3	Exhaust Heat Insulation	Insulation of exhaust (including silencer) with Rockwool/Glasswool (37mm thickness) & 2-3mm Aluminium sheet cladding.	Job	1	56,391	56,391
4	Exhaust Fitting	All bracket, support made with MS angle 50X50X5 mm,	Job	1	38,961	38,961
Commissioning Materials						
5	Radiator Coolant	Havoline Premix Coolant	Liter	160	198	31,680
6	Lube oil	SAE 15 W 40	Liter	160	433	69,280
7	Battery electrolyte	Specific gravity 1250	Liter	60	62	3,720
Dismantle of Existing 500 KVA DG						
8	Dismantle and shifting work	Dismantle, shifting 50 feet (approx.) and replacement on	Job	1	6,835	6,835
9	Dismantle and reconnection work	Dismantle and reconnection of all cable wiring	Job	1	11,620	11,620
10	Dismantle and reinstallation of Exhaust	Dismantle and reinstallation of existing exhaust system 6"	Job	1	40,000	40,000
11	Dismantle and reinstallation of Cooling	Dismantle and reinstallation of existing duct 130 sft	Job	1	35,000	35,000
Fuel Storage Tank Connections						
12	Fuel Pipe	Ø25.4mm (inner), Seamless Mild Steel Pipe; Elbow, Tee, Flange, Nut-bolt, Waher, Gasket, etc as required Welding Joint, leak testing, outside Red-oxide & Enamel Painted.	Meter	30	333	10,000
13	Fuel Pipe Plumbing works & Accessories	Accessory like fittings like ,L bow,T joint,I joint , Converter, etc for fuel pipe, plumbing to Engine & Fuel Tank loading point in the outside of Fuel tank room.	Job	1	20,000	20,000
14	Fuel/Water Separator	Flow Rate: 2400 l/hr Brand: Fleetguard/Racor/Separ Equ.	Pcs	1	123,333	123,333
15	ball valve	25.4 mm dia	Pcs	6	2,133	12,800
					Total	5,44,620

In Work: Taka Five Lac Forty Four Thousand Six Hundred Twenty Only

Terms & Conditions:

- Installation Time: As discussed with the management of TRZ Garments Ind. Ltd.
- Payment Mode: 100 % payment will be issued in advance in favor of Cross-world Power Ltd. with this work order.
- Above price is including vat and Tax.

You therefore requested to do the necessary immediately.
Please feel free to contact us for any further assistance.

For TRZ Garments Ind. Ltd.

Haroon Ar Rashid
Managing Director