

## Habibur Rahman

---

**From:** M Ali Tapan <tapanali@hotmail.com>  
**Sent:** Thursday, February 16, 2017 12:11 PM  
**To:** Habibur Rahman  
**Subject:** Re: BOQ prices with special discount for Shopnaloy 150 kVA Generator.

Dear Sir,

Sorry for delay reply. your quotation is accepted. pls work as soon as possible.

thanks  
Tapan

---

**From:** Habibur Rahman <[habib@cross-world.com](mailto:habib@cross-world.com)>  
**Sent:** Thursday, February 2, 2017 5:35 AM  
**To:** [tapanali@hotmail.com](mailto:tapanali@hotmail.com)  
**Cc:** [moshiur@cross-world.com](mailto:moshiur@cross-world.com); 'Rafi Vai'; [Moazzem@cross-world.com](mailto:Moazzem@cross-world.com)  
**Subject:** RE: BOQ prices with special discount for Shopnaloy 150 kVA Generator.

Dear Sir,

Refer to below mail, previously we provide a BOQ without Power Cable & Control Cable & you have approved with some discount, Thanks for that.

Now plz find the attached **Additional BOQ only** with Power Cables, Control cable, Earthing Cable & some additional Exhaust pipe works.

Please approve the additional works BOQ for further works process.

Sincerely,

**Md. Habibur Rahman** | **CROSS WORLD POWER LTD** | **Manager, Customer Relations** | House NE(O) 06, Road 92, Gulshan-2 Dhaka 1212, Bangladesh | Cell: +88 (02) 01755514711, p: +880 2 5881 1858, 989 1442 | f: +880 2 5881 5160  
| e: [habib@cross-world.com](mailto:habib@cross-world.com) | w: [www.cross-world.com](http://www.cross-world.com)



please consider the environment before printing this email

---

**From:** Habibur Rahman Javed [[mailto:habib@cross-world.com](mailto:mailto:habib@cross-world.com)]  
**Sent:** Tuesday, December 27, 2016 12:37 PM

**CROSS WORLD POWER LIMITED****REVISED ADDITIONAL BOQ OF 1X150kVA GENERATOR**

CLIENT - Mr. Topon

ADDRESS- Cox's Bazar

DATE- 02.02.2017

**GEN MODEL-****ENGINE MODEL-****ALTERNATOR MODEL-**

SL NO	JOB DESCRIPTION	TECHNICAL DETAILS/ BRAND	SCOPE OF SUPPLY	UOM	QTY	UNIT RATE	TOTAL RATE	REMARKS
1	<b>Electrical System:</b>							
1.1	Power Cable (35 °C Ambient on air )	1X1C 95rm NYY DG To ATS 1X1C 95rm NYY Mains To ATS 1X1C 95rm NYY ATS To Load		Meter (Approx.)	60 31 18	975 975 975	58,500 30,225 17,550	Qty. depends upon the panel position.
1.3	Control cable For Sensing	4 X 1.2 rm (40/0.19 mm) Flexible Cable		Meter	125	105	13,125	
2.4	Earthing Cable	1 X 25 rm BYA (Green ) from Earthing Copper bar to gen neutral & equipment & ATS.		Meter (Approx.)	25	255	6,375	Qty. depends upon the earth bar and panel position.
3.1	Exhaust Silencer straight Pipe	MS Pipe bore 4", thickness 3-4mm		Feet (Approx.)	20	875	17,500	As per client, Silencer pipe will extend up to roof top from EGL.
3.4	Exhaust Heat Insulation	Insulation Of Pipe with Rockwool/Glasswool (25.4mm min thickness) along with 26SWG Aluminium sheet cladding.		Job	1	4,500	4,500	
3.5	Exhasut Fitting	All bracket , support must be made with MS angle 50X50		Job	1	4,500	4,500	
				<b>Total (BDT):</b>			<b>152,275</b>	

\*\*\*All the necessary civil works will be done by client under the instruction of CWPL engineer.