

Purchase Order

March 20, 2017 WO # SZ/Thikana-2B/Proc/88 MPR # 12145

The Managing Director

Cross World Power Limited

House # 06, Road # 92, Gulshan-02, Dhaka-1212

Phone: 8811858, 8816528

Attn: Md. Sohel Uddin Bhuiyan

Manager, Sales & Marketing

Cell No: 01755514780

Sub: Work Order against supply & Installation of Generator Eshaust System at Simpletree Thikana 2B (Plot # 2B, Rd # 138, Gulshan-01, Dhaka-1212)

Dear Sir,

In accordance with above subject, subsequent quotation dated on March 19, 2017 & negotiation made with you regarding the subjected matter, we are pleased to issue the work order against supply & installation of Generator Exhaust System at Simpletree Thikana 2B (Plot # 2B, Rd # 138, Gulshan, Dhaka-1212) as per the following rate, specification, terms & conditions.

SL#	Name of Material & Specification	Unit	Qty	Unit Price (Tk.)	Amount (Tk.)
01	Royal Bolt: 10/12 no.	Pcs	10	31.50	315.00
02	Earthting Block / Equipotential Bar: Dimension L X W X D - 250mm X 30mm X 5mm with connection facility	Pcs	01	2,700.00	2,700.00
03	Exhaust Silencer straight Pipe: MS Pipe bore 200mm ,thickness 3-4mm	Feet (Appx)	18	1,123.20	20,217.58
04	Exhaust Bends /Elbow: Long radius 90 deg L bow bore 200mm	Pcs	03	1,497.60	4,492.80
05	Exhaust Flange: Welding neck flange 200 mm bore	Pcs	08	1,016.10	8,128.79
06	MS Pipe Converter: 152 mm to 200 mm	Pc	01	2,673.90	2,673.90

20-13-17

SPACEZERO LTD house 106 road 25 block a banani dhaka 1213 bangladesh telephone +88029887060 +88029 +88029887119 +88029887205 facsimile +88029842122

TIVE BUILDERS

		Total Amount :			109,367.91
13	Battery electrolyte: Specific gravity 1.250	Liter	20	58.50	1,170.00
12	Lube Oil: SAE 15 W 40	Liter	20	378.00	7,559.99
11	Radiator Coolant & DM Water Mix: Havoline Premix Coolant	Liter	20	225.00	4,500.00
10	Radiator Ducting: Duct W X H- 2.5' X 2.5', L- 12' As per layout with 20/22 SWG MS sheet,Angle bar, flat bar support, Canvas cloth etc	Sft	120	243.00	29,159.98
09	Exhaust Fitting: With MS angle 37 X 37 X 5 mm, flat bar, nut bolt, Royal Bolt etc.	Job	01	3,850.20	3,850.20
08	Exhaust Heat Insulation: Insulation with Rockwool/ Glasswool (37mm) and 26 SWG aluminium sheet clading	Job	01	4,813.20	4,813.20
07	Exhaust Silencer Box for 150 kVA: Residential type silencer box without insulation, Axial in incoming pipe dia 8" & axial outgoing pipe dia-8", sound level 48-50 dbA @ 3 m	Pcs	01	19,786.48	19,786.4 <mark>8</mark>

Amount In Word: Taka One Lac Nine Thousand Three Hundred Sixty Seven & Paisa Ninety One Only.

Terms & Conditions:

- 01 Transit Risk: The suppliers will bear full responsibility for carrying the materials. At the time of delivery the materials, any damage of the materials in transit will be supplier's responsibility. Also pls note that during process on work any damage of our assett will be your responsibility, which has to be replaced by the supplier in his
- 02 Mode of Payment: Advance amount of Tk. 50,000.00 to be paid within 5 days, rest amount to be paid after successful commissioning.
- 03 Delivery: Materials has to be completed at site by March 30, 2017.

For Spacezero Limited

Suppliers Acceptence

Spacezero Ltd.

On behalf of Cross World Power LID SPACEZERO LTD house 106 road 25 bloga banani dhaka 1213 bangladesh