

# CROSS WORLD POWER LTD



Ensuring Power Since 1982

REF : CWPL-BBT/0124/17F

DATE : Apr 23, 2017

Rahmat Fashion wear Ltd. (Rahmat Group)  
Senakalyan Bhaban (14th floor), 195 Motijheel, Dhaka-1000.

## COMMERCIAL OFFER

### Sub : Sale Offer for supply of Busbar Trunking Spare Items.

| SL # | Code | Product Name   | Unit | Price (BDT) | Qty. | Total Price(BDT) |
|------|------|--|------|-------------|------|------------------|
| 1)   | 5555 | Offer for installation of Electrical Point Wiring System without any material. | Lot  | 548,632.00  | 1.00 | 548,632.00       |

|  |            |
|--|------------|
| Total ex-works Price (in BDT) =            | 548,632.00 |
| Special Discount for Foreign (in BDT) =    | 198,632.00 |
| Total Discounted ex-works price (in BDT) = | 350,000.00 |
| Grand Total (in BDT) =                     | 350,000.00 |

### Terms & Conditions:

01. Offer Validity : 10 days from the date of this offer.
02. Brand : EAE.
03. Country of Origin : Turkey.
04. Delivery Time : 2 Working Days from the date of W/O along with advance.
05. Payment : 100% Advanced along with Work Order.
06. Warrantee : We warrantee the goods of any manufacturing defects in materials for a period of 1 years from the date of Delivery.

Your truly,  
CROSS WORLD POWER LTD.

Md. Sanwar Parvez  
Sr. Engineer, Sales & Marketing  
Mobile : 01777719792

Md. Moshur Rahman  
Asst. General Manager  
Mobile : 01755 514 703

*Handwritten note:*  
m  
24/04  
2017

DATE: 29/03/17

PROJECT: RAHMAT FASHION WEAR LTD.

DETAILS OF EXTRA WORK SCOPE AS INFORMED BY CLIENT (MR. SAZZAD, MAINTENACE MANAGER & MR. SERAJ, PROJECT ENGR.)

| SL No | Job Title                                       | Job Description   | UoM | Qty | Unit Sale | Total Sale |
|-------|---|---|-----|-----|-----------|------------|
| 1     | 25A/40A BBT Install at 3rd Floor (RMG Building) | Extra 2 lines BBT (Appx. 35m) need to install with connection at 3rd floor of RMG<br>Manpower: 1 nos. day labor+ 1 nos. supervisor<br>Completion time: Appx 4 days  | Job | 1   | 30,330    | 30,330     |
| 2     | Daycare Building CO2 Sensor                     | Extra 20 Nos. power socket needs to avail for CO2 sensor.<br>Groove Cutting- 200 rft<br>PVC pipe laying- 300 rft<br>Cable laying (2.5 rm)- 1200 meter<br>MK Steel Gang Install- 20 Pcs<br>15A Socket Install- 20 Pcs<br>Manpower: 4 nos. day labor+ 1 nos. supervisor<br>Completion time: Appx 8 days         | Job | 1   | 110,511   | 110,511    |
| 3     | RMG GFL CO2 Sensor                              | Extra 13 Nos. power socket needs to avail for CO2 sensor.<br>Groove Cutting- 100 rft<br>PVC pipe laying- 250 rft<br>Cable laying (2.5 rm)- 900m<br>MK Steel Gang Install- 13 Pcs<br>15A Socket Install- 13 Pcs<br>Manpower: 2 nos. day labor+ 1 nos. supervisor<br>Completion time: Appx 7 days               | Job | 1   | 70,135    | 70,135     |
| 4     | RMG 1st+2nd+3rd FL staff toilet CO2 Sensor      | CO2 sensor was not shown for this portion at approved design.<br>Groove Cutting- 70 rft<br>PVC pipe laying- 100 rft<br>Cable laying (1.5 & 2.5 rm)- 200 meter<br>MK Steel 1 Gang Install- 6Pcs<br>15A Socket Install- 6 Pcs<br>Manpower: 2 nos. day labor<br>Completion time: Appx 4 days                     | Job | 1   | 19,144    | 19,144     |
| 5     | Fire & Domestic pump cable laying+Connection    | Fire Pump cable 120 rm laying- 1600', 70 rm laying-400' with connection; Domestic Pump cable (10 rm) laying- 2000' with connection<br>Manpower: 4 nos. day labor+ 1 nos. supervisor<br>Completion time: Appx 6 days   | Job | 1   | 196,997   | 196,997    |
| 6     | LT to Daycare power cable laying+Connection     | Power cable 70 rm laying- 2000', 10 rm laying- 500' with connection<br>Manpower: 4 nos. day labor+ 1 nos. supervisor<br>Completion time: Appx 5 days  | Job | 1   | 110,360   | 110,360    |
| 7     | Point Wiring at Reception RMG GFL               | Wiring was not shown for this portion in approved design.<br>Groove Cutting- 20 rft<br>PVC pipe laying- 100 rft<br>Cable laying (1.5 & 2.5 rm)- 200 meter<br>MK Steel 2 Gang Install- 4Pcs<br>15A Socket Install- 4 Pcs<br>Switch 1 Gang- 4 Pcs<br>Manpower: 2 nos. day labor<br>Completion time: Appx 4 days | Job | 1   | 11,155    | 11,155     |
|       |   |   |     |     | Total     | 548,632    |

Approved: 3,50,000/-  
(Sp: Sanseer)