


PURCHASE ORDER

NUMBER	BS-1/GS Betbunia/2016/34		DATE	10/05/2016	
BENEFICIARY NAME, ADDRESS AND CONTACT			DELIVERY ADDRESS & CONTACT		
Cross World Power Ltd. Plot 1/B, Road 90, Gulshan-2 Dhaka-1212, Bangladesh Attn: Mr. Iftekhar Karim, Chief Operating Officer Cell: 01755514701			Tower Engineers & Construction Construction of 1 x SMBK Padma Multipurpose Bridge Project, Shariatpur Name & Contact: Engr. Md. Hafiz Ullah, Project Manager Cell: 01726589406		
BILL TO BE SUBMITTED TO			Notes/Special Instruction		
Tower Engineers & Construction House # 17, Road # 106, Block-CEN(F) Gulshan-2, Dhaka-1212					
SL	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	TEMPEST Brand 100 KVA (Prime) Rating Diesel Generator with Perkins Engine and Stamford Alternator	Set	01	1,120,000.00	1,120,000.00
	Generator:				
	Brand: Tempest				
	Model : PS100				
	Country of Origin : UK				
	Prime Rating : 100 KVA				
	Port of Shipment : Any Port, UK				
	Standby Rating : /110 KVA				
	Fuel Tank Capacity : 200 Liter				
	Fuel Consumption (L/Hr) @75% Load : 17L				
	Buttery Charger: Auto Battery Charger (ABC) included				
	Vibration Skid: Built-in vibration skid for smooth operation.				
	Emergency Stop: Emergency Stop available as protection device				
	Start System: Automatic Micro Controller based as well manual star/stop system				
	Dimension (Open Set): 188 x 74 x 150 (L x W x H) cm				
	Engine:				
	Brand : Perkins, UK				
	Engine Type : 4 stroke multi cylinder industrial diesel engine suitable for tropical environment				
	Model : 1104C-44TAG2				
	Speed (RPM) : 1500				
	Cooling System : Water				
	Protection: Over speed, under speed, oil pressure, over heating etc.				
	Fuel Tank: Built in with base				
				Total =	1,120,000.00
Amount in Words:		Taka Eleven Lac Twenty Thousand only.			



TERMS & CONDITIONS	
01	The rate of above work is fixed including transportation and Load-Unload cost upto site.
02	Terms of Payment: 20% advance A/C Payee Cheque favoring " Cross World Power Ltd. " along with the work order, 60% paid before delivery. Rest 20% after commissioning.
03	Delivery: Within 5 (five) days from the date of receiving your Work Order with payment and delivery (cost included) at site basis.
04	Installation, Testing & Commissioning : The price quoted above is included with the supervision and commissioning & Commissioning charges of the generator. Materials such as Power & Control Cable, Grounding system, Extension Silencer Pipe, Base etc. required for successful installation, testing & commissioning of the generator will have to be provided by TEC.
05	Warranty : The product is warranted against defects in design, materials and workmanship for a period of Twelve (12) months from the date of commissioning or 18 months from the date of delivery whichever comes earlier.
06	After Sale Service: Dataedge's thrust is not only to sell quality products but also provide effective after sales service support to its customers conducted by factory trained graduate engineers who are well equipped with all necessary instrument and equipment to provide round the clock support including : <ul style="list-style-type: none"> * Easy access of genuine spare parts from the manufacturer Facility of Annual maintenance Contracts * Facility for on site servicing of Engines through duly equipped mobile services vans
07	Company reserves the right to cancel your work order at anytime without assigning any reason


 Director/ Managing Director

I hereby agree with all the terms and conditions of this Purchase Order.

Name:

Copy: 01. Project Engineer; 02. Account Section, H/O; 03. Account Section, Project

