

Ref: MAHL/Mech/HO/Work-order/1665

October 17, 2017

Managing Director  
Cross World Power Ltd.,  
House # NE(O) 06, Road # 92,  
Gulshan-2, Dhaka-1212

E-mail: [sohel@cross-world.com](mailto:sohel@cross-world.com)

Atten.: Md. Sohel Uddin Bhuiyan (Manager, Sales & Marketing)


Subject: Work Order for Supply of (6 units) 500, 65 & 45 KVA Prime 3 Phase, Heavy duty diesel Generating sets.

Dear Sir,

With reference to your quotation no. CWPL-AM/2668/17-R02F, dated October 15, 2017 for supply & commissioning of 500, 65 & 45 KVA 6 units of Diesel Generators together with all components as mentioned in your quotation. Mir Akhter Hossain Ltd. hereby issue work order to you for supply of the above Generators set for our SASEC, Kornofully & Gomoti road Project, on the basis of the quotations & documents provided from your end under the following mutually agreed terms & conditions:-

**Description of the supply items are as below.**

Sl.	Product Name	Price (BDT)	Qty.	Total Price (BDT)
1	Tempest Brand 500 KVA (Prime) Rating Diesel Generator with Perkins engine and Mecc-Alte Alternator. Brand : Tempest Model : PM500 Alternator : Mecc Alte, UK. Country of Origin : UK. Control Module : Deepsea, UK. Port of Shipment : Felixstowe port, UK	39,50,000.00	1 Sets.	39,50,000.00
2	Tempest Brand 65 KVA (Prime) Rating Diesel Generator with Perkins engine and Mecc-Alte Alternator. Brand : Tempest Model : PM65 Alternator : Mecc Alte, UK. Country of Origin : UK. Control Module : Deepsea, UK. Port of Shipment : Felixstowe port, UK	8,70,000.00	2 Sets.	17,40,000.00





Sl.	Product Name	Price (BDT)	Qty.	Total Price (BDT)
3	Tempest Brand 45 KVA (Prime) Rating Diesel Generator with Perkins engine and Mecc-Alte Alternator. Brand : Tempest Model : PM45 Alternator : Mecc Alte, UK / <i>Stamford</i> Country of Origin : UK. Control Module : Deepsea, UK. Port of Shipment : Felixstowe port, UK	7,70,000.00	3 Sets.	23,10,000.00
Total Amount=>				80,00,000.00

#### 1. Control Module Specification

- Control Module Type: Auto start (AMF) digital control module. Deepsea Elect. (DSA) UK.
- Provided with Auto Alarm Indicator: Under/ volts, Under/ over speed, Under/ Over Frequency, Low Oil Pressure, High Engine temperature, Fail to Start and Loss of speed sensing etc.
- Phase Failure Relay: Digital option & control for mains supply lower cut off voltage set and adjustable hysteresis voltage, sensing option etc.

#### 2. Commencement of supply, erection, commission and installation work:

The supplier will do the supply, delivery and commissioning works of the 500, 65 & 45 KVA Diesel Generators immediately after getting the work order & shall complete all the relevant works within 5 (Five) days from the date of work order.

The supplier will hand over the 500, 65 & 45 KVA Diesel Generators to the buyer in good running condition after giving trial run of the same and arrange for training of the personnel of the buyer for smooth operation of the Generators set.

#### 3. Price:

The total price for all the Generators together with supply, erection and commissioning of the 500, 65 & 45 KVA Diesel Generators (without IT & VAT) has been fixed at **Tk. 80,00,000 /-** (**Taka Eighty Lac Only**), including cost of Radiator coolant, DM water, lube oil, Battery electrolyte etc. to be supplied from your end. *Mobly*

#### 4. Payment Schedule:

- 1<sup>st</sup> payment- 25% of contact price as booking money which is approximately Tk.= 20,00,000.00/- shall be made along with the work order through A/C payee cheque.
- 2<sup>nd</sup> payment- 60% of the contact price equals which to Tk.= 48,00,000.00 /-, will be made after delivery, installation, fitting, fixing of newly supplied and handover to buyers. *Mobly*



representative at project site in good running condition as per specification mentioned on your quotation.

3. Final payment equivalent to remaining 15% of the contracted price which equals to Tk.= 12,00,00.00/- will be made upon successful completion & operation of at least 2 (two) month after handover of the same.

**5. Delivery Schedule:**

You will be responsible for complete delivery of the Generator set along with all other accessories as mentioned in your quotation for completion of the work at site and put the 500, 65 & 45 KVA Diesel Generator functional at your own responsibility and arrangement. You should make arrangement of delivery of Generators set within 5 days of issuing this work order and put the Generator in operation within 7 (Seven) days next at our respective designated project. Failing which you will be held responsible for the delay.


**6. Warranty:**

Warranty for 12 (twelve) months or 1500 hrs as mentioned in your offer with all other general terms and conditions shall be followed by the supplier as per the quotation and technical proposal submitted by you on October 17, 2017.

If the above term & conditions are acceptable, you are requested to sign the duplicate copy as token of acceptance of the work order.

Thanking you,  
Very truly yours,

For Mir Akhter Hossain Ltd.

  
(M.G. Mustafa)

Executive Director (Mechanical)

Mir Akhter Hossain Ltd.

House # 13, Road # 12,  
Dhanmondi, Dhaka-1209.

Cell Phone # 01711521826