



Ref: SJIBL/HO/CSD/work order/2017/

October 09, 2017

**Engr. Md. Ariful Islam**  
Manager, Sales & Marketing  
Cross World Power Ltd.  
Plot-1/B, Road # 90,  
Gulshan-2, Dhaka-1212  
Contact No: 01755514731

**Re: Work order for supply and installation of 01(one) unit 20 KVA prime capacity Tempest brand new diesel generator at our Atibazar Branch, Keranigonj, Dhaka costing BDT 6,79,000/- only (Excluding installation materials).**

Dear Sir,

With reference to the above, we are pleased to inform you that the Management of the Bank has accepted your financial offer dated. 09.08.2017 for supply and installation of 20 KVA (prime) capacity Tempest brand new diesel generator at our bank under the following terms and conditions:

1. Specification & Price of Generators:

Particulars	Specification	Qty.	Unit price (excluding installation materials)	Remarks
Generator	Brand: Tempest Model: PM 20 / PS 20 Output (Prime): 20 KVA Volts: 400/230 V (3 Phase), Frequency: 50 HZ Engine: Perkins, UK (Electric start) Alternator: Stamford/ Meccalte, UK, Insulation Class H, With built in soundproof canopy (noise level 75 dbA @ 3 meter & ATS	01	BDT 6,79,000/-	

2. Standard unit price for installation materials:

Sl. No.	Item description	Unit	Standard unit rate in BDT including Govt. Vat & Tax
01	Cable-1Cx10 rm, NYY (BRB/Paradise/approved brand)	1 meter	125.00
02	Cable-1Cx16 rm, NYY (BRB/Paradise/approved brand)	1 meter	185.00
03	Cable-1Cx10 rm, BYA (BRB/Paradise/approved brand)	1 meter	100.00
04	Cable-4x10 rm, NYY (BRB/Paradise/approved brand)	1 meter	535.00
05	Cable-4x16 rm, NYY (BRB/Paradise/approved brand)	1 meter	795.00
06	Flexible cable – 4x1.2rm (BRB/Paradise/approved brand)	1 meter	77.00
07	Flexible pipe-1", 1.5", 2", 2.5", 3"	1 feet	20,25,29,33, 45
08	Earthling (150-200 feet, earth resistance must be <1.0Ω)	1 no.	42,000.00
09	Ducting works ( Made by 22 BWG sheet)	1 sq. Feet	240.00
10	Generator lifting cost (Ground floor to 2 <sup>nd</sup> floor)	1 Job	0.00
11	Generator lifting cost (above 2 <sup>nd</sup> floor) per floor	1 job	2,000.00
12	Silencer Pipe-2" (MS pipe)	1 feet	250.00
13	Silencer Pipe-3" (MS pipe)	1 feet	560.00
14	Silencer Pipe-4" (MS pipe)	1 feet	612.00
15	MS Bend, Elbow-2", 3", 4"	1 no.	350, 450, 650
16	Cable Tie, Screw, Rowel Plug, Clam, Rowel Bolt, PVC	1 Lot	4,000.00

*Ariful Islam*

