



সেনা কল্যাণ সংস্থা

SENA KALYAN SANGSTHA

SENA KALYAN SANGSTHA

RAOWA COMPLEX (Level-6)
VIP ROAD, MOHAKHALI
DHAKA-1206, BANGLADESH
PABX : 88-02-9890819
FAX : 88-02-9890900
E-mail : info@senakalyan.com
Web : www.senakalyan.org

SKS/230/EPM/SKS Tower/Generator **1382**

11 June 2018

NOTIFICATION OF AWARD: SUPPLY, INSTALLATION, TESTING AND COMMISSIONING OF 2×800 KVA AND 1×200 KVA DIESEL GENERATING SET FOR 13-STORIED SKS TOWER AT MOHAKHALI, DHAKA

References:

- SKS Tender Notice in "The Daily Ittefaq" & "The Bangladesh Observer" dated 06 April 2018.
- Your Submitted Tender No Nil; dated 07 May 2018.

1. This is to notify you that your Submitted Tender No: Nil; Dated 07 May 2018 for the **"Supply, Installation, Testing and Commissioning of 2×800 KVA and 1×200 KVA Diesel Generating Set For 13-Storied SKS Tower at Mohakhali, Dhaka"** at a cost of Tk. 2,52,00,000.00 (Tk. Two crore fifty two lac) only has been accepted by the Management of Sena Kalyan Sangstha.

2. You are thus requested to take following actions:

- Accept in writing this Notification of Award within 07 (seven) days of issuance of this letter.
- Sign the Contract Agreement within 07 (seven) days of issuance of this letter.

3. You may proceed with the execution of work only upon completion of the above task and after receiving the work order. You may also note that this Notification of Award shall constitute the formation of the Contract Agreement which shall become binding upon you.

4. You shall give 5% (five percent) Performance Guarantee of total contractual amount to Sena Kalyan Sangstha within 07 (seven) days of receiving Notification of Award which will be retained until expiry of maintenance period.

5. Draft Contract Agreement is attached herewith for your perusal.

6. For necessary action at your end please.

Colonel A B M Mizanur Rahman
Acting Deputy Director General
Engineering & PM Division

Distribution:

External:

Action:

Managing Director

CROSS WORLD POWER LTD

Plot-1/B, Road-90

Gulshan-2, Dhaka-1212

Information:

SKS Tower, Mohakhali, Dhaka

Internal:

Secretariat, SKS

DDG (Fin), SKS

Supply, instattation, testing and commissioning of Diesel Genertor set for SKS Tower Project, Mohakhali, Dhaka -1206					
BOQ For Foreign Item					
SI No	Description of Item	Unit	Quantity	Rate in GBP , CFR Chittagong	Total Amount in GBP , CFR Chittagong
5.1	<p>DIESEL GENERATOR</p> <p>Supply, installation, Diesel Generator set of the following KVA , 400/230V, 3-phase, 50Hz floor mounted inddor type continous rating emergency diesel generating set suitable for tropicalized country like Bangladesh as per detailed speic- fication as mentioned below (Manufactured in USA/UK/Sweeden/GErmany / Switzerland/Frnce /Japan/Italy in accordance with NEMA /IEC/VDE/JIS standards:</p> <p>Four stroke, 1500 , air cooled batter start, diesel engine completed with sound attenuated acoustically treated canopy with sound level 75 dBA 7 distance compelted pakage from manufacturing country</p> <p>Standard accessories viz water cooled radiator with blower fan and fan guard, lubricating oil pump , fuel injection pump, auto speed governor air cleaner, fuel and oil tank automatic safety shut-off and indicator for high water termperture gauge, Oil pressure, Over speed, water temperature, low Oil pressure gauge, tachometer, starting and stopping switch, exhaust silencer, vibration isolator mounting steel base frame to support radiator,Engine and Alternator etc Complete as required</p> <p>Alternator having one single bearing, brushless rotarting type compound self-exciting compound system, drip-proof screen protected type $\pm 1\%$ with electrically operated automatic voltage regulator (AVR) etc. completed as required.</p>				



CROSS WORLD POWER LTD.


Cross-world



Ensuring Power Since 1982

	Full set of tools necessary for maintenance of gener ating set, foundation bolts with nuts, starting batter, connecting leads with sockets, battery charger, filling of lubricants and fuel up to testing period.				
	with auto-start,autoshut off and auto-transfer switch system (ATS) and synchronizing panel for parallel operation of generators trail run shall be done 03 hrs per day for 02 days before handed over. No final payment shall be paid with out full load testing				
5.1	ATS 3200 Amps	Set	1	GBP 12,000 , GBP Twelve Thousand only	GBP 12,000 GBP Twelve Thousand only
5.1.1	800KVA Genset , Brand : Tempest , UK Engine Brand : Perkins Country of Origin : UK Country of Manufacturing : UK <u>Alternator :</u> Brand : Stamford Country of Origin : UK Country of Manufacturing : UK Port of Shipment of Genset : UK Trans-shipment of Genset : Singapore / Colombo	Set	02	GBP 77,500 GBP Seventy Seven Thousand Five Hundred only	GBP 155,000 GBP one lac fifty five thousand only
5.1.3	200KVA Genset , Brand : Tempest , UK Engine Brand : Perkins Country of Origin : UK Country of Manufacturing : UK <u>Alternator :</u> Brand : Stamford Country of Origin : UK Country of Manufacturing : UK Port of Shipment of Genset : UK Trans-shipment of Genset : Singapore / Colombo	Set	01	GBP 24,000 GBP Twenty Four Thousand only	GBP 24,000
Grand Total				CFR GBP 191,000	
In word : CFR GBP One lac ninety one thousand only					

Iftakhar Karim
Iftakhar Karim
Chief operating officer
CROSS WORLD POWER LTD





Supply, instattation, testing and commissioning, Diesel Genertor set for SKS Tower Project, Mohakhali, Dhaka -1206

BOQ For Local Item

SI No	Description of Item	Unit	Quantity	Rate in Taka	Total Amount in Taka
5.1.2	Cable electirc 1C-400 mm ² NYY 600/1000 volts 50Hz or as per recommendation of the manufacture.	Mtr	400	TK 4,060 Taka Four Thousand sixty only	TK 1,624,000.00
5.1.4	Cable electirc 1C- 185 mm ² NYY 600/1000 volts 50Hz or as per recommendation of the manufacture.	Mtr	120	TK 1,905 Taka one thousand nine hundred five only	TK 228,600.00
5.1.5	<p>Earthing:</p> <p>Installation of earthing system incluidng supplying of all materials inlcuding earth electrode of 50mm dia G.I pipe of inspection pit of minimum size 305x305x205mm minimum 40m long, earthing lead of size 2x2/OSWG copper wire , copper earthing block of required size and required size of cable for transformer neutral to earth electrode. Interconnection of bodies of the equipment to equipments as per BNBC and direction of trhe engineer in charge.The earth resistance of the installation should nto exceed i ohm in the direst season.</p>	Job	06	TK 76,000 Taka Seventy Six Thousand only	TK 456,000.00
	Installtion , Testing & commissioning of the above generators	Job	03	TK 236,940 Taka Two Lac Thirty Six Thousand Nine Hundred Forty only	TK 710,820.00
5.1.6	Silencer Pipe Extention with Insulation	Ft	45	TK 5,000 Taka Five Thousand only	TK 225,000.00



CROSS WORLD POWER LTD.

Cross-world



Ensuring Power Since 1982

5.1.7	Hot Air Ducting with louver	Ft	45	TK 5,000 Taka Five Thousand only	TK 225,000 .00
5.1.8	Transportation from Chittagong Port to Site (Excluding Customs duty , CNF & all related Govt. fee which will be bear by SKS authority)	Job	1	TK 75,000 Taka Seventy Five Thousand only	TK 75,000.00
Grand Total				TK 3,544,420 Taka Thirty Five Lac Forty Four Thousand Four Hundred Twenty only	

Ilftekhar Karim

Ilftekhar Karim
Chief Operating officer
CROSS WORLD POWER LTD

