

**CONCORD REAL ESTATE & DEVELOPMENT LTD.**

CONCORD CENTRE, 43, NORTH C/A, GULSHAN, DHAKA-1212

Date: 26-Jul-2018

Ref.: CRDL/2018/07/PO-000454

CROSS WORLD POWER LTD.HOUSE-NE(O) 06, ROAD-92, GULSHAN-2,
DHAKA-1212

Phone: 8811858,8816528

Fax: 8816205

Attn: MR. MOSHIUR RAHMAN

Indent Ref. No.: 81857

**Sub: Work Order for Supply of 400 KVA Prime / 425 KVA Stand by 3 Phase Heavy Duty Diesel
Generating Sets at Concord Zara.**

Dear Sir,

With reference to your Quotation the Management is placed an Order for supply us following materials at Concord Zara, P#3, R#1, B#k, Baridhara..Requisition No.: RQ07-04 000767 dated on 26-Jul-2018 [81857] description given below :

SL	Item Name & Specification	Origin	Brand	Unit	VAT(%)	Tax(%)	Rate	Qty	Amount(BDT)
1	GP10-A-A- GENERATOR [Generator Brand : Tempest, Model : PS400, Country of Origin : UK, Capacity Prime 400KVA Stand by 425 KVA, Engine Brand : Perkins, Model : 2206A-E13TAG3, Origin : UK, Engine Type : 4 stroke mullti cylinder, Alternator Brand : Stamford, Model : HCI444F/ S41LDF, 50 Hz, 3 Phase, Control Module : Deepsea, Origin : UK, Air cooling Insulation Type : Class "H", Auto start (AMF) digital control module Automatic Microcontroller based as well manual start/stop system, Emergency stop available as protection device, Built in vibration skid for smooth operation.]	UK	Tempest				3,750,000.00	1.00	3,750,000.00
2	SILENCER PIPE FITTING (6") [MS Pipe, Elbow, Insulation etc. as per given BoQ.]			RFT			4,250.00	20.00	85,000.00
3	MAIN ATS [Local Built ATS will be supplied in suitable steel enclosure wall mounted, fuses, magnetic contactor coil, indicator etc. as per given BoQ.]			NOS			175,000.00	1.00	175,000.00
4	EARTHING WITH MATERIALS [Earthing with 1.5" dia GI. Pipe Earth Electrode of 40 meter length burried up to a depth of 40 meter Full length GI Pipe Connection on Boring. (Bashundhara Silver). 2 gauge copper wire & 50rm green cable BRB, etc as per given BoQ.]			SET			44,000.00	3.00	132,000.00
5	DUCTING [As per layout with 22 SWG Ms sheet, angle bar, flat bar support, canvas cloth etc. as per given BoQ]			SFT			242.85	280.00	67,998.00
6	INSTALLATION, TESTING & COMMISSIONING [Radiator coolant: Havoline Premix Coolent 60 Liter, Lube Oil SAE 15W 40 Liter 40, Battery electrolye : Specific gravity 1.250 20 Liter, Fuel 400 Liter Diesel for test run etc.]			JOB			60,002.00	1.00	60,002.00
7	SOUND PROOF CANOPY [Local built Acoustic enclosure will reduce the sound level to 75 dBA@ 1 meter in open space and is complete with air inlet and outlet options at the alternator and radiator ends respectively, hinged access doors on either side with proper locking option, silencer, cable entry gland apertures.]			SET			430,000.00	1.00	430,000.00

Amr
29/07/18

Sumit
29-07-18

Munim

Sumit


Total Amount = 4,700,000.00
Carrying & Installation =
Discount (%) =
VAT =
Tax =
Total Payable Amount = 4,700,000.00


Work Order Amount In Word: (Taka Forty Seven Lac Only)

Terms & Conditions :

- 01 Delivery, Supply, Making, Installation & Commissioning Period:- Generator Set will be delivered at our site within 15 days from the date of work order and others materials/services (Main ATS, Canopy, Earthing, and Silencer & Ducting) supply, making, Installation & commissioning works will be completed within 07 days after receiving the Generator Set at Project Site.
- 02 Payment Type:- Payment will be made 50% after delivery at site, 45% after successfully instalation, testing & commissioning, 5% will be paid afer 06 month.
- 03 Warranty:- 24 Months or 3000 Running Hour whichever occurs earlier from the date of commissioning.
- 04 After Sales Service:- After Sales Service is free for 12 months after the date of commissioning without Consumable Items like Filters, Lube Oil etc
- 05 Works Supervision & Training:- Total Works are to be done as per direction of our Senior Engineer (Electrical), All Specifications attached herewith the Work Order, Necessary Training for Operator & Mechanics will be provided by Cross World Power Ltd. at free of Cost for the time of Commissioning the Generator Set
- 06 Quality:- You have to maintain specified Brand/Grade Quality & Quantity. Concord reserves the right to reject the materials for below grade/quality. In that case you will take back the materials at your own cost from the Project Site
- 07 Quantity:- Quantity may vary (increase/decrease). Duct Making Works per Sft. Rate is Tk. 242.85.00 & Silencer System Making Works per Rft. Rate is Tk. 4250.00 above mentioned Quantity & Amount are an estimated cost, payment will be settled as per actual quantity required at the project which is certified by concerned Project In-Charge/Electrical Engineer.
- 08 Tax:- VAT & AIT will be imposed as per Government rules.
- 09 Others:- Concord reserves the right to cancel or change or replace this Work Order any time without giving any reason

Best regards,


MAHBUBUR RAHMAN
GENERAL MANAGER


Procurement Conducted By:
MOHAMMAD AL AMRAN HOSSAIN
ASSISTANT MANAGER

Copy To : 1. ED (Project)
2. ED (CA)
3. GM (A&F)

Work Order Accepted By