

CROSS WORLD POWER LTD



FINANCIAL OFFER

St.vincent Hospital
Cosba,Dinajpur

DATE : Jun 30, 2019
REF : CWPL-AM/2304/19F

FINANCIAL OFFER FOR SUPPLY OF 30 KVA 3 PHASE HEAVY DUTY DIESEL GENERATING SETS.

Dear Sir,

We are pleased to submit our financial offer with reference to our technical offer# CWPL-AM/2304/19T dated Jun 30, 2019 :

1. Price:

SL #	Product Name	Unit	Price (BDT)	Qty.	Total Price(BDT)
1)	TEMPEST Brand 30 KVA (Prime) Rating Diesel Generator with Perkins engine and Stamford alternator BRAND : Tempest ENGINE : Perkins, UK ALTERNATOR : Stamford, UK CONTROL MODULE : Deepsea, UK PORT OF SHIPMENT : Felixstowe port, UK AVAILABILITY : 5 to 15 days from ready stock subject to availability	Set	800,000.00	1.00	800,000.00
2)	Local Canopy for 30 KVA Genset	Pcs.	65,000.00	1.00	65,000.00
3)	Installation Materials (Power Cable & Connection Accessories, Lube Oil, Coolent, Battery Electrolyte, Diesel) As per Attached	Lot	25,000.00	1.00	25,000.00

Total Price (Ready Stock) in BDT 890,000.00

Special Discount (90,000.00)

GRAND TOTAL (Excluding VAT & AIT) in BDT 800,000.00

Amount in words : BDT Eight Hundred Thousand Only.

Payment terms:

① 50% with work order

② 50% after bulky installation.

1 of 2

Plot 1/B, Road 90, Gulshan - 2, Dhaka 1212, Bangladesh | p: (880 2) 5881 1858, 989 1442 | f: (880 2) 5881 5160 | e: info@cross-world.com

Accepted, By

fr. Michele Brambilla
01/07/19

CROSS WORLD POWER LIMITED

BOQ OF 1X30 kVA GENERATOR

CLIENT -ST VINCENT HOSPITAL

ADDRESS- DINAJPUR

DATE- 24-06-19

GEN MODEL-		ENGINE MODEL-	ALTERNATOR MODEL-		
SL NO	JOB DESCRIPTION	TECHNICAL DETAILS/ BRAND	UOM	QTY	REMARKS
1	Electrical System:				
1.1	Power Cable (35 °C Ambient on air)	4CX16 rm NYY DG To ATS/OR MCOS	Meter	15	Cross World
		4CX 16 rm NYY Mains To ATS		0	Client's Scope
		4CX 16 rm rm NYY ATS to Load		0	Client's Scope
1.2	Power Cable Lugs	16 rm , Material -Copper , Surface-Electro Tinned	Pcs	16	Cross World
1.3	Control cable For Sensing	4 X 1.2 rm (40/0.19 mm)Flexible Cable	Meter	15	
1.4	PVC Flexible Pipe	1.5" dia	Meter	15	
1.5	Saddle for flexible pipe	1.5" dia local	pcs	30	
1.6	Royal Plug & Screw	10 no. & 1.5" length	Pack	1	
1.7	PVC Tape	Adhesive Tape 04 color (Red/Yellow/Black/Blue)	Pcs	4	
1.8	Royal Bolt	10 no.	Pcs	14	
1.9	Cable Tie	L - 8"	Pack	1	
1.10	Power Cable Laying	4CX16 rm NYY Cable	Meter	15	
2	Generator Earthing :				
2.1	Earthing Boring	100 rft	Job	0	Client's Scope
2.2	Earthing Copper Lead	4 SWG	Meter	0	
2.3	Earthing Block	Dimension LXWxD - 200mm X 30mm X 5mm with connection facility	Pc	0	
2.4	Earthing Cable	1 X 10 rm BYA (Green) Earthing Copper bar to gen & equipment	Meter	10	
2.5	PVC Flexible Pipe	3/4" inner dia	Meter	5	
2.5	Earthing Cable lugs	10 rm Material -Copper , Surface-Electro Tinned	Pcs	4	
3	Exhaust System:				
3.1	Exhaust Silencer straight Pipe	MS Pipe bore 3" ,thickness 3-4mm	Meter	3	Client's Scope
3.2	Exhaust Bends /Elbow	Long radius 90 deg L bow 3"	Pcs	2	
3.4	Exhaust Socket	3" inner dia	Pcs	1	
3.4	Exhaust Heat Insulation	Insulation Of Pipe with Glasswool (25.4mm min thickness) along with 26SWG Aluminium sheet cladding.	Job	1	
3.5	Exhasut Fitting	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM	Job	1	
04	Cooling System:				
4.1	Radiator Ducting	As per layout with 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth etc WXH=2.4'X2' rft=8	Sq-ft	0	Client's Scope
5	Commissioning Material:				
5.1	Radiator coolant	Havoline Premix Coolent	Liter	10	Cross World
5.2	Lube oil	SAE 15 W 40	Liter	10	
5.3	Battery electrolyte	Specific gravity 1250	Liter	10	
5.4	Diesel		Liter	45	
06	DG On site delivery:				Cross World
6.1	Loading /Unloading/Lifting	Generator dry weight-1500 Kg	Job	1	Client's Scope
7	CIVIL WORK				
7.1	Required DG base	SIZE=LXWXD(INCH)=9'4"X4'X5"	JOB	1	

All civil work done by client

Accepted By

Fr. Michele Brambilla
01/7/19Fr. Michele Brambilla
Director
St. Vincent Hospital.