

HEAD OFFICE

100 Gulshan Avenue
Dhaka 1212
Bangladesh

Ref: EBL/Admin-1/Generator/20 KVA/19/183

August 18, 2019

Cross World Power Ltd.
Plot: 1/B, Road: 90, Gulshan - 02
Dhaka -1212.

Attention: Chairman & CEO

Sub: Work Order for Purchasing 20 KVA Diesel Generator for Three New Banking Booths of Eastern Bank Limited (EBL) at Mirsarai, Chandra & Siddhirgonj.

Reference: Your submitted quotation dated: July 28, 2019.

FA No: Generator/19-171

Dear Sir,

Management of EBL is pleased to award the work for supplying & fitting of 20 KVA Generator for three new banking booths of Eastern Bank Limited (EBL) at Mirsarai, Chandra & Siddhirgonj to Cross World Power Ltd. at Tk. 2,397,880.00 (Taka Twenty Three Lac Ninety Seven Thousand Eight Hundred & Eighty) only including VAT, AIT and transportation expense as per product features mentioned in your submitted quotation. Detail of work is as under:

SL	Detail	Requirement
1	Brand	TEMPEST-UK
2	Model	CS20
3	Capacity (Prime)	20 KVA
4	Capacity (Stand by)	22 KVA
5	Alternator (Brand & Country of Origin)	Stamford, UK
6	Engine	Cummins
7	Fuel Consumption (75% Load)	4.80 Ltr/Hr
8	Warranty	1500Hours or 12 Months
9	After Sales Service	18 Months
10	Days Required for Delivery:	
-	Gen-set with Local Canopy & Local ATS	Within 07 Days from issuance of Work Order
11	Total Price: (BDT)	
-	03 Generator with Local Canopy & Local ATS	Tk. 2,397,880.00 including VAT & TAX



Admin-01, Procurement

2. Following are the Term & Condition of the Work:

- a. Place of installation: i) **EBL Mirsarai Booth:** Hajee Renu Miah Master Shopping Complex (1st Floor), Dhaka-Chattogram Highway, PO & PS: Mirsarai, Dist: Chattogram.
ii) **EBL Chandra, Gazipur Booth:** Momota Super Market, House No. 86/2, Block: H, Ward-7, Sattar Road, Palli Bidyut, Chandra, Gazipur.
iii) **EBL Siddirgonj Booth, Narayangonj:** Sonargaon Mega Complex, Dhaka-Sylhet Highway, Ward-5, Sonargaon, Narayangonj.
- b. Delivery: Within 07 days from issuance of work order.
- c. Warranty & Maintenance: The maintenance period for the Generator set & ATS shall be for 18 (Eighteen) Months from the date of successful commissioning of the set or 12 months/1500 hours whichever comes first. Supplier (CWPL) will be liable for all defects that appear during the maintenance period. For any minor defects during the maintenance period in any component(s) of the Generator(s), it will be repaired by suppliers (CWPL) technical team. If any major defect(s) detected / found in the generator(s) or any component(s) of the Generator(s) within the maintenance period, supplier (CWPL) is liable for replacing of the generator or defective item(s) as soon as complain received from the Bank authority.
- d. Payment Schedule: Payment will be credited in your respective account maintained with EBL after successful installation and commissioning of the each Generator set subject to necessary deduction of VAT & TAX as applicable/admissible.
- e. Security Money: An amount of 10% of the total bill shall be retained as security deposit for a period of minimum 06 (six) months from the date of commissioning of the Generator set.
- f. Penalty: An amount of Tk. 2000.00 (Two Thousand) only will be deducted for each day of delay, if the time schedule of delivery is not maintained.
- g. Safety Measures: Ensure proper safety measures of assigned technical personnel & EBL will not take any responsibility for partial or full damages of technical personnel & items.
- h. Submission of Bill: Bill must be submitted within 15 (Fifteen) days of completion of the work. The Management of EBL will not be liable for bills submitted after unusual delay without any intimation.

You are requested to complete the work as per direction of the Bank Authority. Please note that a satisfactory certificate needs to be obtained with the signature and name seal of employee/concerned user after installation and successful commissioning of the Generator Set for necessary processing at your end. EBL reserves all the right to cancel/amend this work order at any time without showing any reason whatsoever.

Thanking you.



Md. Ohidul Islam
Manager, Admin



Kamal Mustaba Ali
Head of Administration & Security

Above terms & conditions are accepted:

Ariful Islam
Manager, Sales & Marketing
Cross World Power Ltd.

Office Seal

CROSS WORLD POWER LIMITED

BOQ OF 1X20 kVA GENERATOR

CLIENT - EBL

ADDRESS- Chandra Booth, Gazipur

DATE- 25.07.19

SL NO	JOB DESCRIPTION	TECHNICAL DETAILS/ BRAND	UOM	QTY	UNIT RATE	TOTAL RATE	REMARKS
01	Electrical System:						
1.1	Power Cable (30 °C Ambient on ground)	4C-10 rm NYY DG To ATS	Meter	25	560	14000	Considering ATS and MDB Location at 2nd Floor.
		4C-10 rm NYY MAIN To ATS		3	560	1680	
		4C-10 rm NYY ATS To LOAD		3	560	1680	
1.2	Power Cable Lugs	10 rm , Material -Copper , Surface -Electro Tinned	Pcs	24	8	192	
1.3	Control cable For Sensing	4 X 1.2 rm (40/0.19 mm)Flexible Cable	Meter	85	80	6800	
1.4	PVC Flexible Pipe	1" dia	Meter	45	26	1170	
1.5	Saddle For Flexible Pipe	1" dia Local	Pcs	90	4	360	
1.6	Royal Plug & Screw	1.5" length & 10 no.	Pack	2	171	342	
1.7	PVC Tape	Adhesive Tape 04 color (Red/Yellow/Black/Blue)	Pcs	4	29	116	
1.8	Royal Bolt	10 no.	Pcs	10	18	180	
1.9	Cable Tie	L - 10"	Pack	2	171	342	
1.10	Power Cable Laying	4C-10rm Power Cable Laying	Meter	31	100	3100	
02	Exhaust System:						
2.1	Exhaust Silencer straight Pipe	MS Pipe bore 3" ,thickness 3-4mm	Meter	7	1700	11900	
		MS Pipe bore 4" ,thickness 3-4mm	Meter	5	2165	10825	
2.2	Exhaust Bends /Elbow	Long radius 90 deg L bow 3"	Pcs	2	724	1448	
2.3	Reducer	3" to 4"	Pcs	1	724	724	
2.4	Reducer	3" to 2"	Pcs	1	461	461	
2.5	Exhaust Heat Insulation	Insulation Of Pipe with Rockwool/Glasswool (25.4mm min thickness) along with 1 mm Aluminium sheet clading.	Job	1	5000	5000	
2.6	Exhaust Fitting	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM	Job	1	4980	4980	
2.7	Exhaust socket	For 3" Dia pipe	Pcs	1	580	580	
					TOTAL	65880	

NOTE:

- Earthing & All necessary civil work will done by EBL
- Diesel fuel for test run will be arranged by EBL