

CROSS WORLD POWER LIMITED
BOQ OF 1X100 KVA GENERATOR
CLIENT - HOLY GARDEN COMPLEX

ADDRESS-UTTAR AUSHPARA,TONGI

DATE- 28-08-19

GEN MODEL-

ENGINE MODEL-

ALTERNATOR MODEL-

SL NO	JOB DESCRIPTION	TECHNICAL DETAILS/ BRAND	SCOPE OF SUPPLY	UOM	QTY	UNIT RATE	TOTAL RATE	REMARKS
1	Electrical System:							
3	Exhaust System:							
3.1	Exhaust Silencer straight Pipe	MS Pipe bore 4" ,thickness 4mm		Meter	11	1942	21362	
3.2	Exhaust Bends /Elbow	Long radius 90 deg L bow 4"		Pcs	2	855	1710	
3.3	Reducer	3" to 4"		Pcs	1	724		
3.4	Exhaust Heat Insulation with Silencer Box	Insulation Of Pipe with Glasswool (50mm min thickness) along with 26SWG Aluminium sheet cladding.		Job	1	9749	9749	
3.5	Exhaust Fitting with Silencer Box	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM		Job	1	7672	7672	
04	Cooling System:							
4.1	Radiator Ducting	As per layout with 22 SWG MS sheet,Angle bar, flat bar support.Canvas cloth etc		Sq-ft	N/A	-	-	
5	Commissioning Material:							
5.1	Radiator coolant	Havoline Premix Coolant		Liter	15	160	2400	
5.2	Lube oil	SAE 15 W 40		Liter	10	420	4200	
5.3	Battery electrolyte	Specific gravity 1250		Liter	10	90	900	
06	DG On site delivery:							
6.1	Loading /Unloading/Lifting	Generator dry weight-2600 Kg	CWPL	Job	1			
7	Civil Work							
7.1	DG Base	LXWXD=3278X1398X153	CLIENT	JOB	1			
TOTAL TK.(Excluding VAT & AIT)							47993	

Notes:All required civil work will be done by client

client are requested
to provide those materials
CWPL. They ~~are~~ will be paid
the payment after installation.

[Signature]
5/10/19

[Signature]
05/10/2019