



SULTANA SWEATERS LIMITED

Head Office:

Alamgir Tower, House#11/B, Road#55, Block : N.W.(F), Gulshan-02, Dhaka-1212
Phone : 88-02-9852351, 9852352, 9852353, Fax : 88-02-9852354

Factory:

Meherabari, Valuka, Mymensingh, Bangladesh

Date: 22nd February, 2020.

Cross World Power Ltd.

House #1/B, Road # 90, Gulshan-2, Dhaka.

Attention: Md. Najmul Islam

Engineer, Sales

Cell: 01755694136

Subject: Work Order for supply, installation, testing & commissioning of MDB, SDB for Washing plant.

Dear Sir,

With Reference to your quotation dated on 30.12.2019 (Ref : CW/SW/SS/301219), we are pleased to place an order for supply, installation, testing & commissioning of below MDB, SDB and other accessories:

SL. No.	Item Name	Qty (Pcs)	Unit Price (In BDT)	Total Price (In BDT)
1	Manufacture of 14 /16 SWG sheet steel metal enclosed, dust and vermin proof free standing floor mounting indoor type MDB according of IEC/VDE in standard design with Zink primer and two coats of Powder coating paint as per Accord & Alliance. Bus Bar : 1250 A. Neutral 100% & Earthing 50%. MDB Size : 700 mm,1300 mm &1800 mm. Incoming : 03 Nos. Indicator Lamp. 01 Nos. Digital Multi Meter. 03 Nos. CT 800/5 Outgoing : 20 Nos.25A TP MCB ABB Italy. 12Nos. 10A TP MCB ABB Italy. 02 Nos. 63A TP MCB ABB Italy. 04 Nos. Panel Lock, 04 Nos louver with filter, 02 Nos.Cooling fan (10") Wiring PVC Chanel 01 job SS Nut Bolt Cable Gland and Bottom hole (As required) Double door Wiring Cable BRB Door Earthing with 6RM Cable.	01	2,00,000	2,00,000

Continue to 2nd page

continue from 1st page

LABIB GROUP

SULTANA SWEATERS LIMITED

Head Office:

Alamgir Tower, House#11/B, Road#55, Block : N.W.(F), Gulshan-02, Dhaka-1212
Phone : 88-02-9852351, 9852352, 9852353, Fax : 88-02-9852354

Factory:

Meherabari, Valuka, Mymensingh, Bangladesh.

Subject: Work Order for supply, installation, testing & commissioning of MDB, SDB for Washing plant.


SL. No.	Item Name	Qty (Pcs)	Unit Price (In BDT)	Total Price (In BDT)
2	<p>Manufacture of 14 /16 SWG sheet steel metal enclosed, dust and vermin proof free standing floor mounting indoor type SDB according of IEC/VDE in standard design with Zink primer and two coats of Powder coating paint - as per Accord & Alliance.</p> <p>Copper Bus Bar : 630 A. Neutral 100% & Earthing 50%.</p> <p>SDB Size : 350 mm, 1200 mm & 1300 mm.</p> <p>Incoming :</p> <p>03 Nos. Integrator Lamp.</p> <p>01 Nos. Digital Multi Meter.</p> <p>03 Nos. CT 400/5</p> <p>Outgoing :</p> <p>20 Nos. 25A TP MCB ABB Italy.</p> <p>30 Nos. 6A TP MCB ABB Italy.</p> <p>10 Nos. 10A SP MCB ABB Italy.</p> <p>04 Nos. Panel Lock,</p> <p>04 louver with filter, 02 Nos cooling fan.</p> <p>Wiring PBC Chanel.</p> <p>01 job SS Nut Bolt.</p> <p>Cable Gland (As required)</p> <p>Double door</p> <p>Wiring Cable BRB</p> <p>Door Earthing with 6RM Cable.</p>	01	2,20,000	2,20,000
Total Price				4,20,000


In Word: Four lac twenty thousand taka only.


Terms and Conditions :


1. All items should be delivered as per your offer letter and specification at Sultana Sweaters Ltd, Meherabari, Valuka, Mymensingh.
2. All Circuit breaker should be ABB, Italy and Adjustable type.
3. Cable marking, cooling fan with filter, door Earthing and proper annunciations should be present in the panel.
4. Metering should be accurate in the panel.
5. Cable Bottom Entry & Top out and Cable Gland with sheet holes should be supplied by supplier.
6. Making, Installation & Commissioning should be done as per Accord and Alliance.
7. Payment will be made on through Pay order in favor of 'Cross World Power Ltd.'
8. Warranty, Guaranty and after sales service will be 01 year free of cost.
9. Delivery and Installation should be done within 10 days after the date of work order.

Thanking You,


Electrical Engineer
Sultana Sweaters Ltd.


Chief Engr.
Labib Group


Director (Admin)
Sultana Sweaters Ltd.


Deputy Managing Director
Sultana Sweaters Ltd.