

Ref : CW/SS/LTAL/04032020  
Date : Wednesday, March 4, 2020

To,  
Managing Director  
**Lantabur Apparels Ltd**  
kewa, boherarchala, sreepur,  
Gazipur, Dhaka, Bangladesh.

Sub : Offer for supply, installation, testing & commissioning of DB.

#### FINANCIAL PROPOSAL

SL #	Descriptions	Qty	Unit	Unit price IN TAKA	Total price IN TAKA
01)	DB-1 -Cost of complete DB per attached technical specifications.	2	Set	173,000	346,000
02)	DB-2 -Cost of complete DB as per attached technical specifications.	1	Set	143,600	143,600
03)	<u>DELIVERY, INSTALLATION &amp; TESTING</u> ( Cost of complete of the above without any cable & civil works )	1	Job	14,000	14,000
Total Price (IN TAKA)					503,600
Special discount					26,056
Grand Total Price Excluding VAT (IN TAKA)					477,544

#### Terms & Conditions :

- 01) **Validity** : Our offer will remain valid for a period of 40 days from the date of this offer.
- 02) **Delivery** : Within 7-10 days after receipt of confirmed order & payment as per clause # 3.
- 03) **Payment** : 50% as advance along with order & remaining  
40% before delivery at the site.  
10% after commissioning
- 04) **Warranty** : One year after commissioning or one & half year from the date of delivery which

Thanking you.

Yours very truly,  
Md. Sumon Rahman  
Senior Engineer (Project Sales)  
Cross-world Power Ltd

Payment:

① Advance — 1 Lac (Paid)  
② After delivery — 3,77,544 Taka

Rashid  
5/3/2020



## TECHNICAL SPECIFICATION :

## 01) DB-1

QTY	UNIT
Set	2

Sheet steel clad powder coated (14 & 16SWG), dust and vermin proof, free standing, floor mounting, 415V, 50 Hz, Indoor type DB Panel with 400A Hard Drawn Copper Busbar.

Set of components required for the manufacture of LT Panel comprising :-

**INCOMING :**

400A,TP,36KA,415V,50Hz, MCCB with having adjustable overcurrent & magnetic short circuit protection.

Pcs	1
-----	---

Phase indicating Lamp

Pcs	3
-----	---

CB ON OFF TRIP Indication lamp

Pcs	3
-----	---

1x6A,TP MCB for the protection of control circuit

Pcs	1
-----	---

1x2A,SP MCB for the protection of control circuit

Pcs	3
-----	---

**OUTGOING :**

63A,TP,6KA,415V,MCB.

Pcs	14
-----	----

32A,TP,6KA,415V,MCB.

Pcs	3
-----	---

20A,SP,6KA,415V,MCB.

Pcs	4
-----	---

**BUSBAR Details**

400A TPN + 1/2E Common Busbar

**ENCLOSURE As Standard.**

Connection Accessories .

**BRAND**

**MCCB -ABB,ITALY**

**MCB-ABB,GERMANY**

## 02) DB-2

Set	1
-----	---

Sheet steel clad powder coated (14 & 16SWG), dust and vermin proof, free standing, floor mounting, 415V, 50 Hz, Indoor type DB Panel with 320A Hard Drawn Copper Busbar.

Set of components required for the manufacture of LT Panel comprising :-

**INCOMING :**

320A,TP,36KA,415V,50Hz, MCCB with having adjustable overcurrent & magnetic short circuit protection.

Pcs	1
-----	---

Phase indicating Lamp

Pcs	3
-----	---

CB ON OFF TRIP Indication lamp

Pcs	3
-----	---

1x6A,TP MCB for the protection of control circuit

Pcs	1
-----	---

1x2A,SP MCB for the protection of control circuit

Pcs	3
-----	---

**OUTGOING :**

160A,TP,25KA,415V,50Hz, MCCB with having adjustable overcurrent & magnetic short circuit protection.

Pcs	1
-----	---

63A,TP,6KA,415V,MCB.

Pcs	6
-----	---

40A,TP,6KA,415V,MCB.

Pcs	4
-----	---

20A,SP,6KA,415V,MCB.

Pcs	4
-----	---

**BUSBAR Details**

320A TPN + 1/2E Common Busbar

**ENCLOSURE As Standard.**

Connection Accessories .

**BRAND**

**MCCB -ABB,ITALY**

**MCB-ABB,GERMANY**