

Shipan Barua

To: Habibur Rahman; 'Md.Abusieed Sobuj'
Cc: ariful@cross-world.com; aziz@cross-world.com; taz@cross-world.com;
sultan@cross-world.com
Subject: RE: REQUEST FOR PRICING FOR 20 KVA GENERATOR - NEW EBL PREMISES AT
KEPZ SUB-BRANCH, CHATTOGRAM

From: HO/Admin - Ohidul Islam [<mailto:ohidul.islam@ebl-bd.com>]

Sent: Wednesday, September 02, 2020 3:46 PM

To: ariful@cross-world.com

Cc: HO/Admin - Mahbub Hossain Khan; CTG/Admin - Azadul Islam; CTG/Admin – Tanvir Ahammed Chowdhury;
HO/Admin - Kamal Mustaba Ali

Subject: FW: REQUEST FOR PRICING FOR 20 KVA GENERATOR - NEW EBL PREMISES AT KEPZ SUB-BRANCH,
CHATTOGRAM

Importance: High

Dear Mr. Arif
Manager, Sales
[Cross World Power Ltd.](#)

The management of EBL agrees Tk. 1,30,000.00 against your enclosed offer for installing a 20KVA Generator at EBL KEPZ Sub-branch, Chattogram which has already been consented by you verbally.

Please do the needful in association with Mr. Tanvir Ahammad Chowdhury (Cell: 01914-201500), Manager, Chattogram Administration.

[Note: Work Order (WO) for installing 20KVA generator at mentioned site has already been mailed on August 18, 2020]

Thanks & Regards,

MD. OHIDUL ISLAM | SPO & Manager | Unit Head: Procurement | Administration Department | Address: Head Office, Eastern Bank Ltd. 100 Gulshan Avenue, Dhaka-1212 | Mobile: 01892575737 | IP Phone 09666777325 Ext-7764.



From: Md. Ariful Islam [<mailto:ariful@cross-world.com>]

Sent: Thursday, August 27, 2020 2:40 PM

To: HO/Admin - Ohidul Islam

Subject: REQUEST FOR PRICING FOR 20 KVA GENERATOR - NEW EBL PREMISES AT KEPZ SUB-BRANCH,
CHATTOGRAM

Importance: High

Dear Sir ,
Please find attached file .

Best Regards,

Ariful Islam | CROSS WORLD POWER LTD | Manager , Sales | | Plot 1/B, Road 90, Gulshan - 2, Dhaka 1212, Bangladesh | p: +880 2 5881 1858, 989 1442 | f: +880 2 5881 5160 | m: +8801755-514731, 01917-702 131 | e: ariful@cross-world.com | w: www.cross-world.com

 please consider the environment before printing this email

Reff : CWPL-AM/5406/20

Date : 27 - August - 2020

TO

Eastern Bank Limited

100, Gulshan Avenue, Dhaka-1000.

Site ID : Karnaphuli EPZ , Chattogram

QUOTATION FOR SUPPLY OF INSTALLATION & COMMISSIONING LOCAL CANOPY , LOCAL ATS & MATERIALS FOR YOUR 20 KVA DIESEL GENERATING SET AT YOUR SITE

Dear Sir

We have since inspected your site and as desired by you we are now pleased to submit below our cost of installation & commissioning materials for your above mentioned genset.

SL NO	JOB DESCRIPTION	TECHNICAL DETAILS/ BRAND	UOM	QTY	UNIT RATE	TOTAL RATE	REMARKS
1	Local Canopy for 20 KVA Genset		Pcs	1	80,000	80,000	
2	Local Auto Transfer Switch (ATS) for 20 KVA Genset		Pcs	1	14,000	14,000	
1	Electrical System:						
1.1	Power Cable (35 °C Ambient on air)	4CX10 rm NYY DG To ATS	Meter	18	138	2,526	
		4CX 10 rm NYY MAINS To ATS		3	138	421	
		4CX 10 rm NYY ATS to LOAD		3	138	421	
1.2	Cable Lugs	10 rm , Material -Copper , Surface-Electro Tinned	Pcs	24	8	200	
1.3	Control Cable for Sensing	4 X 1.2 rm (40/0.19 mm) Flexible Cable (2XDG to ATS)	Meter	37	91	3,316	
1.4	PVC Flexible Pipe	1.5" dia	Meter	24	41	991	
1.5	Saddle for flexible pipe	1.5" dia local	Pcs	30	5	156	
1.6	Royal Plug & Screw	1.5" length	Pack	1	178	178	
1.7	PVC Tape	Adhesive Tape 04 color (Red/Yellow/Black/Blue)	Pcs	8	30	242	
1.8	PIB Tape		Pcs	1	480	480	
1.9	Royal Bolt	10 no.	Pcs	10	19	188	
1.10	Cable Tie	L - 8"	Pack	1	144	144	
1.11	Power Cable Laying & Connection	4CX10 rm NYY Cable	Meter	24	55	1,347	
2	Generator Earthing :				-	-	
2.1	Earthing Boring	80 rft	Job		6,030	-	
2.2	Earthing Copper Lead (Boring)	4 SWG	Meter	N/A	273	-	CLIENT WILL DONE
2.6	GI Pipe	38m dia	Meter		503	-	
2.3	Earthing Cable (Termination)	1 X 6 rm BYA (Green) Earthing pit to Termination Bar	Meter	10	70	703	Tentative
2.4	PVC Flexible Pipe	3/4" dia	Meter	5	47	234	
2.5	Saddle for flexible pipe	3/4" dia local	Pcs	10	3	31	
2.7	Earthing Block	Dimension LXWxD - 200mm X 30mm X 4mm with connection facility	Pc	1	2,056	2,056	
2.9	Earthing Cable lugs	6 rm Material -Copper , Surface-Electro Tinned	Pcs	5	8	42	
3	Exhaust System:				-	-	
3.1	Exhaust Silencer straight Pipe	MS Pipe bore 3", thickness 3mm	Meter	3	1,798	5,394	
3.2	Exhaust Bends /Elbow	Long radius 90 deg L bow 3"	Pcs	2	754	1,508	
3.3	Exhaust Heat Insulation	Insulation Of Pipe with Rockwool (50mm thickness) along with 26SWG Aluminium sheet cladding.	Job	1	2,990	2,990	
3.4	Exhaust Fitting	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM	Job	1	2,035	2,035	
4	Cooling System:				-	-	
4.1	Radiator Ducting	As per layout with 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth etc WXH=2'X1', L- 5ft (Approx)	Sq-ft	40	247	9,875	
5	Commissioning Material:				-	-	
5.1	Radiator coolant	Havoline Premix Coolant	Liter	10	167	1,667	
5.2	Lube oil	SAE 15 W 40	Liter	10	438	4,375	
5.3	Battery electrolyte	Specific gravity 1250	Liter	10	94	938	
6	DG On site delivery:				0	-	
6.1	Loading /Unloading/Lifting	Generator dry weight-1200 Kg	CWPL	Job	1	-	
7	CIVIL WORK:				0	-	
7.1	DG Base for 30kVA DG	Base dimension LXW(ft)=8'x4.3', Depth, D- 4" RCC with NCF.	Client	Job	1	-	
GRAND TOTAL TK (Including VAT & AIT)						136,457	

In Word : one hundred thirty-six thousand four hundred fifty-seven Only

Assuring you of our best services and careful attention at all times, we look forward to receiving your valued work order. Please retain the original and return the copy of this quotation duly sign by you.

N.B : Cost of additional materials required during the commissioning works of the set to be borne by you.

Thanking you.
Yours faithfully
Cross World Power Limited

Md. Ariful Islam
Manager, Sales & Marketing
01755 514 731

We hereby accept the above terms & Conditions

(Signature with Seal)
For and on behalf of
Eastern Bank Limited