

November 8, 2020

To

CROSS WORLD POWER LIMITED

Plot 1/B, Road 90, Gulshan-2,

Dhaka-1212, Bangladesh

Attention: Md. Borhan Uddin

Engineer, Sales

Cross World Power Ltd.

Dear Concern,

With the reference of your submitted quotation, dated November 5, 2020. We are pleased to inform you that, we accepted your offer for supplying of **65 KVA Generator with local canopy and Local ATS as well as Installation & Commissioning materials**, with the following terms & conditions as well as technical specifications as per your offer reference **CWPL-AM/6178/20-R03F**

SL #	Description	Unit	Unit Price BDT	Total Amount BDT
01	TEMPEST Brand 65 KVA (Prime rating) diesel Generator with Perkins engine (U.K),Stamford Alternator (U.K),Control module from Deep-Sea (U.K), Assemble-UK Country of origin : UK Shipment : UK	01	1,060,000	1,060,000
02	Local canopy for 65 KVA			
03	Local ATS for 65 KVA			
04	Installation & Commissioning materials	1 lot	82,598	82,598
			Total	BDT 1,142,598.00

In Word: One Million One Hundred Forty Two Thousand Five Hundred Ninety Eight Only

Payment terms:


1. 30% (BDT 342,779) payment will be paid along with Work Order.
2. 60% (BDT 685,558) payment will be made at the time of delivery and
3. Rest 10% (BDT 114,260) will be paid as PDC (10 days of delivery) along with 2nd payment.

Delivery: The Generator will deliver within 10-15 days from receiving of work order.

Installation & Commissioning: Three (03) days from the date of delivery subject to site is ready to commissioning.

Warranty: Cross World Power Ltd will provide 02 years warranty from the date of commissioning for any manufacturing defects, or any premature wear & tear. Warranty doesn't cover improper maintenance by the user, consumable items, servicing by unauthorized person, running the generator set above its capacity or any unauthorized modification of the generator set.

Thanking you

For, 
Professor A M M Mujibul Haq 10/11/2019

MONEY RECEIPT

CROSS WORLD POWER LIMITED

Cross-world



Ensuring Power Since 1983

No. CWPL/2020-2021/B-

PLOT - 1/B, ROAD - 90, GULSHAN - 02

09

DHAKA - 1212, BANGLADESH

TEL: (880 2) 58811858, 9891442

Fax: (880 2) 58815160

Sl No:

207

Date

Received with thanks from M/s

The sum of Taka (in words)

On Account of

by Cash /Cheque/D.D./P.O. No.

Dated

As Advance/Part/Full Payment against Bill No.

Dated

TK.

342,779/-

This receipt is valid subject to realisation of Cheque/P.O.D.D

Clients Signature

For CROSS WORLD POWER LIMITED

Handwritten signature

IFIC BANK

Payable at any branch in Bangladesh
120261729



680.2 2155

CAL 5891044

DATE

1 0 1 1 2 0 2 0
D D M M Y Y Y Y

Pay To

CROSS WORLD POWER LIMITED

Or Bearer

The Sum of Taka

Three lac forty-two
thousand and seven hundred
seventy nine only.

Tk

342,779/-

A/C No. 0000100545811

A.M. MUJIBUL HAQ

Handwritten signature: Sheila Tasneem Haq

Please Sign Above This Line

5891044 120261729 0000100545811 11

CROSS WORLD POWER LIMITED
BOQ OF 1X65 KVA GENERATOR



CLIENT - Dr. Mojibul Haq

ADDRESS- Baridhara, Dhaka

DATE- 4/11/2020

SL NO	JOB DESCRIPTION	TECHNICAL DETAILS/ BRAND	SCOPE OF SUPPLY	UOM	QTY	UNIT RATE	TOTAL RATE	REMARKS
1	Electrical System:							
1.1	Power Cable (35 °C Ambient on air)	4C-25 rm NYY DG To ATS 4C-25 rm NYY Mains To ATS 4C-25 rm NYY ATS to Load		Meter	8 6 6	1313 1313 1313	10,504 7,878 7,878	
1.2	Power Cable Lugs	25 rm , Material -Copper , Surface -Electro Tinned		Pcs	26	18	468	
1.3	Control cable For Sensing	4 X 1.2 rm (40/0.19 mm)Flexible Cable		Meter	18	90	1,620	
1.4	PVC Flexible pipe	3" dia		Meter	20	237	4,740	
1.5	Saddle for flexible pipe	3.5" dia local		Pcs	20	16	320	
1.6	Royal Plug & Screw	1.5"		Pack	1	171	171	
1.7	PVC Tape	Adhesive Tape 04 color (Red/Yellow/Black/Blue)		Pcs	4	29	116	
1.8	Royal Bolt	10 no.		Pcs	10	18	180	
1.9	Cable Tie	L - 8"		Pack	1	138	138	
1.10	Power Cable Laying	4C-25rm NYY power cable		Meter	20	70	1,400	
2	Generator Earthing :							
2.1	Earthing Boring	80 rft	CLIENT	Job			-	Already Done
2.2	Earthing Copper Lead	2 SWG	CLIENT	Meter			-	
2.3	GI Pipe (Boring)	38mm dia	CLIENT	Meter			-	
2.4	Earthing Block	Dimension LXWXd - 200mm X 30mm X 4mm with connection facility		Pc	1	1974	1,974	
2.5	Earthing Cable	1 X 16 rm BYA (Green) from Earthing pit to Bar & Earthing Copper bar to gen & equipment		Meter	31	176	5,456	
2.6	Earthing Cable lugs	16 rm Material -Copper , Surface -Electro Tinned		Pcs	6	11	66	
3	Exhaust System:							
3.1	Exhaust Silencer straight Pipe	MS Pipe bore 3" ,thickness 3-4mm		Meter	2	1726	3,452	
3.2	Exhaust Bends /Elbow	Long radius 90 deg L bow 3"		Pcs	1	724	724	
3.3	Exhaust Socket	Threaded 3"dia MS Socket		Pcs	1	592	592	
3.4	Exhaust Heat Insulation with silencer box	Insulation Of Pipe with Glasswool (25.4mm min thickness) along with 26SWG Aluminium sheet clading.		Job	1	3010	3,010	
3.5	Exhaust Fitting with silencer box	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM		Job	1	2180	2,180	
4	Cooling System:							
4.1	Radiator Ducting	As per layout with 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth etc WXH=2.5'X2' rft=7'		Sq-ft	63	237	14,931	
5	Commissioning Material:							
5.1	Radiator coolant	Havoline premix coolant		Liter	15	160	2,400	
5.2	Lube oil	SAE 15 W 40		Liter	10	400	4,000	
5.3	Diesel			Liter	100	75	7,500	
5.4	Battery electrolyte	Specific gravity 1250		Liter	10	90	900	
6	DG On site delivery:							
6.1	Loading /Unloading/Lifting	Generator dry weight-2200 Kg	CWPL	Job	1			
7	Civil work							
7.1	Required DG base	Base dimension LXW(ft)=10'6"x5', Depth, D- 3" CC with NCF.	CLIENT	Job	1		-	
TOTAL TK.(Excluding VAT & AIT)							82,598	

NOTES: All the necessary civil works and Diesel Fuel will be arranged by client with CWPL engineer instruction.

Approved