DE/CW/2936/2020°

Date: 17th November 2020

To:

Cross World Power Limited

Plot-1/B, Road-90, Gulshan-2

Dhaka 1212

Attn:

Ariful Islam (Manager, Sales)

Sub:

Work Order for 80 KVA commissioning including materials (Air marshal retd. Abu Esrar

Residence)

Reff:

You're Quotation Dated 17/11/2020 (Quotation Attached)

Dear Mr. Ariful Islam, based on our telephonic conversation & your above-mentioned quotations, I am pleased to place you the following orders stated under.

SL NO	JOB DESCRIPTION	TECHNICAL DETAILS/ BRAND	UNIT	QTY	UNIT RATE	TOTAL	REMARKS
1	Flooring Control	DRAIND		,	KAIE	RATE	100
-	Electrical System:						
1.1	Power Cable (35 °C	4x1C 35 rm NYY DG To	Met	61	407	24827	, = + = -
	Ambient on air)	ATS	er				
1.2	Power Cable Lugs	35 rm , Material -	Pcs	10	24	240	9 - ,
		Copper, Surface-			, , , , , , , , , , , , , , , , , , ,		
		Electro Tinned					
1.3	Power cable laying	1C-35rm cable	Met	61	72	4392	
1 9	charge		er				± ,
1.4	Control cable For	4 X 1.2 rm (40/0.19	Met	31	90	2790	
Υ.	Sensing	mm)Flexible Cable	er		* =		
		(2XDG to ATS)					
1.5	PVC Flexible pipe	3"Ø	Met	14	237	3318	
			er			18 27	
1.6	Saddle for Flexible Pipe	3.5" Ø Local	Pcs	24	16	384	
1.7	Royal Plug	2" length	Pack	02	53	106	
1.8	Star Screw	2"	Pack	02	158	316	
1.5	PVC Tape	Adhesive Tape 04	Pcs	08	29	232	
- 1		color					
, ,		(Red/Yellow/Black/Blu		= =	1 0		
		e)					
1.6	PIB Tape	S	Pcs	01	461	461	
1.7	Royal Bolt	10 no.	Pcs	10	18	180	
1.8	Cable Tie	L - 10"	Pack	02	158	316	
1.9	Cirket breaker	6 A DP	Pcs	01	850	850	; t g



DULAL ENTERPRISE (PVT) LIMITED House # 01 (2nd Floor), Boad # 06, Sector # 01, Uttara Commercial Area, Dhaka, 1230, Bandladosh

House # 01 (2nd Floor), Road # 06, Sector # 01, Uttara Commercial Area, Dhaka-1230, Bangladesh. Mobile: +8801888162392 (Whatsapp/iM) | E-mail : dulalent@gmail.com | Website: www.facebook.com/dulalenterprise

1.1	Cirket breaker	6 A TP	Pcs	01	1513	1513	
1.1	Existing Cable ladder	For cable in and out	Job	01	1000	1000	
1	cutting				± ,		*

SL NO	JOB DESCRIPTION	TECHNICAL DETAILS/ BRAND	UNIT	QTY	UNIT RATE	TOTAL RATE	REMARKS
2	Generator Earthing:						
2.7	Earthing Cable	1C- 25 rm BYA (Green) from Earthing Copper bar to gen & equipment	Met er	5	259	1295	
2.8	Earthing Cable lugs	25 rm Materia l - Copper , Surface - Electro Tinned	Pcs	6	18	108	
3	Exhaust System:						
3.1	Exhaust Silencer straight Pipe	MS Pipe bore 3" ,thickness 3-4mm	Met er	3	1726	5178	
3.2	Exhaust Bends /Elbow	Long radius 90 deg L bow 3" bore	Pcs	1	724	724	
3.3	Exhaust Socket	welding neck flange 3"dia	Pcs	1	592	592	
3.4	Exhaust Heat Insulation with silencer box	Insulation Of Pipe with Rockwool (25.4mm min thickness) along with 26SWG Aluminium sheet clading.	Job	1	4186	4186	
3.5	Exhaust Fitting with silencer box	All bracket, support must be made with MS angle 50X50X 4, 5 & 6 MM	Job	1	3270	3270	
04	Cooling System:						
4.1	Radiator Ducting	As per layoutLXW=2.68'X2.25' rft=8 with 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth etc	Sq-ft	80	237	18960	HOT AIR TOP EXIT
5	Commissioning Material:		- 1				SEKPU

ILAL ENTERPRISE (PV House # 01 (2nd Floor), Road # 06, Sector # 01, Uttara Commercial Area, Dhaka-1230, Bangladesh.

Mobile: +8801888162392 (Whatsapp/iM) I E-mail: dulalent@gmail.com | Website: www.facebook.com/dulalenterprise

5.1	Radiator coolant	Havoline Premix	Liter	15	160	2400	
		Coolent		8			
5.2	Lube oil	SAE 15 W 40	Liter	10	400	4000	
5.3	Battery electrolyte	Specific gravity 1250	Liter	10	90	900	
6	DG On site delivery:			1			
6.1	Loading	Generator dry weight-	Job	1			
	/Unloading/Lifting	2600 Kg					
	Special Discount					2538	
						80000	

Note: Related Civil work and Diesel Fuel will be arranged by Client as per instruction of CWPL Engineer.

Total Taka Eighty Thousand Only.

You are therefore requested to prepare the specified goods and deliver the goods at site within the scheduled time.

With Best regards

Fidah Tahrim Hossain

Deputy Managing Director