



CONCORD READY MIX & CONCRETE PRODUCTS LTD. (UNIT - I)

PLOT NO. - 22, RAMCHANDRAPUR, BERI BADH, MOHAMMADPUR, DHAKA,

Date: 24-Nov-2020

Ref.: RMC - I/2020/11/PO-000055

CROSS WORLD POWER LTD.

HOUSE-NE(O) 06, ROAD-92, GULSHAN-2,
DHAKA-1212

Phone: 8811858,8816528

Fax: 8816205

Account's Copy

Attn: MR. MOSHIUR RAHMAN

Indent Ref. No.: 123638

Sub: Work Order for Supply, Installation, Testing & Commissioning of 500 KVA Oil Type Transformer at Gabtoli.

Dear Sir,

With reference to your Quotation the Management is placed an Order for supply us following materials at Gabtoli. Requisition No.: RQ11-02 000670 dated on 24-Nov-2020 [123638] description given below :

SL	Item Name & Specification	Origin	Brand	Unit	VAT(%)	Tax(%)	Rate	Qty	Amount(BDT)
1	TRANSFORMER [Supply, Installation, Testing & Commissioning of 500KVA, 3 phase, 50 Hz, oil immersed, naturally air cooled transformer, according to IEC 60076-11, VDE 0532 and DIN 42523 standards with off-load tap changer, 3-HT Bushing & 4- LT Bushing, arranged on tank top, conservator, oil level indicator, drain & filling valves, lifting lugs, bi-directional rollers with first filling of oil in transformer for indoor installation. System voltage: 11 KV, Rated Primary voltage: 11 KV, Rated Secondary Voltage: 415V, Tap changing ratio: 0, ± 2.5%, - 5%, - 7.5%, No-load loss: 927 Watt (approx.), Load loss: 5466 Watt (approx.), Silicon core: USA/Japan/Korea, Oil: Electrol/Sabita/Apar, Copper: Singapore/Malaysia/India. Manufactured by Shakti Engineering Ltd.]			SET	5.00		740,000.00	1.00	740,000.00

We offer Excluding VAT and Including AIT. Total Amount = 740,000.00
 Client imposed VAT 5% of 6,72,000 = 33,600 Carrying & Installation =
 for their rules. They will not provide us Discount (9.19 %) = 68,000.00
 VAT challan, But They will deduct VAT = 33,600 VAT = 33,600.00
 Tax =
 Total Payable Amount = 705,600.00

Work Order Amount In Word: (Taka Seven Lac Five Thousand Six Hundred Only)

Terms & Conditions :

- Scope of Work:- Supply, Installation, Testing and Commissioning of the 500 KVA Transformer. Design, Manufacturing, Routine Test & Testing Tolerances According to IEC Standard.
- Fabrication, Assembly, Compliance, Inspection:- Fabrication & Assembly are to be done at your own Factory. All Equipment's supplied under this contract will be Brand New and comply with our requirements & your Offer. Our assigned Electrical Engineer will inspect your Factory for testing and checking Sub-Station Equipment's before taking delivery.
- Payment Type:- Payment will be made 70% account payee by CD Cheque & 30% account payee by 15 days PD cheque along with work order.
- Quality:- You have to maintain specified Brand/Grade Quality & Quantity. Concord reserves the right to reject the materials for below grade/quality. In that case you will take back the materials at your own cost from the Project Site
- Quantity:- Quantity may vary (increase/decrease). Payment to be settled as per actual received quantity.
- Tax:- VAT will be imposed & 2% AIT will be deducted as per Government rules.
- Others:- Concord reserves the right to cancel or change or replace this Work Order any time without giving any reason
- Warranty & After Sales Service:- Warranty & After Sales Service:- Your supplied equipment's are warranted for the period of 12 months. You have to ensure excellent after sales service within minimum response time from the date of Delivery/Commissioning. Any defect during this period will be rectified promptly by repair/replacement at your own cost
- Contact Person:- Mr. Mahdi; Cell: 01922-120683

Ran
24/11/20

24-11-2020

24-11-2020

24-11-20

24/11/20