

## SPACEZERO LTD

House 135, Road 4, Block A, Banani, Dhaka-1213, Phone-55035669-70,71,72

### Work Order

**Work Order No** : 35-8456 **Create Date** : 24 November 2020

**Requisition No** : 35-6759

**Project** : Simpletree Zeenat

**Supplier** : Cross World Power Ltd.  
House #NE (O) 06, Rd # 92, Gulshan-2, Dhaka-1212

**Attention** : Mr. Sohel Uddin Bhuiyan 01755514780

**Subject** : Purchase/Work order against supply of-80 KVA, Diesel Generator system

**Body Title** : In accordance with above subject & negotiation made with you regarding the subjected matter, we are pleased to issue the purchase/ work order against supply, Installation, testing & commissioning of-80 KVA, Diesel Generator system

SL#	Item & Description	Qty.	Unit	Unit Price	Amount (Tk.)
1	Supply,Installation,Testing & Commissioning of 80 KVA Diesel Generator System (Brand & Origin :Tempest, UK, Engine Brand & origin: Perkins, Uk, Generator Model: PS80, Engine Model: 1104A-44TG2, Con. Panel Model: Deepsea, UK, Stand By Capacity: 88KVA, Prime Capacity : 80KVA, Fuel Tank Capacity:200 Ltr, with local body type canopy and ATS.)	1.00	Package	1,424,640.00	1,424,640.00

<i>AIT</i>	<i>Discount</i>	<i>Tax</i>	<i>VAT</i>	<i>Carrying Charge</i>
0.00	124,640.00	0.00	0.00	0.00

**Grand Total :** **1,300,000.00**

**In Words** : One Million Three Hundred Thousand Taka Only

**Start Date** : 24 November 2020 , **Completion Date** : 01 December 2020

**Delivery Address** : Plot No. 77, Block-D, Road No. 13/A, Banani Model Town, Contact Person: Mr.Farooq-01708-132309,Mr.Mamun-01708-132316

**Delay Charge** : N/A

**Warranty** : 18 Month from the date of delivery

**Payment Mode** : 30% payment after 0% completion. Dt:N/A.(1st advance 30% will be made along with work order and rest Payment issues in Remarks )

Md. Shahriar Parvez (Deputy Manager)  
Approved

**N.B** : TDS will be deducted as per government rule.

This Work Order is electronically generated which is valid without signature.

**Remarks**

- : AIT Deduct 2% @ Tk 26,000.00
- Special Note: Cross World Power Ltd. has understood the design & drawing provided by Spacezero Ltd. Cross World Power Ltd. has visited the project and submitted offer accordingly which reconciled all the information. The complete package work of system is BDT. 13,00,000.00 Locked. This amount shall not be exceed upon any situation against all the specifications, quantity, design & drawing agreed by Cross World Power Ltd. & Spacezero Ltd. The quantity can vary up to +/- 10% except major equipment's will not having any impact on the total value.
1. Supply & installation of 400 Volt 3-phase, 50-Hz floor mounted indoor type diesel generating set with 8 hours built in fuel tank, Locl body type canopy in accordance with NEMA/IEC/VDE/JIS standards etc. all complete in all respect as per direction of the Design Consultant.
- a. 80 KVA (prime) Diesel Generator 01 set @ Tk 1,000,000.00
- b. Body Type Canopy for 80 KVA Genset 01 Set @ TK 120,000.00 (Noise level must be at desired level)
2. Auto Transfer Panel (ATS), Brand of Breaker : ABB or Schneider, Europe origin 01 set @ TK 60,000.00 (Supply & installation of 160A ATS Panel with all other necessary accessories including voltmeter, selector switch, indicating lamp etc. Transfer time 6 to 7 seconds.)
3. Supply & installation of Electrical System (Cables & others) Cable sizes .Cable Brand: BRB/BBS. a. Power Cable (DG Set to Feed Unit Panel) 1c x 35mm NYY FRLS 100 Mtr @ TK 45000.00 and 1c x 16mm BYA FRLS (Green), 35 Mtr @ 7,000.00 b. Communication/Control Cable 01 Lot @ TK 2250.00 c. Earthing Bar (CU)L 250mm x W 50mm- 10mm thickness; Installed at wall with rubber bush, Rowl Bolt, Nut, Washer; Cable connection with bar using Cable lugs 2 Set @ TK 4940.00 d. Cable Tray: Construction Material- proper painted Galvanized sheet (with capsule hole, 4mm thick ; Threaded Stick MS/GI for Support with nut bolt. Size: W X D - 250 mm X 50mm 20 Mtr @ TK 57,400.00
4. Supply & installation of Mechanical System (Pipe, Duct & others)
- a. Silencer exhaust 5 Mtr @ Tk 13,800.00, b. Water Tank Made of 3mm M.S. Plate with all necessary points i.e. inlet, cleanout, overflow, base frame, top net etc. Size W1200mm x D800mm x H1500mm, 01 Nos @ 60,000.00, c. Radiator Exhaust :Each Generator radiator exhaust will be taken to GF outside, length for each DG is around 10 meter. Radiator exhaust will be made of 22 gauge galvanized sheet. Size of Radiator will be as per manufacturer standard. 12 Sqm @ Tk 31080.00, d. Exhaust Louver (for 1 x 80 KVA) Aluminium Z-louver @ radiator duct outlet (WXH-3'x3') 1 nos @ Tk 8,670.00
5. Installation, Testing & Commissioning, 01 Lot @ Tk 14,500.00
6. After discount of TK. 124,640.00, the Grand Total price of TK 1,300,000.00
7. The details specifications, quantity and price distribution are attached as Annexure-I.
8. Technical catalogs are attached as Annexure-II.

**TERMS & CONDITION:**

1. MATERIALS: All goods/services are to be supplied according to the description/specifications given in the work order, quotation or approved sample. No discrepancy is acceptable without our

---

Md. Shahriar Parvez (Deputy Manager)  
Approved

**N.B** : TDS will be deducted as per government rule.

This Work Order is electronically generated which is valid without signature.

prior agreement/consent in writing.

2.PRICE: Prices agreed upon the company or in the quotation are final, no changes can be made at any cost.

3.DELIVERY: Delivery must be made within stipulated time and given delivery place.

4.INSPECTION: We reserve the right to inspect the goods to be supplied under this order but such as inspection does not relieve the suppliers of their responsibilities for defects in materials or quantity or workmanship or quality and for delivery of the goods in accordance with the specifications given. The supplier at their expenses shall remove goods rejected by the project Engineer/Incharge.

5.DEDUCTION: Any additional cost will be on supplier's accounts unless otherwise specified.

6.TRANSIT RISK: the suppliers will bear full responsibility for carrying of materials and all costs and expenses shall be on account of the suppliers. Any damage to the goods in transit will be supplier's responsibility.

7.TERMINATION: Spacezero Ltd reserves the right to reject the merchandise if the supplier failed to execute the contract within the stipulated time and as per specification. If the supplier fails to meet above terms and conditions Spacezero Ltd. has every right to impose penalty against sole discretionary power of Spacezero Ltd management

8.Payment: Payment: 1st Instalment: tk. 30% (Tk .390,000.00) as an advance will be paid along with work order a. 2nd Instalment: 40% (Tk. 520,000.00) will be paid to the SECOND PARTY by the FIRST PARTY after materials delivery at site. 3rd Instalment: 25% (TK. 325,000.00) will be paid to the SECOND PARTY by the FIRST PARTY after successful installation, commissioning, balancing hand handover of Diesel Generator Power system. 4th 5 Instalment: 5% (Tk 65,000.00) will be paid to the SECOND PARTY by the FIRST PARTY after 06 months from handover or within one month from the date of handover against submitted bank guarantee f

---

Md. Shahriar Parvez (Deputy Manager)  
Approved

**N.B** : TDS will be deducted as per government rule.

This Work Order is electronically generated which is valid without signature.