

Ref: MAHL/HO/DEERB/VO/CWPL/GEN 250- 355

Date: 03.03.2021

To,

Cross World Power Ltd.  
Plot 1/B, Road 90, Gulshan-2  
Dhaka-1212, Bangladesh.

Attention : Mr. Sohel Uddin Bhuiyan / Manager, Sales & Marketing

**Sub** : Supply, Installation, Testing & Commissioning of 250 KVA Tempest, UK brand diesel generator with foreign made canopy and ATS for the DEERB Project, Uttara, Dhaka

Dear Sir,

We are pleased to issue you work order as per your quotation submitted ref: CWPL-AM/5156/20-R01F dated on 24<sup>th</sup> August 2020 for the above mention project as per following terms and conditions:

Item No.	Description of Equipment	Qty.	Unit Price (GBP)	Total Price (GBP)
01.	<p>Brand New 250KVA Prime &amp; 275 KVA Standby) Diesel Generator at 1500 rpm, 50 Hz, 3 phase, 4 wire, 400/230 volts</p> <p><b>Brand:</b> Tempest, UK</p> <p><b>Engine:</b> Brand: PERKINS Mode: 1206A-E70TTAG3 Country Origine: UK</p> <p><b>Alternator:</b> Brand: Leroy Somer Model: TAL 046 D , Country Origine: France Control Module: Deep Sea, 7320, UK</p> <p>Foreign built in Acoustic Enclosure will reduce the sound level to 75 dBA @ 3 meter Foreign built ATS will be supplied in a suitable steel enclosure wall mounted, fuses with Europe origin magnetic , 4 Pole. All items should be as per approved specifications</p>	06	21,666.67	130,000.00
Total Price ( with C&F Chittagong) in GBP=				130,000.00

(In Word: One Lac Thirty Thousand GBP only.)



**Terms and Conditions**

**Payment Terms:**

- (i) Seller (Cross World Power Ltd.) will arrange Proforma invoice (PI).
- (ii) Buyer (Mir Akhter Hossain Ltd.) will open irrevocable letter of credit (LC) at sight.
- (iii) Government duty, Local transport, loading and unloading are buyer scope.

**Delivery:**

- (i) Shipment will be within 6-8 weeks after open L/C


**Warranty:** 12 months from the date of commissioning and hand over to the client.

**Training:** Necessary local training for operators will be provided free after commissioning of the generator

**Installation, Testing & Commissioning:**

The rate inclusive of the installation and supervision charge, excluding civil works, manual labor and all local materials (like electrical cable ) earthings, Oil, lube oil, ducting, silencer extension pipe for exhaust etc. and others which are not mentioned in the offer required for successful installation, testing & commissioning of the generator.  
Before installation seller will provide working drawing and method statement and should be approved from engineering in charge.

For Mir Akhter Hossain Ltd.

  
Managing Director