



খগ ৭৯১৪০০৫

Director
National Development Engineers Ltd

Harunor Rashid

Purchase Agreement

This Agreement is made on this the Twenty Seven February, Two thousand and twenty one of the Christian era.

BETWEEN

NATIONAL DEVELOPMENT ENGINEERS LTD., House No. 22, Road No.04, Block-C, Banani, Dhaka-1213, hereinafter referred to as the PURCHASER, represented by its Director, Mr. Raihan Mustafizur, which expression where the context so admits, shall include its successors-in-interest and assigns, of the 1st Party.

AND

CROSS-WORLD LTD. Corporate Sales office: Plot 1/ B, Road No. 90, Gulshan, Dhaka-1212, Bangladesh, hereinafter referred to as the SELLERS, represented by its COO, Engr. Md. Harunor Rashid, which expression where the context so admits, shall include its successors-in-interest and assigns of the 2nd Party.

WHEREAS the PURCHASER finds the offer of the SELLERS competitive and acceptable, and finds the price reasonable, and intends to enter into this Agreement for the purchase of 1x600 KVA, 1x250 KVA, 1x500 KVA & 1x60 KVA Diesel Generator with Foreign Canopy, Foreign ATS Panel, Synchronizing panel Exhaust system & others ancillary works as per the enclosed detail drawing, technical specifications, catalogue and following price.

NOW the PARTIES hereto mutually agree as follows:


That both the SELLERS and the PURCHASER agree to fulfill their part of the contract as mentioned hereunder, and the PURCHASER agrees to pay to the SELLERS as per the following terms of payment & conditions:

1 Scope of work

Import, supply, install, test and Commission the 1x600 KVA, 1x250 KVA, 1x500 KVA & 1x60 KVA Diesel Generator with ATS, Synchronizing panel Exhaust & flue system, Generator Fuel oil system & others ancillary for "Dhaka Elevated Expressway PPP Project under Bangladesh Bridge Authority, Dhaka, Bangladesh". (Including Loading, unloading, carrying up to work site of PART - B), complete in all respect, as per enclosed detail technical specifications, Catalogue and drawing.

2 Total Price Ref: Nill, dt-21.01.2021 and subsequently discussion on 03.02.2021 as per following:

Item No.	Name of Equipment	Qty	Unit	Unit Price in GBP	Total Amount in GBP
PART-A : Imported Materials					
	DIESEL GENERATOR				
1. i	Prime Capacity :	600 KVA	1.00	Set	48,100.00
	Generator Set Brand Name :	Tempest			
	Model/Part number :	PL600			
	Country of origin :	UK			
	Manufacture/Assemble Country :	Allam Marine Ltd / UK			
	Shipment country :	UK			
ii.	Engine Brand Name :	Perkins			
	Model/Part number :	2806A-E18TAG1A			
	Country of origin :	USA			
	Manufacture/Assemble Country :	USA			



“দেশপ্রেমের শপথ নিন, দুর্নীতিকে বিদায় দিন”



খগ ৭৯১৪০০৬

Item No.	Name of Equipment	Qty	Unit	Unit Price in GBP	Total Amount in GBP
iii.	Alternator Brand Name :	Leroy somer			
	Model/Part number :	TAL0473E			
	Country of origin :	France			
	Manufacture/Assemble Country :	France			
	Reference catalog :				
iv.	Generator set parallel operation Control Modules :				
	Brand Name :	Deep SeaElectronics (DSE)			
	Model/Part number :	DSE8610MKII			
	Country of origin :	UK			
	Manufacture/Assemble Country :	UK			
v	Gen Canopy Brand Name :	(Tempest) Allam Marine Ltd			
	Country of origin :	UK			
	Manufacture/Assemble Country :	UK			
	Sound Level :	70dBA at 7meter			
2. i	Prime Capacity :	250 KVA	1.00	Set	23,200.00
	Generator Set Brand Name :	Tempest			
	Model/Part number :	PL250			
	Country of origin :	UK			
	Manufacture/Assemble Country :	Allam Marine Ltd / UK			
	Shipment country :	UK			
ii.	Engine Brand Name :	Perkins			
	Model/Part number :	1206A-E70TTAG3			
	Country of origin :	UK			
	Manufacture/Assemble Country :	UK			
iii.	Alternator Brand Name :	Leroy somer			
	Model/Part number :	TAL046D			
	Country of origin :	France			
	Manufacture/Assemble Country :	France			
iv	Generator set parallel operation Control Modules :				
	Brand Name :	Deep SeaElectronics (DSE)			
	Model/Part number :	DSE8610MKII			
	Country of origin :	UK			
	Manufacture/Assemble Country :	UK			
	Reference catalog :				



“দেশপ্রেমের শপথ নিন, দুর্নীতিকে বিদায় দিন”



খগ ৭৯১৪০০৭

Director
National Development Engineers Ltd

Item No.	Name of Equipment	Qty	Unit	Unit Price in GBP	Total Amount in GBP
v	Gen Canopy Brand Name : (Tempest) Allam Marine Ltd				
	Country of origin : UK				
	Manufacture/Assemble Country : UK				
	Sound Level : 70dBA at 7meter				
3	1250A Auto Transfer Switch (ATS)	1.00	Set	12,000.00	12,000.00
	Panel Manufacturer Name : Allam Marine Ltd.				
	Panel Assembler Name : Allam Marine Ltd.				
	Country of origin : UK				
	Shipment country : UK				
	Air Circuit Breaker (ACB) : 2 nos 1250A, 4P				
	Brand Name : ABB				
	Model/Part number : Emax 2				
	Country of origin : Italy				
3. i	Prime Capacity : 500 KVA	1.00	Set	40,700.00	40,700.00
	Generator Set Brand Name : Tempest				
	Model/Part number : PL500				
	Country of origin : UK				
	Manufacture/Assemble Country : Allam Marine Ltd / UK				
	Shipment country : UK				
ii.	Engine Brand Name : Perkins				
	Model/Part number : 2506A-E15TAG2				
	Country of origin : USA				
	Manufacture/Assemble Country : USA				
iii.	Alternator Brand Name : Leroy somer				
	Model/Part number : TAL0473C				
	Country of origin : France				
	Manufacture/Assemble Country : France				
iv	Generator set parallel operation				
	Brand Name : Deep SeaElectronics (DSE)				
	Model/Part number : DSE7320MKII				
	Country of origin : UK				
	Manufacture/Assemble Country : UK				
v	Gen Canopy Brand Name : (Tempest) Allam Marine Ltd				
	Country of origin : UK				
	Manufacture/Assemble Country : UK				
	Sound Level : 70dBA at 7meter				



“দেশপ্রেমের শপথ নিন, দুর্নীতিকে বিদায় দিন”




৳ ৬৯৩৭৯০০

Director
National Development Engineers Ltd.

Director

Item No.	Name of Equipment	Qty	Unit	Unit Price in GBP	Total Amount in GBP
3	800A Auto Transfer Switch (ATS)	1.00	Set	9,500.00	9,500.00
	Panel Manufacturer Name :	Allam Marine Ltd.			
	Panel Assembler Name :	Allam Marine Ltd.			
	Country of origin :	UK			
	Shipment country :	UK			
	Air Circuit Breaker (ACB) : 2 nos	800A, 3P			
	Brand Name :	ABB			
	Model/Part number :	Emax 2			
	Country of origin :	Italy			
3. i	Prime Capacity :	60 KVA	1.00	Set	7,900.00
	Generator Set Brand Name :	Tempest			
	Model/Part number :	PL60			
	Country of origin :	UK			
	Manufacture/Assemble Country :	Allam Marine Ltd / UK			
	Shipment country :	UK			
ii.	Engine Brand Name :	Perkins			
	Model/Part number :	1103A-33TG2			
	Country of origin :	UK			
	Manufacture/Assemble Country :	UK			
iii.	Alternator Brand Name :	Meccalte			
	Model/Part number :	ECP32-2M			
	Country of origin :	UK			
	Manufacture/Assemble Country :	UK			
iv	Generator set parallel operation				
	Brand Name :	Deep Sea Electronics (DSE)			
	Model/Part number :	DSE7320MKII			
	Country of origin :	UK			
	Manufacture/Assemble Country :	UK			
v	Gen Canopy Brand Name :	Tempest (Allam Marine Ltd)			
	Country of origin :	UK			
	Manufacture/Assemble Country :	UK			
	Sound Level :	70dBA at 7meter			
3	100A Auto Transfer Switch (ATS)	1.00	Set	420.00	420.00
	Panel Manufacturer Name :	Allam Marine Ltd.			
	Panel Assembler Name :	Allam Marine Ltd.			
	Country of origin :	UK			
	Shipment country :	UK			



“দেশপ্রেমের শপথ নিন, দুর্নীতিকে বিদায় দিন”



৳ ৬৯৩৭৯০১


Director
National Development Engineers Ltd.

Rushid

Item No.	Name of Equipment	Qty	Unit	Unit Price in GBP	Total Amount in GBP
	Magnetic Contactor (MC) :				
	Brand Name :			Lovato	
	Model/Part number :			BF65T4A230	
	Country of origin :			Italy	
Total Amount =				Part : A	141,820.00
Special discount =					15,820.00
Say Total Amount in GBP=					126,000.00
In Words- GBP One Lac Twenty Six Thousand					

PART-B : Local Materials

Ref. No	ITEM DESCRIPTION	TECHNICAL DETAILS/ BRAND NAME	QTY	Unit	UNIT RATE in TK	TOTAL AMOUNT in TK
1	Supply ,Installation, Testing & Commissioning of Synchronizing Panel		1.00	Set	1,217,268.00	1,217,268.00
	Panel Manufacturer & Assembler Name :	Cross World Limited				
	Country of origin :	Bangladesh.				
	Air Circuit Breaker (ACB) : 1 nos	1000A, 3P				
	Brand Name :	ABB				
	Model/Part number :	Emax 2				
	Country of origin :	Italy				
	Manufacture/Assemble Country :	Italy				
	Shipment country :	Italy				
	Molded Case Circuit Breaker (MCCB) : 1 nos	400A, 3P				
	Brand Name :	ABB				
	Model/Part number :					
	Country of origin :	Italy				
	Manufacture/Assemble Country :	Italy				
	Shipment country :	Italy				
	Air Circuit Breaker (ACB) : 1 nos	1200A, 3P				
	Brand Name :	ABB				
	Model/Part number :	Emax 2				
	Country of origin :	Italy				
	Manufacture/Assemble Country :	Italy				
	Shipment country :	Italy				



“দেশপ্রেমের শপথ নিন, দুর্নীতিকে বিদায় দিন



৬৯৩৭৯১৪

Director
National Development Engineers Ltd.

Ref. No	ITEM DESCRIPTION	TECHNICAL DETAILS/ BRAND NAME	QTY	Unit	UNIT RATE in TK	TOTAL AMOUNT in TK
2	Exhaust System for 600 & 250 KVA					
2.1	Exhaust Silencer straight Pipe	MS Pipe bore 200mm, thickness 3-4mm for 600KVA	10	meter	4,215.00	42,150.00
2.2	Exhaust Bends /Elbow	Long radius 90 deg L bow 200mm bore	3	Pcs	2,019.00	6,057.00
2.3	Exhaust Flange	Welding neck flange 200mm bore	10	Pcs	795.00	7,950.00
2.5	Exhaust Heat Insulation with silencer box for 600KVA.	Insulation Of Pipe with Rockwool/Glasswool (25.4mm min thickness) along with 26SWG Aluminium sheet cladding.	1	Job	29,348.00	29,348.00
2.6	Exhasut Fitting with silencer box for 600 KVA	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM thicness	1	Job	20,436.00	20,436.00
3	Cooling System for 600KVA					
3.1	Radiator Ducting	As per layout with 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth etc. DXW- 5'X7', RFL-10'	180	Sq-ft	217.00	39,060.00
3	Exhaust System: 250KVA					
3.1	Exhaust Silencer straight Pipe	MS Pipe bore 5", thickness 3-4mm	10	Meter	3,411.00	34,110.00
3.2	Exhaust Bends /Elbow	Long radius 90 deg L bow 6" bore	3	Pcs	1,163.00	3,489.00
3.3	Exhaust Bends / Elbow with Flange	Welding neck flange 6" dia	11	Pcs	551.00	6,061.00
3.4	Exhaust Heat Insulation for 5" dia pipe	Insulation Of Pipe with Rockwool (50mm thickness) along with 26SWG GP sheet jacketing	10	Meter	803.00	8,030.00
3.5	Exhaust Heat Insulation for 1nos. silencer box	Insulation Of Pipe with Rockwool (50mm thickness) along with 26SWG GP sheet jacketing	1	Job	3,059.00	3,059.00
3.6	Exhasut Fitting for 5" dia pipe	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM	10	Meter	602.00	6,020.00
3.7	Exhasut Fitting for 1nos. silencer box	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM	1	Job	2,448.00	2,448.00
4	Cooling System:					
4.1	Radiator Ducting	As per layout with 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth etc. (per DG required ducting area) DXW- 4'X2', RL- 10'	120	Sq-ft	217.00	26,040.00
1	Exhaust System for 1X500 KVA					
1.1	Exhaust Silencer straight Pipe	MS Pipe bore 152mm, thickness 3-4mm for 500KVA	10	meter	3,750.00	37,500.00



“দেশপ্রেমের শপথ নিন, দুর্নীতিকে বিদায় দিন”



৬৯৩৭৯১৫

Director
National Development Engineers Ltd

৬৯৩৭৯১৫

Ref. No	ITEM DESCRIPTION	TECHNICAL DETAILS/ BRAND NAME	QTY	Unit	UNIT RATE in TK	TOTAL AMOUNT in TK
1.2	Exhaust Bends /Elbow	Long radius 90 deg L bow 152mm bore	3	Pcs	1,323.00	3,969.00
1.3	Exhaust Flange	Welding neck flange 152mm bore	6	Pcs	782.00	4,692.00
1.4	Exhaust Heat Insulation with silencer box for 500KVA.	Insulation Of Pipe with Rockwool/Glasswool (25.4mm min thickness) along with 26SWG Aluminium sheet clading.	1	Job	21,302.00	21,302.00
1.5	Exhaust Fitting with silencer box for 600 KVA	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM thicness	1	Job	15,716.00	15,716.00
2	Cooling System for 1X500KVA					
2.1	Radiator Ducting	As per layout with 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth etc. DXW-5'X7', RFL-10'	180	Sq-ft	217.00	39,060.00
	Earthing cable Lugs	120mm Material- copper, Surface-Electro Tinned	10	Pcs	91.00	910.00
1	Exhaust System for 60 KVA					
1.1	Exhaust Silencer straight Pipe	MS Pipe bore 4", thickness 3-4mm	10	meter	1,806.00	18,060.00
1.2	Exhaust Bends /Elbow	Long radius 90 deg L bow 4" bore	2	Pcs	795.00	1,590.00
1.3	Reducer	3" to 4"	1	Pcs	673.00	673.00
1.4	Exhaust Heat Insulation	Insulation Of Pipe with Rockwool/Glasswool (25.4mm min thickness) along with 26SWG Aluminium sheet clading.	1	Job	6,017.00	6,017.00
1.5	Exhaust Fitting	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM thicness	1	Job	4,817.00	4,817.00
2	Cooling System for 1X60KVA					
2.1	Radiator Ducting	As per layout with 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth etc. DXW-2.1'X2.1', RFL-8'	67	Sq-ft	217.00	14,539.00
Total Amount =					Part : B	1,620,371.00
Special discount =					13.60%	220,370.46
Total Amount In TK. Excluding Vat & AIT)						1,400,000.54

3 Terms of Payment :

PART - A Imported Materials

- 1st party will open LC (PI Ref21-03, Date: 10.02.2021)
- 2nd party will send Proforma Invoice to 1st party within 03 days from the date of signing of the agreement.
- Payments by 100% irrevocable L/C at sight
- All kind of cost related to Custom duty and taxes & delivery at site will be done by 1st party





৬৯৩৭৯১০

Director
National Development
Engineers Ltd.

Rashid

PART - B Local Materials

- Taka 6,00,000/= (Six lac) payment will be made before one month of the generator to reach at site.
- Taka 2,00,000/= (Two lac) payment shall be made after arrival of goods at site
- R/A bill will be made as per work progress.
- Final bill will be adjusted based on practical measurement/quantity of items after successfully testing & Commissioning.
- Taka 300,000/= (Three Lac Taka only) shall be made after twelve months from the date of handover or within one month from the date of commissioning against submitted bank guarantee for 12 month.

4 Engineering design drawings :

- Engineering design drawings (ATS, Sync, panel Exhaust system, Fuel oli & acoustic system on duct or exhaust pipe) will be supplied by 2nd party within 10 (ten) working days from the date of signing of the agreement.
- 2nd party will submit detail design drawing to 1st party/client for approval. After approval 2nd party will go for production as per SL 9 terms & Condition.

5 Delivery of equipment and completion of project

- Factory QC inspection (Foreign part) within 60 (Sixty) days from the date of signing of the Agreement.
- Factory QC inspection (Local Assemble part) within 45 (Fourty Five) days from the date of signing of the Agreement.
- Local Assemble part arrive at site within 60 (Sixty) days from the date of signing of the Agreement.
- Installation of Generatot & Local materials part within 140 (one hundred and Fourty) days from the date of signing of the Agreement.
- Testing, Commissioning of the whole generator within 150 (one hundred and Fifty) days from the date of signing of the Agreement.

6 Warranty

2nd party will be liable to replace any component/item of this Generator, ATS, Canopy & Panel, Generatot fuel line, flue gas exhaust line, Radiator duct etc. with all related component for manufacturing defects, wrong installation upto a period of 12 (twelve) months from the date of issue of virtual completion certificate.

7 After sales service

2nd party will provide free maintenance services for 12 (twelve) months from the date of handing over to "Dhaka Elevated Expressway PPP Project under Bangladesh Bridge Authority, Dhaka, Bangladesh".

8 Specification

Detailed Technical Specification, Catalogue of the Generator, ATS canopy with Panel, Fuel line components are attached with the agreement and shall be treated as Part of this agreement. Any deviation in the Specification will not be accepted Enclosed Page No.1 to

9 Special terms & Condition

- 2nd party will fully liable to ATS & Synchronizing panel Cable and termination to busbar etc all complete.
- 2nd party will fully liable for Generator sound level 70dBA @7 meter from any point of generator room exterior wall.
- 2nd party will fully liable for generator room fresh air intake and hot air discharge for cross ventilation and generator better performance in 100% load.
- 2nd party will submitt all type of materials (Part-B) sample for approval. After approval of sample from 1st party/Client, 2nd party will purchase the materials and go for production.
- All Generator silencer should be residential type.
- 2nd party will submitt to 1st party all imported materials factory test report/factory acceptance test report/brosure etc before commissioning.



“দেশপ্রেমের শপথ নিন, দুর্নীতিকে বিদায় দিন”



৳ ৬৯৩৭৯০৮

vii) The special discount percentage is applicable for all item Part -B, if any item quantity increase or decrease percentage will be same.

viii) All kind of civil works done by 1st party.

ix) All kind of cost relevant to FAT (Foreign part- A) will be borne by 1st party but all necessary paper with invitation letter arrange by 2nd party minimum six persons.

x) 2nd party (local supplier) representative must be present during FAT.

IN WITNESS WHEREOF the Parties hereto sign and execute this Agreement on the aforementioned date.

PURCHASER (First Party)

[Signature]
 Raihan Mustafiz
 Director
 National Development Engineers Ltd.
 House No.10, Road No.90
 Gulshan, Dhaka-1212, Bangladesh.

SELLER (Second Party)

[Signature]
 Engr. Md. Harunor Rashid
 COO
 CROSS-WORLD LTD
 Corporate Sales office,
 Plot 1/ B, Road No. 90,
 Gulshan, Dhaka-1212, Bangladesh

In the presence of:

1. Name: *Ashim Kumar Paul*
 Address: *A#22, R#4, BL#2
 Barani, Dhaka-143.*

1. Name: *Md. Sahab Uddin*
 Address: *NDE*

1. Name: *Md. Helal Hossain*
 Address: *NDE*

1. Name: *Md. Shamsul Alam*
 Address: *Sr. Manager, Sales*

1. Name: *Md. Sohel Uddin Bhuiyan*
 Address: *Manager, Sales*

1. Name: *MD. HABIBUR RAHMAN*
 Address: *MANAGER, CRM*

Report Header

Application: Alliance Message Management
Report type: Message Preparation - Message Details Report
Operator: GCBSALMAN
Alliance Server Instance: SAA_Live
Date - Time: 2021/03/02 16:19:42

Message

Start of Message

Message Identifier

Message Preparation Alliance Message Management - Message Creation
Application:

Message Header

Swift	Input	fin.799	FIN MT799 - Free Format Message
FIN			
Sender			
Unit:		GCB	
Sender Logical Terminal:		TTBLBDDHX	
Type:		Institution	
Institution:		TTBLBDDH016	
Receiver			
Type:		Institution	
Institution:		SCBLGB2LXXX	
Address Expansion			
Institution:		STANDARD CHARTERED BANK	
Branch:		(ALL U.K. OFFICES)	
City:		LONDON	
Country:		GB	
Options			
Priority:		Normal	
Monitoring:		None	
User PDE:		No	

Message Text

F20: Transaction Reference Number

235721020008

F21: Related Reference

779113359659-R

F79: Narrative

REFER TO OUR MT 700 DATED 18.02.2021 PLEASE READ THE FOLLOWING CORRECTION:
1. FIELD 42C: READ '360 DAYS FROM THE DATE OF BILL OF LADING BUT PAYMENT WILL BE MADE AT SIGHT' INSTEAD OF EXISTING.
2. FIELD 44E: READ 'ANY PORT OF U.K' INSTEAD OF EXISTING.
3. FIELD 44F: READ 'CHATTOGRAM BANGLADESH BY SEA' INSTEAD OF EXISTING.
4. FIELD 45A: READ 'COUPLED' INSTEAD OF COUPLES.
5. FIELD 45A: READ 'FREIGHT CHARGE: GBP 4220.00' INSTEAD OF EXISTING.
6. FIELD 45A: READ 'CFR CHATTOGRAM BANGLADESH' INSTEAD OF EXISTING.
7. FIELD 46A SERIAL 05: READ 'CERTIFICATE OF ORIGIN IN ONE ORIGINAL AND ONE COPY ISSUED BY ANY CHAMBER OF COMMERCE OF THE BENEFICIARY'S COUNTRY

CERTIFYING THAT THE SHIPPED GOODS ARE OF U.K
ORIGIN' INSTEAD OF EXISTING.
8. FIELD 47A SERIAL 02: READ 'EMAIL
TARIQUL(AT)NDEBD.COM' INSTEAD OF COURIER.
9. FIELD 47A SERIAL 15: READ 'FROM THE DATE OF
BILL OF LADING' INSTEAD OF ACCEPTANCE.

REGARDS.
F.TRADE DEPT.
TBL/GCB.

Network Data

Network: SWIFT

End of Message

Report Footer

Number of Entities: 1
End of report

Report Header

Application: Alliance Message Management
Report type: Instance Search - Detailed Report
Operator: GCBALMAN
Alliance Server Instance: SAA_Live
Date - Time: 2021/02/23 11:10:47

Report Content

Reprint From MFA-0000-000000

Instance Type and Transmission

Notification

(Transmission) of Original sent to SWIFT (ACK)

Network Delivery Status: Network Ack
Priority/Delivery: Normal
Message Input Reference: 1822 210218TTBLBDDHA0161856494678

Message Header

Swift Input: FIN 700 Issue of a Documentary Credit
Sender: TTBLBDDH016
TRUST BANK LTD., THE
(GULSHAN CORPORATE BRANCH)
DHAKA
Receiver: SCBLGB2LXXX
STANDARD CHARTERED BANK
(ALL U.K. OFFICES)
LONDON GB

BD

Message Text

F27: Sequence of Total
Number: 1/
Total: 1
F40A: Form of Documentary Credit
IRREVOCABLE
F20: Documentary Credit Number
235721020008
F31C: Date of Issue
210218 2021 Feb 18
F40E: Applicable Rules
Applicable Rules: UCP LATEST VERSION
F31D: Date and Place of Expiry
Date: 210508 2021 May 08
Place: IN U.K.
F51A: Applicant Bank - Party Identifier - Identifier Code
Identifier Code:
TTBLBDDH016
TRUST BANK LTD., THE
(GULSHAN CORPORATE BRANCH)
DHAKA BD
F50: Applicant
NATIONAL DEVELOPMENT AND ENGINEERS
LIMITED. HOUSE-20/A, ROAD-44,
GULSHAN-2, DHAKA-1212, BANGLADESH.
F59: Beneficiary
Name and Address:
ALLAM MARINE LTD.
WYKE WAY, MELTON, HULL, HU14 3BQ,
ENGLAND, TEL: 01482 636300.
F32B: Currency Code, Amount
Currency: GBP POUND STERLING
Amount: 126000, #126000, #

F41A: Available With ... By ... - Identifier Code - Code

Identifier Code:

SCBLGB2L

STANDARD CHARTERED BANK
(ALL U.K. OFFICES)
LONDON GB

Code:

BY ACCEPTANCE

F42C: Drafts at ...

360 DAYS FROM THE DATE OF
ACCEPTANCE BUT PAYMENT WILL BE
MADE AT SIGHT.

F42A: Drawee - Party Identifier - Identifier Code

Identifier Code:

TTBLDDH016

TRUST BANK LTD., THE
(GULSHAN CORPORATE BRANCH)
DHAKA BD

F43P: Partial Shipments

ALLOWED

F43T: Transshipment

ALLOWED

F44E: Port of Loading/Airport of Departure

ANY UNITED KINGDOM SEA PORT

F44F: Port of Discharge/Airport of Destination

CHATTOGRAM SEAPORT, BANGLADESH BY SEA

F44C: Latest Date of Shipment

210417

2021 Apr 17

F45A: Description of Goods and/or Services

BRAND NEW TEMPEST SPECIFICATION DIESEL GENERATING SETS
COMPRISING OF A PERKINS ENGINE COUPLES TO A LEROY SOMER OR MECC
ALTE ALTERNATOR RATED FOR PRP DUTY @ 400V 3 PHASE 50HZ IN
ACCORDANCE WITH OUR STANDARD AUTOSTART SPECIFICATION.

FREIGHT CHARGE: GBP 4220.

H.S.CODE: 8502.13.00, 8502.12.00, 8502.11.00.

TOTAL GBP 126000.

CFR CHATTOGRAM SEAPORT, BANGLADESH BY SEA.

DESCRIPTION, SPECIFICATION, QUALITY, QUANTITY, UNIT PRICE AND ALL
OTHER TERMS AND CONDITIONS ARE STRICTLY AS PER SUPPLIER'S
PROFORMA INVOICE NO. CW21-03 DATED 10.02.2021.

F46A: Documents Required

01. BENEFICIARY'S SIGNED DRAFTS IN DUPLICATE DRAWN ON STANDARD
CHARTERED BANK, UK (SWIFT CODE: SCBLGB2L) FOR FULL
INVOICE VALUE.

02. BENEFICIARY'S SIGNED COMMERCIAL INVOICE IN QUADRUPPLICATE
CERTIFYING THAT THE SHIPPED GOODS ARE OF U.K ORIGIN.

03. FULL SET OF CLEAN SHIPPED ON BOARD MARINE BILL OF LADING
3/3 ISSUED TO THE ORDER OF 'TRUST BANK LIMITED, GULSHAN
CORPORATE BRANCH, DHAKA, BANGLADESH' MARKED 'FREIGHT PREPAID'
NOTIFY 'ISSUING BANK' AND 'APPLICANT' GIVING FULL ADDRESS.

04. BENEFICIARY'S SIGNED PACKING LIST IN TRIPLICATE.

05. CERTIFICATE OF ORIGIN IN DUPLICATE ISSUED BY ANY CHAMBER OF
COMMERCE OF THE BENEFICIARY'S COUNTRY CERTIFYING THAT THE
SHIPPED GOODS ARE OF U.K ORIGIN.

06. BENEFICIARY'S CERTIFICATE STATING THAT THE SHIPPED GOODS ARE
STRICTLY AS PER L/C TERMS AND AS PER PROFORMA INVOICE SHALL
ACCOMPANY THE ORIGINAL SHIPPING DOCUMENTS FOR NEGOTIATION.

07. INSURANCE COVERED BY THE APPLICANT. ALL SHIPMENT UNDER THIS
CREDIT MUST BE ADVISED BY BENEFICIARY DIRECTLY TO: STANDARD
INSURANCE LIMITED, UTTARA BRANCH, H.M. PLAZA (12TH FLOOR), ROOM
NO-6/B, PLOT NO-34, ROAD NO-02, SECTOR-03, UTTARA C/A,
DHAKA-1230, E-MAIL: UTTARA BR@STANDARDINSURANCE.COM.BD REFERRING
THEIR COVER NOTE NO. SIL/UB/MC-0037/02/2021 DATED 15.02.2021
AND OUR L/C NUMBER. A COPY OF SUCH ADVICE SHOULD ACCOMPANY THE
ORIGINAL SHIPPING DOCUMENTS.

F47A: Additional Conditions

01. ALL SHIPPING DOCUMENTS (EXCEPT CERTIFICATE OF ORIGIN) MUST

APPEAR THE FOLLOWING:

A. L/C NUMBER: 235721020008 DATED: 18.02.2021.

B. IRC NO: OLD = BA-0206983.

NEW = 260326120329820.

C. LCA NO: TBL-I-51039.

D. H.S CODE: 8502.13.00, 8502.12.00, 8502.11.00.

E. ISSUING BANK BIN NO: 000215909-0101.

F. APPLICANT'S TIN NO: 187583824166.

G. APPLICANT'S BIN NO: 000422137-0101.

02. ONE COMPLETE SET OF NON NEGOTIABLE DOCUMENTS ALONG WITH DETAILS PACKING LIST AND COPY OF CERTIFICATE OF ORIGIN MUST BE SENT TO THE APPLICANT WITHIN 10 (TEN) BANKING DAYS FROM THE DATE OF SHIPMENT BY COURIER AND BENEFICIARY'S CERTIFICATE TO THIS EFFECT MUST ACCOMPANY THE ORIGINAL SHIPPING DOCUMENTS.

03. BENEFICIARY SHOULD CERTIFY IN THE COMMERCIAL INVOICES THAT THE QUALITY, QUANTITY, UNIT PRICE AND OTHER PARTICULARS OF THE GOODS SUPPLIED ARE STRICTLY IN CONFORMITY WITH PROFORMA INVOICE.

04. AN AMOUNT EQUIVALENT OF USD 90.00 WILL BE DEDUCTED FROM THE BILL PROCEEDS PRESENTED WITH DISCREPANCY(IES). HOWEVER, THIS DOES NOT CONSTITUTE AN AUTOMATIC ACCEPTANCE OF THE DISCREPANT DOCUMENTS BY US.

05. AN AMOUNT EQUIVALENT OF USD 50.00 WILL BE DEDUCTED FROM THE BILL PROCEEDS AS BILL PAYMENT CHARGES.

06. PACKING SHOULD BE EXPORT STANDARD.

07. SHORT FORM, BLANK BACKED, STALE BILL OF LADING NOT ALLOWED.

08. FREIGHT CHARGE AND FOB VALUE OF GOODS MUST BE SHOWN SEPARATELY IN THE INVOICE.

09. IMPORTER'S NAME, ADDRESS, TIN BIN NO MUST APPEAR ON AT LEAST 2 PERCENT OF TOTAL PACKAGES/CARTONS OF THE GOODS. BENEFICIARY'S CERTIFICATE IN THIS REGARD MUST ACCOMPANY WITH THE ORIGINAL DOCUMENTS.

10. SHIPMENT/TRANSHIPMENT THROUGH ISRAELI FLAG/VESSEL OR PORT IS NOT ALLOWED.

11. ALL DOCUMENTS MUST BE MADE IN ENGLISH VERSION.

12. DOCUMENTS HAVING DATE PRIOR TO LC OPENING DATE IS NOT ACCEPTABLE.

13. THIRD PARTY DOCUMENTS EXCEPT INVOICE & DRAFT IS ACCEPTABLE.

14. A CERTIFICATE ISSUED BY THE BENEFICIARY STATING THAT THE GOODS ARE BRAND NEW AND HAVE BEEN TESTED IN ACCORDANCE WITH ISO8528 AND ARE SUPPLIED WITH ALLAM MARINE STANDARD WARRANTY.

15. ALTHOUGH THE TENOR OF THE LC IS AT 360 DAYS FROM THE DATE OF ACCEPTANCE, STANDARD CHARTERED BANK, U.K (SWIFT: SCBLGB2L) IS AUTHORIZED TO DISCOUNT AND PAY THE BILL VALUE TO THE BENEFICIARY AT SIGHT BASIS AFTER RECEIPT THE COMPLYING PRESENTATION FROM BENEFICIARY OR BENEFICIARY'S BANK AT STANDARD CHARTERED BANK, U.K COUNTER SUBJECT TO RECEIVING ACCEPTANCE FROM LC ISSUING BANK. DISCOUNTING AND CONFIRMATION CHARGES ARE ON APPLICANT'S ACCOUNT AND WILL BE PAID ON MATURITY.

F71D: Charges

ALL BANK CHARGES OUTSIDE BANGLADESH INCLUDING ADVISING AND REIMBURSEMENT CHARGES ARE ON BENEFICIARY'S ACCOUNT BUT ADD CONFIRMATION AND DISCOUNTING CHARGES ARE ON APPLICANT'S A/C.

F48: Period for Presentation in Days

Days: 21

Narrative: /WITHIN THE L/C VALIDITY.

F49: Confirmation Instructions

WITHOUT

F53A: Reimbursing Bank - Party Identifier - Identifier Code

Identifier Code:

SCBLGB2L

STANDARD CHARTERED BANK
(ALL U.K. OFFICES)
LONDON GB

F78: Instructions to the Paying/Accepting/Negotiating Bank

BENEFICIARY MUST PRESENT DOCUMENTS TO STANDARD CHARTERED BANK,
U.K FOR NEGOTIATION AND SCB u.k, WILL FORWARD THE NEGOTIATED
DOCUMENTS BY COURIER SERVICE TO: TRUST BANK LIMITED, GULSHAN
CORPORATE BRANCH, 53 GULSHAN AVENUE, GULSHAN-1, DHAKA-1212,
BANGLADESH. NEGOTIATING BANK IS AUTHORIZED TO CLAIM REIMBURSEMENT
FOR THE AMOUNT OF NEGOTIATION ON DUE DATE/AT MATURITY TO OUR USD
ACCOUNT MAINTAINED SCB U.K (SWIFT:SCBLGB2L) FIVE (05) WORKING
DAYS PRIOR TO CLAIMING SUCH REIMBURSEMENT THE NEGOTIATING BANK
SHALL ADVISE US BY AUTHENTICATED SWIFT AND IN CASE OF DISCREPANT
DOCUMENT NEGOTIATING BANK SHOULD NOT NEGOTIATE DOCUMENTS WITHOUT
OUR PRIOR APPROVAL.

F57A: 'Advise Through' Bank - Party Identifier - Identifier Code

Identifier Code:

LOYDGB2L

LLOYDS BANK PLC
(U.K. INTERNATIONAL SERVICES)
LONDON GB

F72Z: Sender to Receiver Information

THIS CREDIT IS ISSUED SUBJECT TO
UNIFORM CUSTOMS AND PRACTICE FOR
DOCUMENTARY CREDIT (2007 REVISION)
ICC PUBLICATION NO.600

Message Trailer

{CHK:C3C7830D2543}

PKI Signature: MAC-Equivalent

Interventions

formatted_interventions

Category : Network Report
Creation Time : 18/02/21 18:26:29
Application : SWIFT Interface
Operator : SYSTEM
Text
{1:F21TTBLBDDHA0161856494678}{4:{177:2102181822}{451:0}}

End of Message

Report Footer

Number of Entities:

1

End of report

21.1.21

To

The Managing Director
National Development & Engineers Ltd.
House # 06, Road # 90, Gulshan # 02,
Dhaka-1208

Dear Sir

Greeting from Cross world Power Limited. Please find the below summary offer for your kind consideration:

Description of Package B		Manufacturer	Qty		Currency	Unit Price	Total Price in (GBP)	Total Price in BDT
1	TEMPEST Brand 600 KVA (Prime) Rating Diesel Generator with Perkins engine and Leroy Somer alternator, with DSE-8610 sync controller without Breaker & Foreign Canopy	Tempest, UK	1	nos	GBP	48,100	48,100	
2	TEMPEST Brand 250 KVA (Prime) Rating Diesel Generator with Perkins engine and Leroy Somer alternator, with DSE-8610 sync controller without Breaker with Foreign Canopy	Tempest, UK	1	nos	GBP	23,200	23,200	
3	TEMPEST Brand 500 KVA (Prime) Rating Diesel Generator with Perkins engine and Leroy Somer alternator, with DSE-7320 controller & Breaker with Foreign Canopy	Tempest, UK	1	nos	GBP	40,700	40,700	
4	TEMPEST Brand 60 KVA (Prime) Rating Diesel Generator with Perkins engine and Meccalte alternator	Tempest, UK	1	nos	GBP	7,900	7,900	
5	1250A 4P auto-transfer switch (ATS) with 2nos 1250A 4P ACB and incoming & outgoing cable termination point. FOR 2 DG (600KVAX1 & 400KVAX1)	Tempest, UK	1	Job	GBP	12,000	12,000	
6	800A TP auto-transfer switch (ATS) with 2nos 800A TP ACB and incoming & outgoing cable termination point. FOR 1 DG (500 KVAX1)	Tempest, UK	1	Job	GBP	9,500	9,500	
7	Foreign ATS for 60KVA	UK	1	nos	GBP	420	420	
8	Supply, installation, testing and commissioning of locally assembled Generator Panel/Synchronizing Panel consisting of 1 no. motorized paralleling TP ACB (1000A) & 1 no. motorized paralleling TP MCCB/ACB (400A) in incoming side and 1 no. 1250A TP ACB in outgoing side, 2500A TPN&E copper busbar including digital metering, indicating lamp, control cable all other necessary accessories	CWPL	1	Job	BDT			1,150,000
9	Exhaust System for 2 DG Set & Installation materials (2x800KVA + 1x400KVA+1x500KVA+1x250KVA)	CWPL	1	Job	BDT			403,000
TOTAL PRICE OF PACKAGE-B (Excluding VAT & AIT) in BDT & GBP.							141,820	1,553,000
(Less) Special discount							12820	155,300
TOTAL PRICE OF PACKAGE-B (Excluding VAT & AIT) in BDT & GBP.							129,000	1,397,700

Md. Sohel Uddin Bhuiyan
Manager (Sales)
Cros world Power Limited

= 126000
= 126000
Rashed 31/2/21

CROSS WORLD POWER LIMITED									
BOQ OF 250kVA GENERATOR									
CLIENT -NDE (PACKAGE-B)			ADDRESS- GULSHAN-1			DATE- 05.10.19			
GEN MODEL-		ENGINE MODEL-		ALTERNATOR MODEL-					
SL NO	JOB DESCRIPTION	TECHNICAL DETAILS/ BRAND		SCOPE OF SUPPLY	UOM	QTY	UNIT RATE	TOTAL RATE	REMARKS
1	Electrical System:								
1.1	Power Cable (35 °C Ambient on air)	1C-185 rm NYY DG To ATS		Client	Approx. Meter	N/A		0	
1.9	Cable Ladder	300X50 mm Made with 37x37x5 mm MS angle & 37x5 mm flatbar with painting. Support with threaded stick MS/GI rod, lock nut bolt and washer.		Client	Meter Approx.	N/A	-	-	
1.10	Cable Laying system	Cable laying and termination system			Meter	-	-	-	
1.3	Control cable For Sensing	4X 1.2 rm (40/0.19 mm) Flexible Cable			Meter Approx.	40	-	-	-
2	Earthing System						-	-	
2.1	Earth Inspection Pit	L X W X D- 600x600x600 mm with Brick, 100mm thick RCC slab with 400mm CI manhole		Client	Nos.		-	-	
2.2	Earthing Boring	1nos, 30m boring depth					-	-	
2.3	GI Pipe (Boring)	38.1mm Dia G.I. Pipe with accessories					-	-	
2.4	Earthing Copper Lead (Boring)	Installation of solid cooper wire earthing lead 2 SWG in 38.1 mm dia GI pipe & termination of connection at both end			Meter	N/A	-	-	
	Earthing Copper Lead (Termination)	Installation of solid cooper wire earthing lead 2 SWG in 38.1 mm dia GI pipe & termination of connection at both end					-	-	-
3	Exhaust System:						-	-	
3.1	Exhaust Silencer straight Pipe	MS Pipe bore 5", thickness 3-4mm			Meter	10	3,411	34,112	
3.2	Exhaust Bends /Elbow	Long radius 90 deg L bow 6" bore			Pcs	3	1,163	3,488	
3.3	Exhaust Bends / Elbow with Flange	Welding neck flange 6" dia			Pcs	11	551	6,056	
3.4	Exhaust Heat Insulation for 5" dia pipe	Insulation Of Pipe with Rockwool (50mm thickness) along with 26SWG GP sheet jacketing			Meter	10	803	8,026	
3.5	Exhaust Heat Insulation for 1nos. silencer box	Insulation Of Pipe with Rockwool (50mm thickness) along with 26SWG GP sheet jacketing			Job	1	3,059	3,059	
3.6	Exhasut Fitting for 5" dia pipe	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM			Meter	10	602	6,017	
3.7	Exhasut Fitting for 1nos. silencer box	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM			Job	1	2,448	2,448	
4	Cooling System:						-	-	
4.1	Radiator Ducting	As per layout with 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth etc. WXD-4'X2'; RFT-10'			Sq-ft	120	217	26,040	
5	Commissioning Material:						-	-	
5.4	Fuel	Diesel For Test Run		Client	Liter	N/A	-	-	
6	DG On site delivery:						-	-	
6.1	Loading /Unloading/Lifting	Generator dry weight-4200 Kg		CWPL	Job	1	-	-	
7	Civil Work						-	-	
7.1	DG Foundation	DG CC foundation WXLXH-16.5'X6'X3"		Client	Job	1	-	-	
TOTAL TK.(Excluding VAT & AIT)								89245.59	

Note:
-- All necessary civil work will done by client as per CWPL engineer instruction.

Client Name: NDE (Package B)		Address:		Date:				
Gen Model:		Engine Model :		Alternator Model :				
SI No	Job Description	Tehcnical Details/ Brand	Scope Of Supply	Unit	Quantity	Unit Rate	Total Rate	Remarks
1	Electrical System for 1X500kVA							
1.1	Generator Power Cable (35 °C in air)	8X1C - 185 mm2 NYY DG to ATS 8X1C -185 mm2 NYY ATS to LT 8X1C -185 mm2 NYY ATS to LOAD	CLIENT	Meter	TBA	-	-	As discussed with client
1.4	Cable Laying Charge	1X185 mm2 NYY Power Cable		Meter	TBA		-	
1.10	Cable Ladder	600 X 50 mm Made with 37x37x5 mm MS angle & 37x5 mm flatbar with painting. Support with threaded stick MS/GI rod, lock nut bolt and washer.	CLIENT	Meter	-	0	-	As discussed with client
1.2	Control cable for sensing	4 X 1.2 rm (40/0.19 mm)Flexible Cable		Meter	50		-	
2	Generator Earthing for 1X500kVA						-	
2.1	Earthing Boring	100 rft		Job			-	
2.2	Earthing Copper Lead	2 SWG		Meter			-	
2.3	GI Pipe	38mm dia GI pipe		Meter			-	
2.4	Earthing Copper Lead termination	2 SWG		Meter			-	
2.5	PVC Flexible pipe for earthing	3/4" inner dia		Meter			-	
2.6	Earhting Block	Dimension LXWXD - 300mm X 50mm X 10mm with connection facility		Pcs			-	
2.7	Earthing Cable	1CX 120 mm2 BYA (Green) from Earting Copper bar to gen & equipment for 1X500 Kva		Meter	TBA		-	
2.8	Earthing Cable lugs	120 rm Material -Copper , Surface-Electro Tinned		Pcs	10	91	905	
3	Exhaust System for 1X500kVA						-	
3.1	Exhaust Silencer straight Pipe	MS Pipe bore 152 mm , thickness 3-4mm		Meter	10	3,750	37,500	
3.2	Exhaust Bends/Elbow	Long radius 90 deg L bow dia 152 mm Bore		Pcs	3	1,323	3,970	
3.3	Exhaust Flange	Welding neck flange 152 mm Bore			6	782	4,692	
3.4	Exhasut Fitting with Silencer box	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM		Job	1	15,716	15,716	
3.5	Exhaust Heat Insulation with silencer box	Insulation Of Pipe with Rockwool/Glasswool (25.4mm min thickness) along with 1 mm Aluminium sheet clading.		Job	1	21,302	21,302	Tentative as discussed with client
4	Cooling Systems for 1X500kVA						-	
4.1	Radiator Hot Air Ducting	WXH- 5'X4'; rft=10'; Made With 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth, Iron mesh etc for 2X500 Kva.		Sq-ft (Approx.)	180	217	39,060	
5	Commissioning Material for 1X500kVA						-	
5.4	Fuel for tial run	2 hrs / 5 day trial run operation by skilled operator with supply of necessary fuel as per manufacturers instruction. @ 75% load	Client	Liter	N/A	-	-	
6	DG On site delivery						-	
6.1	Loading /Unloading	Generator dry weight- 4700Kg for 500Kva with foreign canopy	CWPL	Job	1	-	-	Standard case only
7	Civil Works						-	
7.1	Generator Foundation for 500Kva with foreign canopy	Base dimension (LXW)ft-12'2"X4'8.5 D-6" RCC with NCF.	Client	Job	1	-	-	As per approved drawing
Total Tk --(Excluding VAT & AIT)						123,146		

Note: Related Civil work will be done by Client as per instruction of CWPL Engineer.

CROSS WORLD POWER LIMITED
BOQ OF 1X60KVA GENERATOR

CLIENT -NDE (Package-B)		ADDRESS-		DATE- 30.12.19				
GEN MODEL-		ENGINE MODEL-		ALTERNATOR MODEL-				
SL NO	JOB DESCRIPTION	TECHNICAL DETAILS/ BRAND	SCOPE OF SUPPLY	UOM	QTY	UNIT RATE	TOTAL RATE	REMARKS
1	Electrical System:							
1.1	Power Cable (35 °C Ambient on air)	1C 25rm NYY DG to ATS 1C 25rm NYY MAINS to ATS 1C 25rm NYY ATS toLOAD	Cleint	Meter			-	
1.10	Power Cable Laying	25rm NYY Power Cable Laying & Installation work.		Meter	N/A	-	-	
1.2	Control cable For Sensing	4 X 1.2 rm (40/0.19 mm)Flexible Cable			40		-	
2	Generator Earthing :					-		
2.1	Earthing Boring	100rft	Cleint	Job	N/A	-	-	
2.2	Earthing copper lead	4 SWG		Meter		-	-	
2.3	Earthing copper lead termination	4 SWG		Meter		-	-	
2.4	GI Pipe	38mm inner dia		Meter		-	-	
2.5	Earth Inspection Pit	LxWxD- 600x600x600 mm with Brick, 100mm thick RCC slab with 400mm CI manhole		Job		-	0	
2.6	Earthing Cable	1C 16 rm BYA (Green) from Earthing Copper bar to gen & equipment		Meter		-	-	
3	Exhaust System:					-		
3.1	Exhaust Silencer straight Pipe	MS Pipe bore 4" ,thickness 3-4mm		Meter	10	1,806	18,061	
3.2	Exhaust Bends /Elbow	Long radius 90 deg Elbow 4" bore		Pcs	2	795	1,590	
3.3	Reducer	3"to 4"		Pcs	1	673	673	
3.4	Exhaust Heat Insulation	Insulation of Pipe with Rockwool (25.4mm min thickness) along with 26SWG Aluminium sheet cladding.		Job	1	6,017	6,017	Box fitting & insulation considered inside of canopy
3.5	Exhaust Fitting	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM		Job	1	4,817	4,817	
4	Cooling System:					-		
4.1	Radiator Ducting	(WXH) inch- (2.1'X2.1') Feet L-8 FT As per layout with 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth, iron net mesh etc		Sq-ft	67	217	14,539	
5	Commissioning Material:					-		
5.4	Diesel for test run	50% of tank capacity	Client	Liter	N/A	-	-	
07	Civil works:					-	-	
7.3	CC Foundation	LXWXD- 114" X50" X 6" DG base will made by CC	Client	Job	1	-	-	
TOTAL TK.(Excluding VAT & AIT)							45,698	

Note:All required civil work will be done by client. (All materials quantity may vary . Bill will be claim at actual.)

CROSS WORLD POWER LIMITED

Client Name: NDE (PACKAGE-B)

1X250kVA & 1X600kVA DG - SYNC PANEL

SL No.	DG Spares: Repair/Service Items	UOM	Qty	Unit Price	Total Price	Remarks
1	Sheet steel clad powder coated (14/16 SWG, dust and vermin proof, free standing, floor mounting, 415V, 50 Hz, Indoor type Generator Synchronizing Panel with 2000A hard drawn copper busbar	Set	2	50,667	101,333	
	Dimension/Size : (H-2000 X W-700 X D-800)mm					
2	Common Copper Busbar WXD: (150mm X 10)mm (2.0 A/mm ²)	Meter	7	16,486	115,405	
3	Terminal Copper Busbar for 400A MCCB WXD: (32mm X 8)mm	Meter	3	2,814	8,441	
	Terminal Copper Busbar for 1000A TP ACB WXD: (80mm X 10)mm	Meter	3	8,793	26,378	
4	Terminal Copper Busbar for 1250A TP ACB WXD: (80mm X 10)mm	Meter	4	8,793	35,171	
5	FOR INCOMING					
6	1000A 65 kA TP Fixed type ACB with closing solenoid and store -energy spring charged operating mechanism and solid state microprocessor controlled adjustable thermal overload and short-circuit releases with following accessories:	No	1	200,000	200,000	
	1 X Closing Coil					
	1 X Gear motor for spring charge					
	1 X Under Voltage Release					
	Brand : ABB					
7	630A 50 kA TP fixed type motorized MCCB	No	1	192,000	192,000	
	1 X Motor mechanism					
	1 X Under Voltage Release					
	1 X Auxiliary					
	Brand : ABB					
6	FOR OUTGOING					
	1250A 65 kA TP Fixed type ACB with closing solenoid and store -energy spring charged operating mechanism and solid state microprocessor controlled adjustable thermal overload and short-circuit releases with following accessories:	No	1	234,000	234,000	
	1 X Closing Coil					
	1 X Gear motor for spring charge					
	1 X Under Voltage Release					
	Brand : ABB					
9	Heatshrink tube	Meter	20	324	6,480	
7	Indicating Lamp (open, close, trip)	Nos.	6	329	1,973	
9	Emergency Button	Nos.	2	2,055	4,110	
10	Buzzer Button	Nos.	2	644	1,288	
11	Auto/Man selector	Nos.	2	2,219	4,438	
12	Phase Indicating lamp RYB	Nos.	6	329	1,973	
13	ON OFF Push Button	Nos.	2	2,055	4,110	
15	Digital Multi function Meter, Schneider DM6000 -	Nos.	1	9,886	9,886	
16	1600/5A Current Transformer 10/5VA, Class-1 -	Set	3	2,599	7,797	
19	Connection Accessories	Set	1	71,653	71,653	
Total Amount (BDT)					1,026,435	