

**FINANCIAL OFFER**

Rahmat Spinning Mills Ltd. (Rahmat Group)  
Senakalyan Bhaban (14th floor), 195  
Motijheel, Dhaka-1000.

DATE : Mar 23, 2021  
REF : CWPL-AM/0665/21-R01F

**FINANCIAL OFFER FOR SUPPLY OF 60 KVA 3 PHASE HEAVY DUTY DIESEL GENERATING SETS.**

Dear Sir,

We are pleased to submit our financial offer with reference to our technical offer# CWPL-AM/0665/21-R01T dated Mar 23, 2021 :

**1. Price:**

| SL # | Product Name                                                                                                                                                                                                                                                                                                                 | Unit | Price (BDT) | Qty. | Total Price(BDT) |
|------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|-------------|------|------------------|
| 1)   | TEMPEST Brand 60 KVA (Prime) Rating Diesel Generator with Perkins engine and Mecc-Alte alternator<br>BRAND : Tempest<br>ENGINE : Perkins, UK<br>ALTERNATOR : Mecc Alte, UK<br>CONTROL MODULE : Deepsea, UK<br>PORT OF SHIPMENT : Felixstowe port, UK<br>AVAILABILITY : 5 to 15 days from ready stock subject to availability | Set  | 900,000.00  | 1.00 | 900,000.00       |
| 2)   | Local Canopy for 60 KVA Genset                                                                                                                                                                                                                                                                                               | Pcs. | 95,000.00   | 1.00 | 95,000.00        |
| 3)   | Local Auto Transfer Switch (ATS) for 60 KVA Genset                                                                                                                                                                                                                                                                           | Pcs. | 30,000.00   | 1.00 | 30,000.00        |
| 4)   | Commissioning Materials for 2X60 KVA DG (As per Attached)                                                                                                                                                                                                                                                                    | Lot  | 139,846.00  | 1.00 | 139,846.00       |

Total Price (Ready Stock) in BDT 1,164,846.00

**GRAND TOTAL (Excluding VAT & AIT) in BDT 1,164,846.00**

Amount in words : BDT One Million One Hundred and Sixty-Four Thousand Eight Hundred and Forty-Six Only.



**CROSS WORLD POWER LIMITED**  
**BOQ OF 2X60KVA GENERATOR**

Bahela Hospital

ADDRESS- Sirairgonj

DATE- 23/03/2021

**Cross-world**

| SL NO                           | JOB DESCRIPTION                           | TECHNICAL DETAILS/ BRAND                                                                                               | SCOPE OF SUPPLY | UOM   | QTY | UNIT RATE | TOTAL RATE | REMARKS            |
|---------------------------------|-------------------------------------------|------------------------------------------------------------------------------------------------------------------------|-----------------|-------|-----|-----------|------------|--------------------|
| 1                               | Electrical System:                        |                                                                                                                        |                 |       |     |           |            |                    |
| 1.1                             | Power Cable (35 °C Ambient on air )       | 4C-35 rm NYV DG-1 To MCOS-1<br>4C-35 rm NYV DG-2 to MCOS-2<br>4C-35 rm NYV Mains to MCOS & MCOS to Load done by client |                 | Meter | 11  | 2,103     | 22,445     |                    |
| 1.2                             | Power Cable Lugs                          | 35 rm, Material -Copper , Surface-Electro Tinned<br>4 X 1.2 rm (40/0.19 mm)Flexible Cable                              | Client          | Pcs   | N/A |           | 16,032     |                    |
| 1.3                             | Control cable For Sensing                 | (2XDG to ATS)                                                                                                          |                 | Meter | 18  | 24        | 432        |                    |
| 1.4                             | PVC Flexible pipe                         | 3" dia                                                                                                                 |                 | Meter | 37  | 90        | 3,293      |                    |
| 1.5                             | Saddle for flexible pipe                  | 3.5" dia local                                                                                                         |                 | Meter | 20  | 237       | 4,740      |                    |
| 1.6                             | Royal Plug & Screw                        | 1.5"                                                                                                                   |                 | Pcs   | 25  | 16        | 400        |                    |
| 1.7                             | PVC Tape                                  | Adhesive Tape 04 color (Red/Yellow/Black/Blue)                                                                         |                 | Pack  | 2   | 171       | 342        |                    |
| 1.8                             | Royal Bolt                                | 10 no.                                                                                                                 |                 | Pcs   | 12  | 29        | 348        |                    |
| 1.9                             | Cable Tie                                 | L- 8"                                                                                                                  |                 | Pcs   | 10  | 18        | 180        |                    |
| 1.10                            | Power Cable Laying                        | 4C-35rm NYV power cable                                                                                                |                 | Pack  | 3   | 138       | 414        |                    |
| 2                               | Generator Earthing :                      |                                                                                                                        |                 | Meter | 18  | 59        | 1,079      |                    |
| 2.1                             | Earthing Boring                           | 80 ft.                                                                                                                 |                 | Job   | 2   | 7237      | 14,474     |                    |
| 2.2                             | Earthing Copper Lead                      | 2 SWG                                                                                                                  |                 | Meter | 52  | 419       | 21,716     |                    |
| 2.3                             | GI Pipe (Boring)                          | 38mm dia                                                                                                               |                 | Meter | 14  | 483       | 6,762      |                    |
| 2.4                             | Earthing Block                            | Dimension LXWXD - 200mm X 30mm X 4mm with connection facility                                                          |                 | Pc    | 2   | 1974      | 3,948      | Client can be done |
| 2.5                             | Earthing Cable                            | 1 X 16 rm BYA (Green ) from Earthing Copper bar to gen & equipment                                                     |                 | Meter | 12  | 222.55    | 2,671      |                    |
| 2.6                             | Earthing Cable lugs                       | 16 rm Material -Copper , Surface-Electro Tinned                                                                        |                 | Pcs   | 12  | 11        | 132        |                    |
| 3                               | Exhaust System:                           |                                                                                                                        |                 |       |     |           |            |                    |
| 3.1                             | Exhaust Silencer straight Pipe            | MS Pipe bore 3" ,thickness 3-4mm                                                                                       |                 | Meter | 7   | 1726      | 12,082     |                    |
| 3.2                             | Exhaust Bends /Elbow                      | Long radius 90 deg L bow 3"                                                                                            |                 | Pcs   | 2   | 724       | 1,448      |                    |
| 3.3                             | Exhaust Socket                            | Threaded 3"dia MS Socket                                                                                               |                 | Pcs   | 4   | 592       | 2,368      |                    |
| 3.4                             | Exhaust Heat Insulation with silencer box | Insulation Of Pipe with Glasswool (25.4mm min thickness) along with 26SWG Aluminium sheet cladding.                    |                 | Job   | 1   | 5600      | 5,600      |                    |
| 3.6                             | Exhaust Fitting with silencer box         | All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM                                                    |                 | Job   | 1   | 4340      | 4,340      |                    |
| 4                               | Cooling System:                           |                                                                                                                        |                 |       |     |           |            |                    |
| 4.1                             | Radiator Ducting                          | As per layout with 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth etc WXH=3'X2.3' L=9'                       |                 | Sq-ft | N/A |           |            | Hot air FRONT Exit |
| 5                               | Commissioning Material:                   |                                                                                                                        |                 |       |     |           |            |                    |
| 5.1                             | Radiator coolant                          | Havoline premix coolant                                                                                                |                 | Liter | 30  | 160       | 4,800      |                    |
| 5.2                             | Lube oil                                  | SAE 15 W 40                                                                                                            |                 | Liter | 20  | 400       | 8,000      |                    |
| 5.3                             | Battery electrolyte                       | Specific gravity 1250                                                                                                  |                 | Liter | 20  | 90        | 1,800      |                    |
| 6                               | DG On site delivery:                      |                                                                                                                        |                 |       |     |           |            |                    |
| 6.1                             | Loading /Unloading/Lifting                | Generator dry weight-2200 Kg                                                                                           | CWPL            | Job   | 1   |           |            |                    |
| 7                               | Civil work                                |                                                                                                                        |                 |       |     |           |            |                    |
| 7.1                             | Required DG base                          | Base dimension LXW(ft)=9'4"x4'4", Depth, D- 5" RCC with NCF.                                                           | CLIENT          | job   | 1   |           |            |                    |
| TOTAL TK. (Excluding VAT & AIT) |                                           |                                                                                                                        |                 |       |     |           | 139,846    |                    |

NOTES: All the necessary civil works and Diesel Fuel will be arranged by client with CWPL engineer instruction.