

PURCHASE ORDER

GP House
Bashundhara, Baridhara
Dhaka
BD
1229
Phone No: +88029882990
Fax No: +88029882970

Order No.: 60004515
Release No.: 0
Date: 25-APR-2021
Agreement No: GP-04983
PR Nos.: 50029187
Department: Tower & Infra
Operations.Technology

Supplier Name: CROSS WORLD LTD.
Address: HOUSE-NE(O)-06, ROAD-92,
GULSHAN-2
DHAKA
1000
Telephone:
Fax:
E-mail:
Communication E-mail: ariful@cross-world.com

S.No	Item	Item Description	Delivery Date	Unit of Measure	Qty	Unit Price (BDT)	Total (BDT)
1	40077219	ALUMINIUM LADDER 40MM---- CHINA/INDIA/BANGLADESH	31-AUG-2021	Each	160 0	261.36	418,176.00
2	40077215	32 A MCB (SP) - 6KA	31-AUG-2021	Each	260	352.30	91,598.00
3	40077216	1X120 RM (61W), PVC CABLE NYY	31-AUG-2021	Each	100	1,413.75	141,375.00
4	40077217	1X240 RM (37W), NYY, (BBS, BRB, PARADISE)	31-AUG-2021	Each	265 1	2,811.90	7,454,346.90
5	40077218	1X95 RM (19W), BYA, GREEN COLOR	31-AUG-2021	Each	150	1,021.80	153,270.00
Total Price(BDT)							8,258,765.90

Please deliver the above equipment, materials or services as per agreed terms & conditions given below.

Delivery Terms: As per agreement.

Delivery Mode: As per Agreement

Place of Delivery: As per agreement

VAT/TAX: As per Agreement

Work Completion Letter: As per Agreement

Payment Terms: As per agreement

Termination/Revision: As per Contract

Packing: As per Agreement

Invoice: To be Prepared as per GP Instruction

Certificate: N/A

Payment Schedule: As per agreement

Inspection: N/A

Penalty on Delay: As per agreement

Warranty: As per agreement



Authorized Signature



Authorized Signature

Note: Please sign and return the confirmation copy by fax/ mail.

SL No	Item Name	Description	Unit	Quantity	Rate	Total Amount	Remarks
1	1600 A MCCB (TP) - Adjustable - 50kA	1600 A MCCB (TP) - Brand: ABB, DM smith, Legrand (UK/EU) approved by GP	Each	9	140,921	1,268,293	Actual delivery - 6 nos
2	Busbar upgradation	Busbar rating upgradation to 1500A in MDB at 2F and 3F	Each	2	77,100	154,199	
3	1600A- On load Manual Changeover Switch	1600A- On load Manual Changeover Switch by 03 nos ACB 1600A & will have mechanical interlocking ACB Brand : ABB, schneider, Legrand, Made in UK/EU	Each	6	85,366	512,195	Actual delivery - 5 nos & another one will be Havells Manual Changeover
4	1250 A MCCB (TP) - Adjustable - 50kA	1250 A MCCB (TP) - Brand: ABB, DM smith, Legrand (UK/EU) approved by GP	Each	7	93,225	652,575	
5	630A TPN -Uro-Load/ On Load Manual Changeover Switch Brand : Socumac/ Havells Made in India/China-Best Quality	630A TPN - Uro-load/On load Manual Changeover Switch Brand : Socumac/ Havells Made in India/China-Best Quality	Nos	4	73,171	292,683	Actual delivery - 6 nos
6	SDB: Distribution Board	SDB: Distribution Board , 4' x 4' x 12", Material 16 SWG MS sheet with 14 SWG Sheet door (Half Door should be perforated), which includes digital voltmeter with selector switch, 3 indicating lamp, bus bars fitted in the DB as phase, neutral & earth bar & fitting fixing of one incoming MCCB & outgoing MCB, colored heat sink tube for Bar, 3p/1p connected with malingering 3 phase distribution bars with proper color code jumper cable & necessary cable lug for incoming & outgoing. All outgoing cable will go outside of the DB through the bottom portion of the DB through the proper size PVC cable glands / approved Design. DB must be of powder coating painting with birch grey color. An extra cover with back side fire roof insulation & SS hinge will be three - cover will be pressing type locked (Double) Magnetically / approved Design. The bottom side of the DB must be of DUSTPROOFED.	Nos	7	54,034	378,237	
7	630 A MCCB (TP) - Adjustable - 50kA	630 A MCCB (TP) - Brand: ABB, DM smith, Legrand (UK/EU) approved by GP	Each	16	39,024	624,390	It may be 400 A MCCB
8	Surge Reduction Filter (SRF)	Surge Reduction Filter, SRF 400A or Above rating	No.	4	797,727	3,190,909	
9	SDB: Distribution Board	SDB: Distribution Board ,36"/40" x20"/24" x 12", Material 16 SWG MS sheet with 14 SWG Sheet door (Half Door should be perforated), which includes digital voltmeter with selector switch, 3 indicating lamp, bus bars fitted in the DB as phase, neutral & earth bar & fitting fixing of one incoming MCCB & outgoing MCB, colored heat sink tube for Bar, 3p/1p connected with malingering 3 phase distribution bars with proper color code jumper cable & necessary cable lug for incoming & outgoing. All outgoing cable will go outside of the DB through the bottom portion of the DB through the proper size PVC cable glands / approved Design. DB must be of powder coating painting with birch grey color. An extra cover with back side fire roof insulation & SS hinge will be three - cover will be pressing type locked (Double) Magnetically / approved Design. The bottom side of the DB must be of DUSTPROOFED.	No.	4	49,156	196,623	
10	250 A MCCB (TP) - Adjustable - 36kA	250 A MCCB (TP) - Brand: ABB, DM smith, Legrand (UK/EU) approved by GP	Each	10	15,989	159,892	

11	20 A MCB (SP) - 6kA	20 A MCB (SP) - Brand: ABB, DM smith, Legrand (UK/EU) approved by GP	Each	-	352	-
12	32 A MCB (SP) - 6kA	32 A MCB (SP) - Brand: ABB, DM smith, Legrand (UK/EU) approved by GP	Each	180	352	63,415
13	1X150 rm (37w) NYFF, DC power cable	1X150 rm (37w), NYFF; DC power cable	Meter		3,225	-
14	1X240 rm (61w) NYFF; DC power cable	1X240 rm (61w), NYFF; DC power cable	Meter		5,150	-
15	1X120 rm (61w), PVC cable NYY	1X120 rm (61w), PVC cable NYY (BBS, BRB, Paradise anyone brand)	Meter	100	1,414	141,375
16	SDB: Distribution Board for Aircon	SDB: Distribution Board for Aircon of main incoming 250A MCCB, outgoing of 24 nos 32A, TP, MCB integrated with 24V DC relay and MC for auto switch off during fire detection system (CB, MC, relay prices aren't included). The main MCCB will be 02 in each DB, power of one CB will be from same floor and another will be from another floor and both the CB will be manually ineterlocked to throw anyone power to the busbar	No.	2	76,563	153,125
17	Magnetic Contact 32A, TP	Magnetic Contact 32A, TP, Made in Togami/Siemens/Schneider	Nos	48	3,523	169,106
18	250 A MCCB (TP) - Adjustable - 36kA	250 A MCCB (TP) - Adjustable - 36kA	Nos	2	15,989	31,978
19	32 A MCB (TP) - 6kA	20 A MCB (TP) - Brand: ABB, DM smith, Legrand (UK/EU) approved by GP	Each	48	1,626	78,049
20	1X240 rm (37w), NYY, (BBS, BRB, P	1X240 rm (37w), NYY, (BBS, BRB, Paradise)	Meter	2,651	2,812	7,454,347
21	1X95 rm (19w), BYA, green color	1X95 rm (19w), BYA, green color	Meter	150	1,022	153,270
22	Aluminium ladder 40mm----China/India/Bangladesh	Aluminium ladder 40mm----China/India/Bangladesh	RFT	1,600	261	418,182
23	Roxtec module RM 15W40	Roxtec module with removable layer, RM 15W40, external dimension (HxW): 15x40mm	Each	192	2,716	521,432
24	Roxtec module RM 20W40	Roxtec module with removable layer, RM 20W40, external dimension (HxW): 20x40mm	Each	192	2,716	521,432
25	Roxtec module RM 60	Roxtec module with removable layer, RM 60, external dimension (HxW): 60x60mm	Each	48	2,716	130,358
26	Roxtec module RM 80	Roxtec module with removable layer, RM 80, external dimension (HxW): 80x80mm	Each	96	2,716	260,716
27	Roxtec wedge Kit unit	Roxtec wedge unit, wedge Ex AISI 316 - highly efficient compression unit for roxtec module installation. The components are galvanized kit with wedge clip and lubricant	Each	48	22,632	1,086,316
28	Roxtec galvanized B Frame 6X4	Roxtec galvanized Frame, B6x1C Ex GALV; dimension (HxW): 218x220mm	Each	12	101,389	1,216,674
29	Installation accessories for electrical works	Installation accessories with lugs, PIB tape, tie, marking etc	LS	1	70,588	70,588
30	Installation Service for electrical works	Installation Service for above materials	LS	1	58,824	58,824
31	750KVA generator relocation	Dismantling of 750KVA DG with ATS, silencer box, pipe, ducting and reinstallation of those including new ducting and new fuel pipe connection from new fuel tank in new location	Nos	1	500,000	500,000
32	High capacity AVR relocation	800/1000KVA AVR dismantling, inter district transportaion, installation and commissioning	EACH	2	47,059	94,118

Actual delivery 300 mm MS Galbalanized Ladder - 800 ft

33	Diesel refilling system for generator	Supply and installation of refilling system that stores fuel in existing fuel tanks of 03 generators. The system will facilitate diesel refilling from truck parked at road on site.	EACH	1	243,902	243,902
34	High electrical resistant and non conductive insulation mats	High electrical resistant and non conductive insulation mat for substation and AVR room	Sq Meter	200	1,625	325,000
35	Installation Service for insulation mats	Installation Service for above materials	Sq Meter	200	235	47,059