



Please supply in accordance with the following condition/s :

SL	Code	Item	Category	Prep No.	Quantity	Unit Rate	Value
1	020005514	Canopy Work	Supply & Installation	P202101D00028NP	1.000 Unit	60,00,000.000 BDT	60,00,000.000
Usage Type - Common, Inventory Type - Need Basis, Part no - , Import or Local - Local-Dhaka							
Delivery date : 05/06/2021 12:00, Quantity : 1.000 Unit							

Gross Total : 60,00,000.000
Less Discount :
Other Charge: .000
Total : 60,00,000.000

Total (In Words) : Sixty Lac BDT

Terms and conditions :

1. The Company reserves all rights to cancel the Work Order any time if final delivery does not comply with the approved sample / specification.
2. Bill to be submitted along with a copy of the order after delivery of item/s or completion of services. Please quote our Work Order no. on all correspondences, Challan, Invoice, Advice, notes etc.
3. All admissible taxes, VAT etc. will be deducted from bills according to Govt. Rules.
4. N.B. : Advance Tk. 10,00,000.00 will be paid after delivery the Materials and rest amount will be paid after complete the job.

Received By :

Date :

Authorised By :

(Sr. Manager, Commercial)

Date :

FINANCIAL OFFER

Opsonin Pharma Limited
30, New Eskaton Road, GPO Box # 2962,
Dhaka-1000

DATE : May 02, 2021
REF : CWPL-AM/0356/21-R02F

FINANCIAL OFFER FOR SUPPLY AND INSTALLATION OF ROOM CANOPY WITH NEW SETUP

Dear Sir,

We are pleased to submit our financial offer with reference to our technical offer# CWPL-AM/0356/21-R02T dated May 02, 2021 :

1. Price:

SL #	Product Name	Unit	Price (BDT)	Qty.	Total Price(BDT)
1)	Supply And Installation Of Room Canopy for 01 Nos DG (with New setup)	Set	2,262,637.00	1.00	2,262,637.00
2)	Supply And Installation Of Room Canopy for 02 Nos DG (with New setup)	Set	4,352,995.00	1.00	4,352,995.00

Total Price (Ready Stock) in BDT 6,615,632.00

Special Discount (615,632.00)

GRAND TOTAL (Excluding VAT) in BDT 6,000,000.00

Amount in words : BDT Six Million Only.

CROSS WORLD POWER LTD

2. PAYMENT TERMS: 1) 100% at the time of work order.

3. DELIVERY: Within 5 to 15 days from the date of your valued work order, subject to availability of stock

4. VALIDITY: This offer is valid for 30 days from the date of this offer.

We hope the above offer is acceptable to you and we look forward to your valued work order in our favour. Should you require further information or discussion, please feel free to contact the undersigned.

Sincerely,

Arunangshu Paul

Manager, Sales & Marketing

Mobile : 01755 514 747

CROSS WORLD POWER LIMITED**BOQ of 1X1250kVA (ONE ROOM) GENERATOR ROOM ACOSTIC TO ATTAIN 80dba @ 3m****For ENR-05**

SI No	Job Description	Tehcnical Details/ Brand	UOM	QTY	REMARKS
1	Room Canopy Work:				
1.1	Radiator hot air Acoustic Panel for 1250kVA	Supply & installtion of radiator front side hot air passing and sound proof system louver box with ladder system pertitions and will be both sides glass wool, cover by mesh wire iron net. Glasswool thickness 4 inch. Box size –Height-96in X Wide 102in X Depth – 60in.	Nos	2	
1.2	Fresh Air inlet Acoustic Panel	Supply & installation of sound proof air inlet box fresh air inlet on the room with ladder system pertitions and will be both sides glass wool, cover by mesh wire iron net. Glasswool thickness 4 inch. The Main front louver must be dust proofing system. Box size - Hight -108inX Width - 108in X Depth– 54in	Nos	2	
1.3	Acoustic Door	Supply & installation of sound proof frame system door. Inside will have glasswool insulation & purported sheet. Door size- Height – 84 inch X Width – 60 inch X Deep – 10 inch.	Pcs	1	
1.4	Acoustic Lining In Roof	Roof will be sound proof U channel Glasswool and Purporated Sheet. Glasswool thickness 2inch.	Sq-ft	N/A	
1.4	Acoustic Lining In wall	Roof will be sound proof U channel Glasswool and Purporated Sheet. Glasswool thickness 2inch.	Sq-ft	1220	
1.6	Ventilation Fan [Inlet]	36" inner dia drum fan, CFM-20000, Brand- LOCAL	Pcs	2	
	Acoustic box for Ventialtion Fan	Acoustic Lining in both side of fan. Material- 14 SWG MS, 3" thick Glasswool & Iron Net with Louver. DIM: WXH- 4'X4'	Pcs	2	
1.7	Ventialtion Fan Motor Starter Panel (Delta)	Supply, installation, testing and commissioning 2NOS 4KW motor control panel with DELTA STARTER starter with necessary internal wiring.	Set	1	
1.8	Exhaust Silencer Box (Residential Type)	Supply & installation of Residential type Silencer Box, axial Incoming pipe dia- 10" (Single) & axial out outgoing pipe dia - 10" (single). Insertion loss 35-40 dBA.	Pcs	4	
1.9	Existing canopy dismantle	Existing induvidual floor mounted canopy dismantle	Job	2	
1.9	Delivery & Installation		Job	1	