

General Services Division

AIBL/HO/GSD/2021/1110

Date: 06-06-2021

The Managing Director
Cross World Limited.
House- NE (0) 06, Road-92
Gulshan-2
Dhaka-1212.

Sub: Work Order for supply, installation, testing & commissioning of 01 (one) unit 20 KVA (prime output). 3 Phase 4 Wire Forestcity, UK Diesel Generator with foreign ATS & Local Canopy.

Muhtaram,

Assalamu Alaikum

In connection to your tender price and subsequent negotiation, we would like to inform you that our management has been pleased to issue a work order for supply, installation, testing & commissioning of 01 (one) unit 20 KVA (Prime output) Forestcity, UK brand generator at Jhenaidah Branch, Jhenaidah as per following specifications, terms & conditions:

| S/N | Description | Rate | Qty. | Amount |
|---|---|------------------|------|---------------|
| 01 | → <u>Brand</u> : Tempest, <u>Country of origin</u> : UK, <u>Model</u> : PS20/PM20 → <u>Engine</u> : PERKINS, UK <u>Country of origin</u> : UK, <u>Engine Model</u> : 404A-22G1, 404D-22G, 4 Stroke Diesel Engine, Mechanical Governor, Foreign made Silencer → <u>Prime output</u> : 20 KVA → <u>Stand by Output</u> : 21.5 KVA → <u>Alternator Brand</u> : Stamford/Meccalte, <u>Country of origin</u> : Italy/UK, <u>Model no</u> : P144D, ECP28-M4,SOL2-G1, Rotation-1500 rpm, Power Factor-0.8 , three phase 400V/230V, 50 Hz, Automatic Voltage Regulator → <u>ATS</u> : Tempest, <u>Country of origin</u> : UK, <u>Brand of Magnetic contactor</u> : ABB/Equivalent → <u>Canopy</u> : Local, <u>Sound Level</u> : 70-75 db(A) at 07, <u>Fuel Consumption at 75% load</u> : 3 Litre/hour, <u>Fuel tank capacity</u> : 66 litres → <u>Cooling system</u> : Water Cooled Including generator delivery, loading/unloading/lifting, installation charge, power cable (up to 50m), EarthLink and all necessary materials. | @ Tk. 8,45,000/- | 01 | Tk 8,45,000/- |
| Total (Taka Eight lac forty five thousand only) | | | | 8,45,000/- |

Terms and Conditions:

1. You will have to complete the supply, installation, testing and commissioning works of the generator sets at our Jhenaidah Branch, Jhenaidah within 07 (Seven) days from the date of issuance of work order.
2. Final bill must be submitted along with the clearance certificate from the respective branch manager of the bank.
3. Payment will be made after successful installation, testing & commissioning of Generator duly certified by the respective Branch Manager. An amount equivalent to 5% of the bill shall be deducted as security deposit & refunded after a period of 1 (one) year from the date of satisfactory installation subject to clearance from the branch.
4. INCOME TAX & VAT will be applicable for your bill as per existing Govt. rules.

5. **2 (two) years warranty** of the complete Generator set with accessories & spares from the date of successful installation & commissioning will have to be provided.
6. You will have to provide necessary manual, electrical layout (including MDB, supply source and outlet), operating instructions and necessary training.
7. If the supply, installation & commissioning is not completed within the stipulated time as fixed above, you will be liable for penalty @ Tk.1000/-(one thousand) only per day that shall be deducted from your bill.
8. **Servicing of the supplied equipments is to be provided free of cost at least 3 (three) times a year during the warranty period and as & when asked by the Bank authority. If the supplier fails to attend any servicing work during the warranty period, the works will be carried out by engaging separate contractor and the bill will be deducted from the security deposit of the supplier.**
9. The items supplied must meet the specifications in full. In case of any variation, the Bank authority reserves the right to reject the item(s) & material(s) completely or partially. AIBL authority also reserves the right to cancel or make any alteration of the work order at any time without showing any reason.
10. You will have to provide all electrical cables & other accessories as required at the time of installation and extra payment shall be made if the required power cable is above 50 meter.
11. All other terms and conditions of the quotation shall remain unchanged.

If the above terms and conditions are acceptable to you, please sign on the duplicate copy of this work order as token of your acceptance.

Ma-assalam.

Yours faithfully


(Engr. Md. Habib Ullah)
Senior Executive Vice President
