



CONCORD REAL ESTATE & BUILDING PRODUCTS LTD. (UNIT - I)

CONCORD CENTRE, 43, NORTH C/A, GULSHAN, DHAKA-1212

Date: 14-Jul-2021

Ref.: CRPL - I/2021/07/PO-000077

CROSS WORLD POWER LTD.

HOUSE-NE(O) 06, ROAD-92, GULSHAN-2, DHAKA-1212

Phone: 8811858,8816528

Fax: 8816205

Attn: MR. Paul

Account's Copy

Indent Ref. No.: 155047

Sub: Work Order for Supply, Installation, Testing and Commissioning of 250 KVA & 150 KVA Diesel Generator set at CONCORD FAHIL.

Dear Sir,

With reference to your Quotation the Management is placed an Order for supply us following materials at CONCORD FAHIL, Plot No. 15, Park Road, Baridhara. Requisition No.: RQ06-02 000787 dated on 23-Jun-2021 [155047] description given below :

SL	Item Name & Specification	Origin	Brand	Unit	VAT(%)	Tax(%)	Rate	Qty	Amount(GBP)
1	DIESEL GENERATOR 150 KVA [150 KVA Tempest (UK) Diesel Generator set: Model: PL150, Prime Power:150 KVA, Standby Power: 165 KVA, Engine: Perkins(UK), Type/Model: 1106A-70TAG2, Alternator: Leroy Somer (Czech), Model/Type: TAL 044 J, 50 Hz, Battery: 24V, Water cooled, Residential type Exhaust system, Control panel: DEEPSEA-UK (Price in GBP)]			set			14,000.00	1.00	14,000.00
2	DIESEL GENERATOR 250 KVA [250 KVA Tempest (UK) Diesel Generator set: Model: PL250#SYNC, Prime Power:250 KVA, Standby Power: 275 KVA, Engine: Perkins(UK), Type/Model: 1206A-E70TTAG3, Alternator: Leroy Somer (France), Model/Type: TAL 046 D, 50 Hz, Battery: 24V, Water cooled, Residential type Exhaust system, Control panel: DEEPSEA-UK (Price in GBP)]			SET			20,000.00	1.00	20,000.00
3	SYNCHRONIZING PANEL [Factory Made in built synchronizing panel]			NOS			0.00	1.00	0.00

Total Amount = 34,000.00
Carrying & Installation =
Discount (%) =
VAT =
Tax =
Total Payable Amount = 34,000.00

Work Order Amount In (GBP Thirty Four Thousand Only)

Terms & Conditions

- 01 Delivery Period:- Delivery will be made at our site by 08 - 10 weeks from the date of L/C. L/C will be done by Concord.
- 02 Payment Type:- 34,000 GBP will be paid by 100% irrevocable L/C by Concord in favor of Allam Marine Limited, Wyke Way, Melton, Hull, HU14 3BQ, England . Customs Duty, insurance, Bank charge, Transportation, Loading-Unloading etc. will directly pay to the concern authority at actual cost. Cross world Power Ltd. will bear L/C amendment, quarter charges or any other relevant fees/penalties if the production or shipment is been delayed by supplier.
- 03 Quality:- You have to maintain specified Brand/Grade Quality & Quantity. Concord reserves the right to reject the materials for below grade/quality. In that case you will take back the materials at your own cost from the Project Site.

15/07/21

15/07/21

15/07/21

- 04 Others:- Concord reserves the right to cancel or change or replace this Work Order any time without giving any reason
- 05 Warranty:- 12 Months warranty will be provided by CWPL from the date of commissioning.
- 06 Supplied Materials:- All materials are to be supplied according to the description/specifications enclosed in this work order & your quotation approved concerned Department of Concord Group. No discrepancy is acceptable without our prior agreement/consent in written. All materials will be inspected and approved by the EME department of the Concord Group.

Best regards,

15-07-21

MUHAMMAD ARSIL ISLAM
DEPUTY GENERAL MANAGER

15/7/21

Procurement Conducted By:

MD. MAHMUDUL HASAN
DEPUTY MANAGER

Copy To 1. ED (Project)
2. GM (A&F)

Work Order Accepted By

**CONCORD REAL ESTATE & BUILDING PRODUCTS LTD. (UNIT - I)**

CONCORD CENTRE, 43, NORTH C/A, GULSHAN, DHAKA-1212

Date: 14-Jul-2021

Ref.: CRPL - I/2021/07/PO-000075

CROSS WORLD POWER LTD.HOUSE-NE(O) 06, ROAD-92, GULSHAN-2,
DHAKA-1212

Phone: 8811858,8816528

Fax: 8816205

Attn: MR. Paul

Account's Copy

Indent Ref. No.: 155046

**Sub: Work Order for Supply, Installation, Testing and Commissioning of 250 KVA & 150 KVA Diesel
Generator's Local Materials at CONCORD FAHIL.**

Dear Sir,

With reference to your Quotation the Management is placed an Order for supply us following materials at CONCORD FAHIL, Plot No. 15, Park Road, Baridhara. Requisition No.: RQ06-02 000768 dated on 22-Jun-2021 [155046] description given below :

SL	Item Name & Specification	Origin	Brand	Unit	VAT(%)	Tax(%)	Rate	Qty	Amount(BDT)
1	SILENCER PIPE FITTING (6") [MS Pipe - 6", 3mm thickness, Insulation by rockwool/ glasswool & 26 SWG aluminum sheet]			RFT			1,998.00	100.00	199,800.00
2	Testing and commissioning [Control Cable, Cable Lugs, Insulation tape, PIB Tape, Line Tape, Cable Tie, Royal Bolt, Screw, Royal Plug, Lube Oil, Coolant, Distilled Water, Diesel: 400 L, Cable Laying: Generator to Sync. panel, ATS to EMDB (Excl. Power & Green cable)]			job			120,000.00	1.00	120,000.00
3	EARTHING WITH MATERIALS [Earthing 120' with copper wire 1x2 SWG, 1.5" dia GI pipe 120', Boring, Tape, Pit Excluded]			SET			35,500.00	4.00	142,000.00
4	EXHAUST DUCT [22 SWG GP Sheet with supporting, Angle, flat bar, canvas cloth etc]			SFT			280.00	600.00	168,000.00
5	CANOPY FOR 150 KVA GENERATOR [Cross World will comply 75-80 dB sound level at 3 meter distance (open space) by local made canopy.]			nos			175,000.00	1.00	175,000.00
6	CANOPY FOR 250 KVA GENERATOR [Cross World will comply 75-80 dB sound level at 3 meter distance (open space) by local made canopy.]			nos			220,000.00	1.00	220,000.00

Total Amount = 1,024,800.00

Carrying & Installation =

Discount (%) =

VAT =

Tax =

Total Payable Amount = 1,024,800.00

Work Order Amount In Word: (Taka Ten Lac Twenty Four Thousand Eight Hundred Only)

Terms & Conditions :


- Delivery Period:- Materials i.e. ATS, Canopy, Earthing, Ducting, Silencer Pipe etc. have to be delivered at our site within 15 days after delivery of Genset.
- Payment Type:- Payment will be made 70% advance with work order & rest 30% will be paid within 30 days after commissioning.
- Quality:- You have to maintain specified Brand/Grade Quality & Quantity. Concord reserves the right to reject the materials for below grade/quality. In that case you will take back the materials at your own cost from the Project Site
- Quantity:- Quantity may vary (increase/decrease). Hot Air Ducting work per sft rate is @Tk 280; Silencer pipe extension work per rft Rate is @Tk.1998. Above mentioned Quantity & Amount are an estimated cost, payment will be settled as per actual quantity required at the project which is certified by concerned Project In-Charge/Electrical Engineer.
- Tax:- Mushak -6.3 will provide by vendor & AIT will be deducted as per govt. rule.
- Others:- Concord reserves the right to cancel or change or replace this Work Order any time without giving any reason

- 07 Installation, Testing & Commissioning:- Installation, Testing & Commissioning has to be made at our site within 15 days after materials delivery. If fail to complete successful commissioning within specified time, delay penalty @ 0.1% per day up to 5% from the total payable amount will be charged.
- 08 Works Supervision & Training:- Total Work has to be done as per direction of our Senior Engineer (Electro Mechanical), All Specifications attached herewith the Work Order, Necessary Training for Operator & Mechanics will be provided by Cross World Power Ltd. at free of Cost.
- 09 Warranty:- 12 Months from the date of Commissioning

Best regards,


MUHAMMAD ARSIL ISLAM
DEPUTY GENERAL MANAGER

Copy To : 1. ED (Project)
2. GM (A&F)


Procurement Conducted By:
MD. MAHMUDUL HASAN
DEPUTY MANAGER


Work Order Accepted By