

## Shipan Barua

---

**To:** Md. Habibur Rahman Javed; Md. Abusieed Sobuj  
**Cc:** Ariful Islam; Harunor Rashid  
**Subject:** RE: WORK ORDER FOR INSTALLING 20 KVA GENERATOR\_NEW EBL SUB-BRANCH AT KOCHUKHET, DHAKA

---

**From:** Ariful Islam <[ariful@cross-world.com](mailto:ariful@cross-world.com)>  
**Sent:** Sunday, September 12, 2021 6:43:31 PM  
**To:** Md. Habibur Rahman Javed <[habib@cross-world.com](mailto:habib@cross-world.com)>; Shipan Barua <[shipan@cross-world.com](mailto:shipan@cross-world.com)>  
**Cc:** Harunor Rashid <[harunor@cross-world.com](mailto:harunor@cross-world.com)>; Md. Ziaul Islam <[zia@cross-world.com](mailto:zia@cross-world.com)>  
**Subject:** FW: WORK ORDER FOR INSTALLING 20 KVA GENERATOR\_NEW EBL SUB-BRANCH AT KOCHUKHET, DHAKA

Dear All ,  
Please find following mail from EBL & take the necessary action regarding local canopy, ATS & Installation materials .

Best Regards,

**Ariful Islam** | **CROSS WORLD POWER LTD** | **Manager , Sales** | | Plot 1/B, Road 90, Gulshan - 2, Dhaka 1212, Bangladesh | p: +880 2 5881 1858, 989 1442 | f: +880 2 5881 5160 | m: +8801755-514731, 01917-702 131 | e: [ariful@cross-world.com](mailto:ariful@cross-world.com) | w: [www.cross-world.com](http://www.cross-world.com)

 please consider the environment before printing this email

---

**From:** HO/Admin - Ohidul Islam [<mailto:ohidul.islam@ebl-bd.com>]  
**Sent:** Sunday, September 12, 2021 4:28 PM  
**To:** [ariful@cross-world.com](mailto:ariful@cross-world.com)  
**Cc:** HO/Admin - Rustom Ali; HO/Admin - B. M. SADMAN SAKIB; HO/Administration - Asraful Hoque Asif; HO/Admin - Kamal Mustaba Ali  
**Subject:** FW: WORK ORDER FOR INSTALLING 20 KVA GENERATOR\_NEW EBL SUB-BRANCH AT KOCHUKHET, DHAKA  
**Importance:** High

Dear Mr. Ariful Islam  
Manager, Sales  
[Cross World Power Ltd.](http://Cross World Power Ltd.)

In reference to below mail, the price of installing the Generator in the following premises has been fixed as:

1. For Nabisco Sub-branch, Tejgaon, Dhaka-Tk. 277,654.00
2. For Kochukhet Sub-branch, Dhaka-Tk. 227,266.00

The price mentioned above has been fixed after negotiation with you over phone.

Thanking you,

**Md. Ohidul Islam**  
**AVP & Senior Manager**  
Administration Department | Eastern Bank Ltd, Head Office |  
100 Gulshan Avenue, Dhaka-1212 | Mobile: 01892575737 |  
Tel: 09666777325, Ext-7764 |

 **Eastern Bank Ltd.**   

**From:** Md. Ariful Islam [<mailto:ariful@cross-world.com>]

**Sent:** Thursday, September 09, 2021 12:41 PM

**To:** HO/Admin - Ohidul Islam

**Cc:** HO/Admin - Rustom Ali; HO/Admin - B. M. SADMAN SAKIB; HO/Administration - Asraful Hoque Asif; HO/Admin - Kamal Mustaba Ali

**Subject:** RE: WORK ORDER FOR INSTALLING 20 KVA GENERATOR\_NEW EBL SUB-BRANCH AT KOCHUKHET, DHAKA  
**Importance:** High

Dear Sir ,

Thanks for your work order . After receiving work order , we have already visited the Tejgaon & Kochukhet Sub Branch . Please find attached financial proposal of Canopy , ATS & Installation materials of Genset for Tejgaon & Kochukhet Sub Branch of EBL . After your confirmation , we will start fabrication work of Canopy & Installation of Genset . If you have any query regarding this please feel free to contact with us .

Best Regards,

**Ariful Islam** | **CROSS WORLD POWER LTD** | **Manager , Sales** | | Plot 1/B, Road 90, Gulshan - 2, Dhaka 1212, Bangladesh | p: +880 2 5881 1858, 989 1442 | f: +880 2 5881 5160 | m: +8801755-514731, 01917-702 131 | e: [ariful@cross-world.com](mailto:ariful@cross-world.com) | w: [www.cross-world.com](http://www.cross-world.com)

 please consider the environment before printing this email

**From:** HO/Admin - Ohidul Islam [<mailto:ohidul.islam@ebl-bd.com>]

**Sent:** Tuesday, August 31, 2021 4:05 PM

**To:** [ariful@cross-world.com](mailto:ariful@cross-world.com)

**Cc:** HO/Admin - Rustom Ali; HO/Admin - B. M. SADMAN SAKIB; HO/Administration - Asraful Hoque Asif; HO/Admin - Kamal Mustaba Ali

**Subject:** WORK ORDER FOR INSTALLING 20 KVA GENERATOR\_NEW EBL SUB-BRANCH AT KOCHUKHET, DHAKA

Dear Concern

Cross World Ltd.

The Management of EBL is pleased to award the work for supplying & installing of a **20KVA Generator** at the site mentioned below with following particulars:

Location	Product Name	Capacity	Brand	Origin	Assemble	Price (In Tk.)
<b>Kochukhet Sub-branch</b> <u>Address:</u> Kochukhet, Dhaka.	Generator	20 KVA	Tempest/Bideford	UK	UK	6,90,000.00

**In Word: Taka Six Lac Ninety Thousand Only.**

**Terms & Conditions:**

1. The quoted price is inclusive of VAT & Tax.
2. The price of ATS & Canopy is not included with the quoted price and the cost of these will be borne by the bank at actual.
3. The costs of installation & commissioning materials are to be borne by the bank at actual.
4. The price is exclusive of fuel/diesel initially needed to make the generator functional.
5. The above work order has been awarded to you on the basis of your quotation and no deviation thereof will be accepted by the bank.
6. **Date of Delivery: By September 30, 2021. You are requested to keep the Generator (20KVA) available at your premises so that you can supply the item as soon as instruction is given from EBL for the delivery.**
7. An amount of Tk. 2,000.00 (Taka Two Thousand Only) will be deducted for each day of delay in delivery.
8. An amount of 10% of the total bill shall be retained as 'Security Deposit' for a period of minimum 06 (six) months from the date of commissioning of the generator.

**Eastern Bank Limited**  
100, Gulshan Avenue, Dhaka-1212.

Project: Eastern Bank Limited, Tejgaon Sub-Branch

**OFFER FOR SUPPLY OF LOCAL CANOPY, ATS WITH COMMISSIONING MATERIALS FOR 20 KVA 3 PHASE HEAVY DUTY DIESEL GENERATING SETS.**

SL NO	JOB DESCRIPTION	TECHNICAL DETAILS/ BRAND	UOM	QTY	UNIT RATE	TOTAL RATE	REMARKS
1	Local Canopy for 20 KVA Genset	75 dBA @ 3 meter	Nos	1	100,000	100,000	
2	Local Auto Transfer Switch (ATS) for 20 KVA Genset	ABB or Equivalent	Nos	1	25,000	25,000	
3.1	Power Cable (35 °C Ambient on air )	4CX10 rm NYY DG To ATS 4CX 10 rm NYY MAINS To ATS 4CX 10 rm NYY ATS to LOAD	Meter	47 7 7	827 827 827	38,812 5,797 5,797	Depend on cable laying route
3.2	Cable Lugs	10 rm , <b>Material</b> -Copper , <b>Surface</b> -Electro Tinned	Pcs	26	9	236	
3.3	Control Cable for Sensing	4 X 1.2 rm (40/0.19 mm) Flexible Cable (2XDG to ATS)	Meter Approx.	73	113	8,293	
3.4	PVC Flexible Pipe	1.5" dia	Meter	61	44	2,695	
3.5	Saddle for flexible pipe	1.5" dia local	Pcs	60	6	340	
3.6	Royal Plug & Screw	1.5" length	Pack	5	194	969	
3.7	PVC Tape	Adhesive Tape 04 color (Red/Yellow/Black/Blue)	Pcs	8	33	263	
3.8	PIB Tape		Pcs	N/A	-	-	
3.9	Royal Bolt	10 no.	Pcs	10	20	204	
3.1	Cable Tie	L - 8"	Pack	3	156	469	
3.12	Power Cable Laying & Connection	4CX10 rm NYY Cable	Meter	61	60	3,663	
4	<b>Generator Earthing :</b>				-	-	
4.1	Earthing Boring	100 rft	Job	1	8,202	8,202	
4.2	Earthing Copper Lead (Boring)	4 SWG	Meter	34	297	9,958	
4.3	PVC Flexible Pipe	3/4" dia	Meter	3	25	75	
4.4	Saddle for flexible pipe	3/4" dia local	Pcs	3	3	10	
4.5	GI Pipe	38m dia	Meter	7	547	3,832	
4.6	Earthing Block	Dimension LXWXD - 200mm X 30mm X 4mm with connection facility	Pc	1	2,237	2,237	
4.7	Earthing Cable	1 X 10 rm BYA (Green ) Earthing block to gen & equipment	Meter	10	161	1,615	
4.8	Earthing Cable lugs	10 rm <b>Material</b> -Copper , <b>Surface</b> -Electro Tinned	Pcs	5	9	45	
5	<b>Exhaust System:</b>				-	-	
5.1	Exhaust Silencer straight Pipe	MS Pipe bore 3", thickness 3mm	Meter	11	1,956	20,873	
5.2	Exhaust Bends /Elbow	Long radius 90 deg L bow 3"	Pcs	1	821	821	
5.3	Exhaust Heat Insulation	Insulation Of Pipe with Rockwool (50mm thickness) along with 26SWG Aluminium sheet cladding.	Job	1	7,756	7,756	
5.4	Exhaust Fitting	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM	Job	1	5,970	5,970	
6	<b>Cooling System:</b>				-	-	
6.1	Radiator Ducting	As per layout with 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth etc WXH=2'X1', L- 15ft (Approx)	Sq-ft	90	297	26,724	Top exit
7	<b>Commissioning Material:</b>				-	-	
7.1	Radiator coolant	Havoline Premix Coolant	Liter	10	170	1,700	
7.2	Lube oil	SAE 15 W 40	Liter	10	430	4,300	
7.3	Battery electrolyte	Specific gravity 1250	Liter	10	100	1,000	
8	<b>CIVIL WORK (EBL Scope)</b>	<b>EBL Scope</b>					
8.1	DG Base for 20kVA DG	Base dimension LXW(ft)=8'x4.3', Depth, D- 2" CC with NCF.	Job	1			
<b>TOTAL TK (Including VAT &amp; AIT)</b>						<b>287,654</b>	

Note: Related Civil work and Diesel Fuel for Test Run will be arranged by Client as per instruction of CWPL Engineer.

Sincerely,



**Md. Ariful Islam**  
Manager, Sales & Marketing  
Mobile : 01755 514 731