


Purchase Order

Name and address of Supplier	Cross-world	PO No:	2021/September/Procurement Dept./006
		PO Date:	02.09.2021
	Plot 1/B, Road 90, Gulshan - 2, Dhaka 1212, Bangladesh	Customer Name & Delivery Location	IPDC Finance Limited Hosna Centre (4 <sup>th</sup> Floor) 106, Gulshan Avenue Dhaka-1212, Bangladesh


Price Details		
Total Price (Including Canopy & ATS)	:	1,207,000.00
Commissioning Material cost	:	168,000.00
Total Cost	:	1,375,000.00
Less: Special Discount	:	98,500.00
Total cost after discount	:	1,276,500.00
VAT (7.5%)	:	95,737.50
Grand Total (Including VAT & AIT)	:	1,372,237.50
Technical Specification		
Brand	:	Tempest & Perkins, Uk
Model	:	PS45 & 1103A-33TGI
Country of Origin	:	UK
Capacity	:	49.5 KVA (Stand by), 45 KVA (Prime)
Speed	:	1500 RPM
Fuel Tank Capacity	:	130 Liter
Fuel Consumption	:	8.20 Ltr. /Hr. at 75% Load
Service Warranty	:	1500 hours or 1 year whichever comes first effective from the date of commissioning without consumable items



সেরা আর্থিক প্রতিষ্ঠান



General Terms & Conditions	Special Terms & Conditions
<ul style="list-style-type: none"><li>Amount including applicable Tax, VAT, and other government levies. Which will be deducted from final bill.</li><li>Amount including Delivery, Installation and commissioning charge</li><li>The validity of the PO will be for 1 month.</li><li><b>30 % amount will be paid as advance, 70% of the payment will be made after delivery.</b></li><li>Payment will be made within 14 working days after submission of complete bill, challan and mushak copy.</li><li>Delivery, Installation and commissioning should be completed within 12<sup>th</sup> September, 2021.</li><li>This price offer is considered confidential and should not be divulged to third party directly or indirectly.</li><li>IPDC Finance preserves the right to change, modify and cancel this PO.</li></ul>	<ul style="list-style-type: none"><li>Product must be in compliance with provided quotation.</li><li>In case of any default or damaged product, supplier must replace the product at their own cost. Moreover, 10% amount will be deducted from the final bill.</li></ul>

IPDC Representative	Vendor Representative
 Bushra Ishrat Procurement & Payment Processing Executive	

CROSS WORLD POWER LIMITED						
BOQ OF 45 KVA GENERATOR						
CLIENT - IPDC Finance Limited			ADDRESS- Jashore			
GEN MODEL- PS45		ENGINE MODEL-		ALTERNATOR MODEL-		
ELECTRICAL INSTALLATIONS						
SL NO	JOB DESCRIPTION	TECHNICAL DETAILS/ BRAND	SCOPE OF SUPPLY	UOM	QTY	REMARKS
1	Electrical System:					
1.1	Power Cable (35 °C Ambient on air )	4C-16 rm NYY DG To ATS		Meter	55	
1.2		4C-16 rm NYY Mains To ATS		Meter	3	
1.3		4C-16 rm NYY ATS to Load		Meter	5	
	Breaker	63 A TP MCCB		Nos	1	
1.4	Power Cable Laying	4C-16rm		Meter	63	
1.5	Power Cable Lugs	10 rm , Material -Copper , Surface-Electro Tinned		Pcs	26	
1.6	Control cable For Sensing	4 X 1.2 rm (40/0.19 mm)Flexible Cable		Meter	113	
1.7	PVC Flexible pipe	3"Ø		Meter	25	
1.8	Saddle for Flexible pipe	3" Ø Local		Pcs	30	
1.9	Royal Plug & Screw	1.5" length		Pack	3	
1.10	PVC Tape	Adhesive Tape 04 color (Red/Yellow/Black/Blue)		Pcs	4	
1.11	Royal Bolt	10 no.		Pcs	10	
1.12	Cable Tie	L - 6"/8 "		Pack	3	
2	Generator Earthing :					
2.1	Earthing Boring	1 Nos, 100 feet boring		Job	1	
	GI Pipe (Boring)	38.1mm Dia		Meter	7	
2.2	Earthing Copper Lead (Boring)	4 SWG		Meter	32	
	Earthing Copper Lead (Termination)	4 SWG		feet	3	
2.3	Earthing Block	LXWXD - 200mm X 30mm X 5mm with connection facility, isolator, royal bolt etc		Pc	1	
2.4	Earthing Cable	1 X 10 rm BYA (Green ) from Earthing Copper bar to gen & equipment		Meter	12	
2.5	Earthing Cable Lugs	10 rm , Material -Copper , Surface-Electro Tinned		Pcs	4	
3	Exhaust System:					
3.1	Exhaust Silencer straight Pipe	MS Pipe bore 3" ,thickness 3-4mm		Meter	4	
3.2	Exhaust Bends /Elbow	Long radius 90 deg L bow		Pcs	1	
3.3	Exhaust Flange	Threaded 3"dia MS Flange		Pcs	2	
	Reducer	2"-3"		Nos	1	
3.4	Exhaust Heat Insulation	Insulation Of Pipe with Rockwool/Glasswool (25.4mm min thickness) along with 26SWG Aluminium sheet cladding		Job	1	
3.5	Exhasut Fitting	All bracket , support must be made with MS angle 50X50X 4, 5 & 6 MM		Job	1	
04	Cooling System:					
4.1	Radiator Ducting	WXH - , L - As per layout with 22 SWG MS sheet,Angle bar, flat bar support,Canvas cloth etc		Sq-ft	35	Hot air exit top of the canopy
5	Commissioning Material:					
5.1	Radiator coolant	Havoline Premix Coolent		Liter	10	
5.3	Lube oil	SAE 15 W 40		Liter	10	
5.4	Battery electrolyte	Specific gravity 1250		Liter	10	
06	DG On site delivery:					
6.1	Loading /Unloading/Lifting	Generator weight-954 Kg with Comm. Materials	CWPL	Job	1	
07	Civil works:					
7.1	Generator foundation	Dimension L X W -7'-6" "X5'-6"Depth D: 2"	CLIENT	Job	N/A	

Note: All Types of Civil work will be done by client.

Note: All Types of Civil work will be done by client.